



**CONTRACTS AND SPECIFICATIONS BUREAU
Proposal**

Proposal ID: 47-C047-064

Letting Date: August 18, 2026

Call Order: 005

Proposal Work Type: BRIDGE REPLACEMENT - CCS

DBE Goal: 0.0%

Contracting Authority: IDA COUNTY

Proposal Guaranty: \$50,000.00

This proposal includes the following project(s):

Project Number: BRS-C047(64)--60-47

County: IDA

Project Work Type: BRIDGE REPLACEMENT - CCS

Route: D15

Location: On D 15, Over UNNAMED CREEK, from Ida/Sac W .04 miles to Bridge S25 T89 R39

Road System: FARM TO MARKET ROAD

Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

Contract Time

Proposal ID: 47-C047-064

Call Order: 005

Letting Date: August 18, 2026

Site ID	Site Details			Liquidated Damages
00	Late Start Date	06/21/2027	80 WORK DAYS	\$1,000.00

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

Notes

Proposal ID: 47-C047-064

Call Order: 005

Letting Date: August 18, 2026

Notes :

There are no notes for this proposal.

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 47-C047-064

Call Order: 005

Letting Date: August 18, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.
410.11	*** STORM WATER POLLUTION PREVENTION PLAN *** A Storm Water Pollution Prevention Plan has been developed by the Contracting Authority for one or more projects on this contract. See the project plans (or other contract document) for specific Storm Water Pollution Prevention Plan details.
500.01	*** WINTER WORK *** The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.
FHWA-1273.09	FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023 23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.
GS-23006	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 47-C047-064

Call Order: 005

Letting Date: August 18, 2026

Note	Description
IA26-28.4	PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20260028 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY) Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract. *** Additional Requirement *** The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 47-C047-064

Call Order: 005

Letting Date: August 18, 2026

SECTION: 0001

ITEMS FOR A 110'-0 X 30'-6 CONTINUOUS CONCRETE SLAB BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	400.000 CY				
0020	2102-2710090 EXCAVATION, CLASS 10, WASTE	728.000 CY				
0030	2104-2710020 EXCAVATION, CLASS 10, CHANNEL	1,700.000 CY				
0040	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	750.000 CY				
0050	2121-7425020 GRANULAR SHOULDERS, TYPE B	115.000 TON				
0060	2123-7450000 SHOULDER CONSTRUCTION, EARTH	5.000 STA				
0070	2301-0690210 BRIDGE APPROACH, TWO LANE	433.600 SY				
0080	2401-6745625 REMOVAL OF EXISTING BRIDGE	LUMP SUM	LUMP SUM			
0090	2402-2720000 EXCAVATION, CLASS 20	120.000 CY				
0100	2403-0100010 STRUCTURAL CONCRETE (BRIDGE)	255.100 CY				
0110	2404-7775005 REINFORCING STEEL, EPOXY COATED	66,056.000 LB				
0120	2414-6424124 CONCRETE OPEN RAILING, TL-4	242.000 LF				



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 47-C047-064

Call Order: 005

Letting Date: August 18, 2026

SECTION: 0001

ITEMS FOR A 110'-0 X 30'-6 CONTINUOUS CONCRETE SLAB BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	2501-0201042 PILES, STEEL, HP 10 X 42	1,950.000 LF				
0140	2501-5478042 CONCRETE ENCASEMENT OF STEEL H PILES, HP 10 X 42 (P10L TYPE 3)	380.000 LF				
0150	2502-8221305 SUBDRAIN OUTLET, DR-305	1.000 EACH				
0160	2505-4008120 REMOVAL OF STEEL BEAM GUARDRAIL	282.000 LF				
0170	2505-4008410 STEEL BEAM GUARDRAIL BARRIER TRANSITION SECTION, BA-201	4.000 EACH				
0180	2505-4021010 STEEL BEAM GUARDRAIL END ANCHOR, BOLTED	4.000 EACH				
0190	2505-4021710 STEEL BEAM GUARDRAIL TANGENT END TERMINAL, LS-625	4.000 EACH				
0200	2507-3250005 ENGINEERING FABRIC	900.000 SY				
0210	2507-6800061 REVETMENT, CLASS E	625.000 TON				
0220	2507-6875002 REVETMENT, REMOVE AND REPLACE	50.000 CY				
0230	2510-6745850 REMOVAL OF PAVEMENT	508.000 SY				
0240	2526-8285020 CONSTRUCTION SURVEY, CONTROL POINT SURVEY	LUMP SUM	LUMP SUM			



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 47-C047-064

Call Order: 005

Letting Date: August 18, 2026

SECTION: 0001

ITEMS FOR A 110'-0 X 30'-6 CONTINUOUS CONCRETE SLAB BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM			
0260	2527-9263209 PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	3.790 STA				
0270	2528-2518000 SAFETY CLOSURE	2.000 EACH				
0280	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
0290	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
0300	2601-2634100 MULCHING	1.800 ACRE				
0310	2601-2636043 SEEDING AND FERTILIZING (RURAL)	0.900 ACRE				
0320	2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING	0.900 ACRE				
0330	2602-0000020 SILT FENCE	675.000 LF				
0340	2602-0000030 SILT FENCE FOR DITCH CHECKS	176.000 LF				
0350	2602-0000101 MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	851.000 LF				
0360	2602-0000312 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	420.000 LF				



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 47-C047-064

Call Order: 005

Letting Date: August 18, 2026

SECTION: 0001

ITEMS FOR A 110'-0 X 30'-6 CONTINUOUS CONCRETE SLAB BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0370	2602-0010010 MOBILIZATIONS, EROSION CONTROL	1.000 EACH		600.00000		600.00
0380	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	1.000 EACH		1,200.00000		1,200.00

Section: 0001

Total: _____.

Total Bid: _____.