



CONTRACTS AND SPECIFICATIONS BUREAU Proposal

Proposal ID: 57-4775-646

Letting Date: August 18, 2026

Call Order: 007

Proposal Work Type: BRIDGE NEW - PPCB

DBE Goal: 0.0%

Contracting Authority: CITY OF MARION

Proposal Guaranty: \$750,000.00

This proposal includes the following project(s):

Project Number: HDP-4775(646)--71-57

County: LINN

Project Work Type: BRIDGE NEW - PPCB

Route: ALBURNETT ROAD

Location: In the city of Marion, Alburnett Road Extension

Road System: URBAN

Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

Contract Time

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

Site ID	Site Details	Liquidated Damages
00	9/15/2028 COMPLETION DATE Overall Site.	\$2,000.00
01	11/5/2027 COMPLETION DATE Stg 1-5 and Stg 10-14. See description below.	\$2,000.00

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit



Contracts and Specifications Bureau

7/14/2026 10:05 AM

Notes

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

Notes :

Site 01

All roadways, bridges, driveways, sidewalks, and Indian Creek Trail paving complete within the limits of stage 1 through stage 5 and stage 10 through stage 14 and open to traffic.

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.
410.11	*** STORM WATER POLLUTION PREVENTION PLAN *** A Storm Water Pollution Prevention Plan has been developed by the Contracting Authority for one or more projects on this contract. See the project plans (or other contract document) for specific Storm Water Pollution Prevention Plan details.
500.01	*** WINTER WORK *** The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.
660.26	*** SPECIALTY ITEM *** The item 'TRAFFIC SIGNALIZATION' and/or 'TRAFFIC SIGNAL INSTALLATION' is considered a specialty item for this project. When performed by subcontract, the cost of the specialty item/s so performed by subcontract may be deducted from the total cost before computing the amount of work required to be performed by the Prime Contractor with his/her own organization. Refer to Article 1108.01 of the Standard Specifications.
DS-23011	DEVELOPMENTAL SPECIFICATIONS FOR FLOATING SILT CURTAIN
DS-23015	DEVELOPMENTAL SPECIFICATIONS FOR STRUCTURAL CONCRETE COATING
DS-23082	DEVELOPMENTAL SPECIFICATIONS FOR HIGH PERFORMANCE CONCRETE FOR STRUCTURES

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

Note	Description
DS-23083	DEVELOPMENTAL SPECIFICATIONS FOR FIBER REINFORCEMENT FOR STRUCTURAL CONCRETE
FHWA-1273.09	FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023 23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.
GS-23006	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION
IA26-28.4	PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20260028 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY) Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract. *** Additional Requirement *** The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.
SP-236072	SPECIAL PROVISIONS FOR WATER MAIN Linn County HDP-4775(646)--71-57
SP-236075	SPECIAL PROVISIONS FOR ANTI-GRAFFITI COATING Linn County HDP-4775(646)--71-57



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

Note	Description
SP-236084	SPECIAL PROVISIONS FOR RECTANGULAR RAPID FLASHING BEACON SYSTEM Linn County HDP-4775(646)--71-57



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

SECTION: 0001

Items for a 201'-4 x 38'-0 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2101-0850001 CLEARING AND GRUBBING	2.400 ACRE				
0020	2101-0850002 CLEARING AND GRUBBING	783.700 UNIT				
0030	2102-2625001 EMBANKMENT-IN-PLACE, CONTRACTOR FURNISHED	41,433.000 CY				
0040	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	13,645.000 CY				
0050	2102-2710080 EXCAVATION, CLASS 10, UNSUITABLE OR UNSTABLE MATERIAL	816.000 CY				
0060	2102-2710090 EXCAVATION, CLASS 10, WASTE	1,626.000 CY				
0070	2102-2712015 EXCAVATION, CLASS 12, BOULDERS OR ROCK FRAGMENTS	136.000 CY				
0080	2102-2713090 EXCAVATION, CLASS 13, WASTE	50.000 CY				
0090	2104-2710020 EXCAVATION, CLASS 10, CHANNEL	3,954.000 CY				
0100	2105-8425005 TOPSOIL, FURNISH AND SPREAD	5,975.000 CY				
0110	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	3,077.000 CY				
0120	2107-0875000 COMPACTION WITH MOISTURE AND DENSITY CONTROL	41,433.000 CY				



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

SECTION: 0001

Items for a 201'-4 x 38'-0 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	2109-8225100 SPECIAL COMPACTION OF SUBGRADE	36.700 STA				
0140	2113-0001000 SUBGRADE STABILIZATION MATERIAL, MODIFIED SUBBASE	2,448.000 SY				
0150	2113-0001100 SUBGRADE STABILIZATION MATERIAL, POLYMER GRID	23,658.700 SY				
0160	2115-0100000 MODIFIED SUBBASE	8,208.900 CY				
0170	2121-7425010 GRANULAR SHOULDERS, TYPE A	14.020 TON				
0180	2123-7450020 SHOULDER FINISHING, EARTH	94.000 STA				
0190	2213-7100400 RELOCATION OF MAIL BOXES	3.000 EACH				
0200	2301-0690201 BRIDGE APPROACH, BR-201	342.300 SY				
0210	2301-0690203 BRIDGE APPROACH, BR-203	963.700 SY				
0220	2301-1033070 STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 7 IN.	1,135.000 SY				
0230	2301-1033080 STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 8 IN.	14,649.600 SY				



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

SECTION: 0001

Items for a 201'-4 x 38'-0 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	2301-1033090 STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 9 IN.	5,166.000 SY				
0250	2301-4874500 MEDIAN, P.C. CONCRETE, AS PER PLAN	221.700 SY				
0260	2301-4875006 MEDIAN, P.C. CONCRETE, 6 IN.	274.900 SY				
0270	2301-6911722 PORTLAND CEMENT CONCRETE PAVEMENT SAMPLES	LUMP SUM	LUMP SUM			
0280	2301-7000110 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR PCC PAVEMENT THICKNESS (BY SCHEDULE)	25,640.000 EACH		1.00000	25,640.00	
0290	2304-0101000 TEMPORARY PAVEMENT	530.000 SY				
0300	2315-8275025 SURFACING, DRIVEWAY, CLASS A CRUSHED STONE	59.300 TON				
0310	2315-8275025 SURFACING, DRIVEWAY, CLASS A CRUSHED STONE TEMPORARY	180.000 TON				
0320	2401-6745910 REMOVAL OF SIGN	21.000 EACH				
0330	2401-6750001 REMOVALS, AS PER PLAN	LUMP SUM	LUMP SUM			



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

SECTION: 0001

Items for a 201'-4 x 38'-0 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0340	2402-0425031 GRANULAR BACKFILL	499.000 TON				
0350	2402-2720000 EXCAVATION, CLASS 20	581.000 CY				
0360	2402-2721000 EXCAVATION, CLASS 21	278.000 CY				
0370	2403-0100000 STRUCTURAL CONCRETE (MISCELLANEOUS)	8.600 CY				
0380	2403-0100010 STRUCTURAL CONCRETE (BRIDGE)	539.600 CY				
0390	2403-1000005 FIBER REINFORCEMENT FOR STRUCTURAL CONCRETE	436.100 CY				
0400	2403-1000010 TRIAL BATCH AND TEST PLACEMENT (FIBER REINFORCED CONCRETE)	LUMP SUM	LUMP SUM			
0410	2403-7000210 HIGH PERFORMANCE STRUCTURAL CONCRETE	460.100 CY				
0420	2403-7303000 STRUCTURAL CONCRETE COATING	253.700 SY				
0430	2404-7775000 REINFORCING STEEL	85,654.000 LB				
0440	2404-7775005 REINFORCING STEEL, EPOXY COATED	149,924.000 LB				
0450	2404-7775009 REINFORCING STEEL, STAINLESS STEEL	3,658.000 LB				



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

SECTION: 0001

Items for a 201'-4 x 38'-0 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0460	2407-0551363 BEAMS, PRETENSIONED PRESTRESSED CONCRETE, C63	18.000 EACH				
0470	2407-0551371 BEAMS, PRETENSIONED PRESTRESSED CONCRETE, C71	9.000 EACH				
0480	2408-7800000 STRUCTURAL STEEL	10,136.000 LB				
0490	2412-0000100 LONGITUDINAL GROOVING IN CONCRETE, BRIDGE DECK AND/OR APPROACHES	863.000 SY				
0500	2414-6425410 CONCRETE BARRIER, REINFORCED, SEPARATION	529.400 LF				
0510	2414-6444100 STEEL PIPE PEDESTRIAN HAND RAILING	467.400 LF				
0520	2414-6460000 ORNAMENTAL METAL RAILING	454.200 LF				
0530	2416-0100015 APRONS, CONCRETE, 15 IN. DIA.	2.000 EACH				
0540	2416-0100018 APRONS, CONCRETE, 18 IN. DIA.	4.000 EACH				
0550	2416-0100024 APRONS, CONCRETE, 24 IN. DIA.	2.000 EACH				
0560	2416-0100030 APRONS, CONCRETE, 30 IN. DIA.	1.000 EACH				
0570	2416-0100048 APRONS, CONCRETE, 48 IN. DIA.	1.000 EACH				



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

SECTION: 0001

Items for a 201'-4 x 38'-0 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0580	2416-1160018 CULVERT, CONCRETE ENTRANCE PIPE, 18 IN. DIA.	88.000 LF				
0590	2431-0000100 SEGMENTAL BLOCK RETAINING WALL	1,993.200 SF				
0600	2433-0001042 CONCRETE DRILLED SHAFT, 42 IN. DIAMETER	382.000 LF				
0610	2433-0003000 DEMONSTRATION SHAFT	20.000 LF				
0620	2435-0130148 MANHOLE, SANITARY SEWER, SW- 301, 48 IN.	6.000 EACH				
0630	2435-0140148 MANHOLE, STORM SEWER, SW-401, 48 IN.	5.000 EACH				
0640	2435-0140196 MANHOLE, STORM SEWER, SW-401, 96 IN.	2.000 EACH				
0650	2435-0250100 INTAKE, SW-501	1.000 EACH				
0660	2435-0250284 INTAKE, SW-502, 84 IN.	6.000 EACH				
0670	2435-0250500 INTAKE, SW-505	3.000 EACH				
0680	2435-0250700 INTAKE, SW-507	4.000 EACH				
0690	2435-0250900 INTAKE, SW-509	22.000 EACH				



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

SECTION: 0001

Items for a 201'-4 x 38'-0 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0700	2435-0251000 INTAKE, SW-510	3.000 EACH				
0710	2435-0251110 INTAKE, SW-511 MODIFIED	1.000 EACH				
0720	2435-0251224 INTAKE, SW-512, 24 IN.	1.000 EACH				
0730	2435-0254100 INTAKE, SW-541	1.000 EACH				
0740	2435-0400308 INTERNAL DROP CONNECTION, SW-308	1.000 EACH				
0750	2435-0600010 MANHOLE ADJUSTMENT, MINOR	5.000 EACH				
0760	2435-0600020 MANHOLE ADJUSTMENT, MAJOR	1.000 EACH				
0770	2435-0700020 CONNECTION TO EXISTING INTAKE	1.000 EACH				
0780	2502-6745952 REMOVAL OF SUBDRAIN	498.500 LF				
0790	2502-8212036 SUBDRAIN, LONGITUDINAL, (SHOULDER) 6 IN. DIA.	6,170.600 LF				
0800	2502-8213104 SUBDRAIN, PVC, STANDARD, NON- PERFORATED, 4 IN.	47.400 LF				
0810	2502-8213106 SUBDRAIN, PVC, STANDARD, NON- PERFORATED, 6 IN.	8.500 LF				



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

SECTION: 0001

Items for a 201'-4 x 38'-0 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0820	2502-8221303 SUBDRAIN OUTLET, DR-303	40.000 EACH				
0830	2502-8221305 SUBDRAIN OUTLET, DR-305	1.000 EACH				
0840	2503-0114215 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 15 IN.	2,032.000 LF				
0850	2503-0114218 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 18 IN.	315.000 LF				
0860	2503-0114224 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 24 IN.	624.000 LF				
0870	2503-0114230 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 30 IN.	198.000 LF				
0880	2503-0114236 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 36 IN.	42.000 LF				
0890	2503-0114248 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 48 IN.	819.000 LF				



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

SECTION: 0001

Items for a 201'-4 x 38'-0 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0900	2503-0200036 REMOVE STORM SEWER PIPE LESS THAN OR EQUAL TO 36 IN.	1,691.000 LF	_____	_____	_____	_____
0910	2503-0200136 REMOVE STORM SEWER PIPE GREATER THAN 36 IN.	152.900 LF	_____	_____	_____	_____
0920	2504-0114008 SANITARY SEWER GRAVITY MAIN, TRENCHED, POLYVINYL CHLORIDE PIPE (PVC), 8 IN.	923.900 LF	_____	_____	_____	_____
0930	2504-0114015 SANITARY SEWER GRAVITY MAIN, TRENCHED, POLYVINYL CHLORIDE PIPE (PVC), 15 IN.	413.400 LF	_____	_____	_____	_____
0940	2504-0200404 SANITARY SEWER SERVICE STUB, POLYVINYL CHLORIDE PIPE (PVC), 4 IN.	221.200 LF	_____	_____	_____	_____
0950	2504-0200406 SANITARY SEWER SERVICE STUB, POLYVINYL CHLORIDE PIPE (PVC), 6 IN.	271.100 LF	_____	_____	_____	_____
0960	2504-0240036 REMOVE SANITARY SEWER PIPE LESS THAN OR EQUAL TO 36 IN.	1,595.200 LF	_____	_____	_____	_____
0970	2504-0240145 SANITARY SEWER CLEANOUT	3.000 EACH	_____	_____	_____	_____
0980	2507-2638650 BRIDGE WING ARMORING - EROSION STONE	12.600 SY	_____	_____	_____	_____
0990	2507-3250005 ENGINEERING FABRIC	5,884.400 SY	_____	_____	_____	_____



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

SECTION: 0001

Items for a 201'-4 x 38'-0 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1000	2507-6800061 REVTMENT, CLASS E	6,441.600 TON				
1010	2510-6745850 REMOVAL OF PAVEMENT	13,155.800 SY				
1020	2510-6750600 REMOVAL OF INTAKES AND UTILITY ACCESSES	28.000 EACH				
1030	2511-0302600 RECREATIONAL TRAIL, PORTLAND CEMENT CONCRETE, 6 IN.	2,442.500 SY				
1040	2511-0310100 SPECIAL COMPACTION OF SUBGRADE FOR RECREATIONAL TRAIL	10.450 STA				
1050	2511-6745900 REMOVAL OF SIDEWALK	1,297.400 SY				
1060	2511-7526004 SIDEWALK, P.C. CONCRETE, 4 IN.	1,045.700 SY				
1070	2511-7526006 SIDEWALK, P.C. CONCRETE, 6 IN.	3,568.300 SY				
1080	2511-7526006 SIDEWALK, P.C. CONCRETE, 6 IN. STAMPED	76.200 SY				
1090	2511-7528101 DETECTABLE WARNINGS	460.300 SF				
1100	2515-2475006 DRIVEWAY, P.C. CONCRETE, 6 IN.	1,854.100 SY				
1110	2515-2475007 DRIVEWAY, P.C. CONCRETE, 7 IN.	1,254.100 SY				



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

SECTION: 0001

Items for a 201'-4 x 38'-0 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1120	2515-6745600 REMOVAL OF PAVED DRIVEWAY	2,333.600 SY				
1130	2516-8725065 SPECIAL RETAINING WALL, AS PER PLAN	47.200 SF				
1140	2519-1002048 FENCE, CHAIN LINK, 48 IN. HEIGHT	154.000 LF				
1150	2519-3300600 FENCE, SAFETY	2,780.000 LF				
1160	2519-4200020 REMOVAL AND REINSTALLATION OF FENCE, CHAIN LINK	208.400 LF				
1170	2519-4200120 REMOVAL OF FENCE, CHAIN LINK	132.000 LF				
1180	2520-3350015 FIELD OFFICE	1.000 EACH				
1190	2523-0000100 LIGHTING POLES BRIDGE POLE	4.000 EACH				
1200	2523-0000100 LIGHTING POLES COMBINATION ROADWAY AND TRAIL POLE	6.000 EACH				
1210	2523-0000100 LIGHTING POLES ROADWAY POLE	7.000 EACH				
1220	2523-0000100 LIGHTING POLES TRAIL POLE	6.000 EACH				
1230	2523-0000200 ELECTRICAL CIRCUITS	4,028.000 LF				



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

SECTION: 0001

Items for a 201'-4 x 38'-0 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1240	2523-0000310 HANDHOLES AND JUNCTION BOXES	13.000 EACH				
1250	2523-0000400 CONTROL CABINET	2.000 EACH				
1260	2524-6765010 REMOVE AND REINSTALL SIGN AS PER PLAN	4.000 EACH				
1270	2524-9276010 PERFORATED SQUARE STEEL TUBE POSTS	330.000 LF				
1280	2524-9276021 PERFORATED SQUARE STEEL TUBE POST ANCHOR, BREAK-AWAY SOIL INSTALLATION	23.000 EACH				
1290	2524-9276024 PERFORATED SQUARE STEEL TUBE POST ANCHOR, BREAK-AWAY CONCRETE INSTALLATION	7.000 EACH				
1300	2524-9325001 TYPE A SIGNS, SHEET ALUMINUM	206.500 SF				
1310	2525-0000100 TRAFFIC SIGNALIZATION	LUMP SUM	LUMP SUM			
1320	2526-8285010 CONSTRUCTION SURVEY, MONUMENT PRESERVATION	LUMP SUM	LUMP SUM			
1330	2526-8285020 CONSTRUCTION SURVEY, CONTROL POINT SURVEY	LUMP SUM	LUMP SUM			
1340	2526-8285030 CONSTRUCTION SURVEY, RIGHT OF WAY	LUMP SUM	LUMP SUM			



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

SECTION: 0001

Items for a 201'-4 x 38'-0 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1350	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM			
1360	2527-9263143 PAINTED SYMBOLS AND LEGENDS, DURABLE	81.000 EACH				
1370	2527-9263181 PAVEMENT MARKINGS REMOVED	59.240 STA				
1380	2527-9263190 SYMBOLS AND LEGENDS REMOVED	8.000 EACH				
1390	2527-9263217 PAINTED PAVEMENT MARKINGS, DURABLE	230.050 STA				
1400	2527-9263231 REMOVABLE TAPE MARKINGS, WET RETROREFLECTIVE	50.480 STA				
1410	2527-9270112 GROOVES CUT FOR PAVEMENT MARKINGS	230.050 STA				
1420	2527-9270120 GROOVES CUT FOR SYMBOLS AND LEGENDS	81.000 EACH				
1430	2528-2518000 SAFETY CLOSURE	27.000 EACH				
1440	2528-8400048 TEMPORARY BARRIER RAIL, CONCRETE	2,069.000 LF				
1450	2528-8400256 TEMPORARY TRAFFIC SIGNALS	1.000 EACH				



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

SECTION: 0001

Items for a 201'-4 x 38'-0 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1460	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
1470	2528-9109020 TEMPORARY LANE SEPARATOR SYSTEM	3,130.000 LF				
1480	2528-9290050 PORTABLE DYNAMIC MESSAGE SIGN (PDMS)	40.000 CDAY				
1490	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
1500	2537-8900500 AMENDED SOIL	130.000 CY				
1510	2552-0000140 ROCK EXCAVATION	436.000 CY				
1520	2552-0000210 TRENCH FOUNDATION	317.000 TON				
1530	2552-0000220 REMOVAL, DISPOSAL, AND REPLACEMENT OF UNSUITABLE BACKFILL MATERIAL	5,806.000 CY				
1540	2552-0000300 TRENCH COMPACTION TESTING	LUMP SUM	LUMP SUM			
1550	2554-0112008 WATER MAIN, TRENCHED, DUCTILE IRON PIPE (DIP), 8 IN.	150.000 LF				
1560	2554-0112012 WATER MAIN, TRENCHED, DUCTILE IRON PIPE (DIP), 12 IN.	764.000 LF				



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

SECTION: 0001

Items for a 201'-4 x 38'-0 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1570	2554-0114006 WATER MAIN, TRENCHED, POLYVINYL CHLORIDE PIPE (PVC), 6 IN.	653.000 LF				
1580	2554-0203000 FITTINGS BY WEIGHT, DUCTILE IRON	4,212.000 LB				
1590	2554-0205110 WATER SERVICE STUB, COPPER, 1 IN.	611.800 LF				
1600	2554-0205410 WATER SERVICE CORPORATION, COPPER, 1 IN.	21.000 EACH				
1610	2554-0205710 WATER SERVICE CURB STOP AND BOX, COPPER, 1 IN.	21.000 EACH				
1620	2554-0207006 VALVE, GATE, DIP, 6 IN.	1.000 EACH				
1630	2554-0207008 VALVE, GATE, DIP, 8 IN.	1.000 EACH				
1640	2554-0207012 VALVE, GATE, DIP, 12 IN.	2.000 EACH				
1650	2554-0209012 VALVE REMOVAL, 12 IN.	1.000 EACH				
1660	2554-0210201 FIRE HYDRANT ASSEMBLY, WM-201	4.000 EACH				
1670	2554-0210205 FIRE HYDRANT ASSEMBLY REMOVAL	2.000 EACH				
1680	2554-0211000 FLUSHING DEVICE (BLOWOFF), TEMPORARY	2.000 EACH				



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

SECTION: 0001

Items for a 201'-4 x 38'-0 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1690	2554-0212020 VALVE BOX EXTENSION	1.000 EACH				
1700	2554-0212040 VALVE BOX ADJUSTMENT, MINOR	7.000 EACH				
1710	2554-0212050 VALVE BOX REMOVAL	4.000 EACH				
1720	2555-0000010 DELIVER AND STOCKPILE SALVAGED MATERIALS	LUMP SUM	LUMP SUM			
1730	2557-0000100 LONGITUDINAL GROOVING IN CONCRETE, PAVEMENT	963.700 SY				
1740	2599-9999005 (‘EACH’ ITEM) PIPE SUPPORT OVER EXISTING UTILITY	20.000 EACH				
1750	2599-9999005 (‘EACH’ ITEM) SUBDRAIN CLEANOUT, TYPE B	17.000 EACH				
1760	2599-9999009 (‘LINEAR FEET’ ITEM) PAVEMENT NOTCH REPLACEMENT	44.000 LF				
1770	2599-9999010 (‘LUMP SUM’ ITEM) CONCRETE WASHOUT	LUMP SUM	LUMP SUM			
1780	2599-9999010 (‘LUMP SUM’ ITEM) MAINTENANCE OF SOLID WASTE COLLECTION	LUMP SUM	LUMP SUM			
1790	2599-9999010 (‘LUMP SUM’ ITEM) RECTANGULAR RAPID FLASHING BEACON (RRFB)	LUMP SUM	LUMP SUM			



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

SECTION: 0001

Items for a 201'-4 x 38'-0 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1800	2599-9999010 (‘LUMP SUM’ ITEM) WATER MAIN ABANDONMENT	LUMP SUM	LUMP SUM			
1810	2599-9999014 (‘SQUARE FEET’ ITEM) INSULATION BOARD	160.000 SF				
1820	2599-9999014 (‘SQUARE FEET’ ITEM) TEXTURED CONCRETE FORM LINER	2,284.000 SF				
1830	2599-9999018 (‘SQUARE YARDS’ ITEM) ANTI- GRAFFITI COATING	290.400 SY				
1840	2601-2634105 MULCHING, BONDED FIBER MATRIX	12.260 ACRE				
1850	2601-2634150 MULCHING, WOOD CELLULOSE FIBER	0.060 ACRE				
1860	2601-2636018 WETLAND GRASS SEEDING	0.120 ACRE				
1870	2601-2636043 SEEDING AND FERTILIZING (RURAL)	0.250 ACRE				
1880	2601-2636044 SEEDING AND FERTILIZING (URBAN)	5.130 ACRE				
1890	2601-2638352 SLOPE PROTECTION, WOOD EXCELSIOR MAT	883.000 SQ				
1900	2601-2642120 STABILIZING CROP - SEEDING AND FERTILIZING (URBAN)	6.880 ACRE				



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

SECTION: 0001

Items for a 201'-4 x 38'-0 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1910	2602-0000020 SILT FENCE	4,812.900 LF				
1920	2602-0000071 REMOVAL OF SILT FENCE OR SILT FENCE FOR DITCH CHECKS	4,812.900 LF				
1930	2602-0000101 MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	482.000 LF				
1940	2602-0000150 STABILIZED CONSTRUCTION ENTRANCE, EC-303	255.000 LF				
1950	2602-0000212 FLOATING SILT CURTAIN (HANGING)	1,062.000 LF				
1960	2602-0000240 MAINTENANCE OF FLOATING SILT CURTAIN	532.000 LF				
1970	2602-0000312 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	8,577.000 LF				
1980	2602-0000351 REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	8,577.000 LF				
1990	2602-0000500 OPEN-THROAT CURB INTAKE SEDIMENT FILTER, EC-602	358.000 LF				
2000	2602-0000510 MAINTENANCE OF OPEN-THROAT CURB INTAKE SEDIMENT FILTER	32.000 EACH				
2010	2602-0000520 REMOVAL OF OPEN-THROAT CURB INTAKE SEDIMENT FILTER	32.000 EACH				



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-4775-646

Call Order: 007

Letting Date: August 18, 2026

SECTION: 0001

Items for a 201'-4 x 38'-0 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
2020	2602-0000530 GRATE INTAKE SEDIMENT FILTER BAG, EC-604	14.000 EACH	_____	_____	_____	_____
2030	2602-0000540 MAINTENANCE OF GRATE INTAKE SEDIMENT FILTER BAG	14.000 EACH	_____	_____	_____	_____
2040	2602-0000550 REMOVAL OF GRATE INTAKE SEDIMENT FILTER BAG	14.000 EACH	_____	_____	_____	_____
2050	2602-0010010 MOBILIZATIONS, EROSION CONTROL	16.000 EACH		600.00000		9,600.00
2060	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	4.000 EACH		1,200.00000		4,800.00
Section: 0001			Total:		_____	
			Total Bid:		_____	