



CONTRACTS AND SPECIFICATIONS BUREAU Proposal

Proposal ID: 70-C070-078

Letting Date: August 18, 2026

Call Order: 101

Proposal Work Type: PCC PAVEMENT - GRADE & REPLACE

DBE Goal: 0.0%

Contracting Authority: MUSCATINE COUNTY

Proposal Guaranty: \$125,000.00

This proposal includes the following project(s):

Project Number: FM-C070(78)--55-70

County: MUSCATINE

Project Work Type: PCC PAVEMENT - GRADE &
REPLACE

Route: 230TH ST.

Location: On 230TH STREET G28, From Louisa County Line to Iowa 70

Road System: FARM TO MARKET ROAD

Federal Aid - Wages: Non-Federal Aid - Predetermined Wages are not in Effect

Contract Time

Proposal ID: 70-C070-078

Call Order: 101

Letting Date: August 18, 2026

Site ID	Site Details			Liquidated Damages
00	Late Start Date	08/23/2027	55 WORK DAYS	\$1,000.00

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

Notes

Proposal ID: 70-C070-078

Call Order: 101

Letting Date: August 18, 2026

Notes :

There are no notes for this proposal.



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 70-C070-078

Call Order: 101

Letting Date: August 18, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.
500.01	*** WINTER WORK *** The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.
GS-23006	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 70-C070-078

Call Order: 101

Letting Date: August 18, 2026

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2102-2625000 EMBANKMENT-IN-PLACE	714.000 CY				
0020	2102-2713090 EXCAVATION, CLASS 13, WASTE	8,400.000 CY				
0030	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	363.000 CY				
0040	2113-0001100 SUBGRADE STABILIZATION MATERIAL, POLYMER GRID	19,508.500 SY				
0050	2115-0100000 MODIFIED SUBBASE	3,113.000 CY				
0060	2115-0100200 MODIFIED SUBBASE, PLACE ONLY	2,284.000 CY				
0070	2121-7425020 GRANULAR SHOULDERS, TYPE B	2,010.000 TON				
0080	2213-7100400 RELOCATION OF MAIL BOXES	5.000 EACH				
0090	2301-0690201 BRIDGE APPROACH, BR-201	435.400 SY				
0100	2301-1033070 STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 7 IN.	635.000 SY				
0110	2301-1033090 STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 9 IN.	17,140.000 SY				



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 70-C070-078

Call Order: 101

Letting Date: August 18, 2026

SECTION: 0001

ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	2301-6911722 PORTLAND CEMENT CONCRETE PAVEMENT SAMPLES	LUMP SUM	LUMP SUM			
0130	2301-9091000 RUMBLE STRIP PANEL (PCC SURFACE)	2.000 EACH				
0140	2312-8260051 GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE	30.000 TON				
0150	2314-8257000 DUST CONTROL SURFACE TREATMENT	79.200 STA				
0160	2315-8275025 SURFACING, DRIVEWAY, CLASS A CRUSHED STONE	105.000 TON				
0170	2317-7000110 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR PCC PAVEMENT SMOOTHNESS (BY SCHEDULE)	12,855.000 EACH		1.00000		12,855.00
0180	2502-8212034 SUBDRAIN, LONGITUDINAL, (SHOULDER) 4 IN. DIA.	11,400.000 LF				
0190	2502-8221306 SUBDRAIN OUTLET, DR-306	40.000 EACH				
0200	2510-6750501 REMOVAL AND CRUSHING OF PAVEMENT	13,587.300 SY				
0210	2526-8285020 CONSTRUCTION SURVEY, CONTROL POINT SURVEY	LUMP SUM	LUMP SUM			



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 70-C070-078

Call Order: 101

Letting Date: August 18, 2026

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0220	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM			
0230	2527-9263217 PAINTED PAVEMENT MARKINGS, DURABLE	503.650 STA				
0240	2528-2518000 SAFETY CLOSURE	4.000 EACH				
0250	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
0260	2528-8445113 FLAGGERS	10.000 EACH		660.00000		6,600.00
0270	2528-9290050 PORTABLE DYNAMIC MESSAGE SIGN (PDMS)	28.000 CDAY				
0280	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
0290	2601-2634100 MULCHING	1.000 ACRE				
0300	2601-2636043 SEEDING AND FERTILIZING (RURAL)	0.500 ACRE				
0310	2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING	0.500 ACRE				
0320	2602-0000312 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	1,950.000 LF				



7/14/2026 10:05 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 70-C070-078

Call Order: 101

Letting Date: August 18, 2026

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0330	2602-0000351 REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	1,950.000 LF				
0340	2602-0010010 MOBILIZATIONS, EROSION CONTROL	2.000 EACH	600.00000		1,200.00	
0350	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	1.000 EACH	1,200.00000		1,200.00	
Section: 0001			Total:			
			Total Bid:			