PAVEMENT MARKING LINE TYPES

Line factors based on 6-inch wide continuous line.
*BCY4 - Place on the same side of the roadway to match existing markings near the project.
**NPY4 - Estimating purposes only. No Passing Zone Lines will be located in the field.
***MNY6 - Factor of 1.00 includes number of 6-inch passes to cover median nose area.

BCY4: Broken Centerline (Yellow) @ 0.17 | BCY6: Broken Centerline (Yellow) @ 0.25 | BLC6: Broken Line Contrast (White/Black) @ 0.50 | BLW4: Broken Lane Line (White) @ 0.17 | BLW6: Broken Lane Line (White) @ 0.25
CBW6: Crosswalk Bar (White) @ 10.00 | CHW8: Channelizing Line (White) @ 1.33 | CHW10: Channelizing Line (White) @ 1.67 | CHY8: Channelizing Line (Yellow) @ 1.33 | CHY10: Channelizing Line (Yellow) @ 1.67
CLW6: Crosswalk Line (White) @ 2.00 | DCY4: Double Centerline (Yellow) @ 1.34 | DCY6: Double Centerline (Yellow) @ 2.00 | DDY4: Double Dotted Line (Yellow) @ 0.44 | DDY6: Double Dotted Line (Yellow) @ 0.67
DLW4: Dotted Line (White) @ 0.22 | DLW6: Dotted Line (White) @ 0.33 | DLY4: Dotted Line (Yellow) @ 0.22 | DLY6: Dotted Line (Yellow) @ 0.33 | ELW4: Edge Line Right (White) @ 0.67
ELW6: Edge Line Right (White) @ 1.00 | ELY4: Edge Line Left (Yellow) @ 0.67 | ELY6: Edge Line Left (Yellow) @ 1.00 | LDW8: Lane Drop (White) @ 0.33 | LDW10: Lane Drop (White) @ 0.42
MNY6: Median Nose (Yellow) @ 1.00 | NPY4: No Passing Zone Line (Yellow) @ 0.84 | NPY6: No Passing Zone Line (Yellow) @ 1.25 | RLW4: Ramp Edge Line Right (White) @ 0.67 | RLW6: Ramp Edge Line Right (White) @ 1.00
RLY4: Ramp Edge Line Left (Yellow) @ 0.67 | RLY6: Ramp Edge Line Left (Yellow) @ 1.00 | SLW2: Stop Line (White) @ 4.00 | SLW4: Solid Lane Line (White) @ 0.67 | SLW6: Solid Lane Line (White) @ 1.00
SPW4: Sloped Curb 4" (White) @ 2.16 | SPW6: Sloped Curb 6" (White) @ 2.28 | SPY4: Sloped Curb 4" (Yellow) @ 2.16 | SPY6: Sloped Curb 6" (Yellow) @ 2.28 | STW6: Standard Curb 6" (Yellow) @ 2.03
STY6: Standard Curb 6" (Yellow) @ 2.03 | YLW2: Yield Line (White) @ 1.15

Line No.	Road ID	Station From	Station To	Lane	Marking Type	Left	Center	Right	Groove Marking Needed?	Groove Qty. (STA)	BCY4* Factored (STA)	CHW8 Factored (STA)	DCY4 Factored (STA)	DCY6 Factored (STA)	ELW4 Factored (STA)	ELW6 Factored (STA)	NPY4** Factored (STA)	NPY6** Factored (STA)	SLW2 Factored (STA)	Remarks
1.0	C25	3768+18.00	3778+99.00	Both	Removal of Paint		X		No		1.84									Stage 1
11.0	C25	3784+83.00	3796+69.00	EB	Removal of Paint			X	No						7.95					Stage 1
37.0	C25	3786+60.00	3787+45.00	EB	Removal of Paint	X			No			1.13								Final
38.0	C25	3794+36.00	3795+21.00	EB	Removal of Paint	X			No			1.13								Final
2.0	C25	3778+99.00	3782+81.00	EB	Removal of Paint		X		No								3.21			Stage 1
41.0	C25	3786+60.00	3795+21.00	WB	Removal of Paint	X			No			11.45								Final
43.0	C25	3768+40.00	3778+99.00	EB	Removal of Paint		X		No									13.24		Final
45.0	C25	3782+81.00	3783+18.00	EB	Removal of Paint		X		No									0.46		Final
20.0	C25	3786+60.00	3787+48.00	EB	Removal of Paint			X	No			11.45								Stage 2
21.0	C25	3794+34.00	3795+21.00	EB	Removal of Paint			X	No			11.45								Stage 2
24.0	C25	3786+60.00	3787+45.00	WB	Removal of Paint			X	No			1.13								Stage 2
25.0	C25	3794+36.00	3795+21.00	WB	Removal of Paint			X	No			1.13								Stage 2
27.0	C25	3784+83.00	3787+48.00	WB	Removal of Paint	X			No						1.78					Stage 2
46.0	C25	3783+18.00	3783+18.00	EB	Removal of Paint		X		No										0.48	Final
47.0	C25	3798+18.00	3798+18.00	WB	Removal of Paint		X		No										0.48	Final
28.0	C25	3794+34.00	3796+75.00	WB	Removal of Paint	X			No						1.61					Stage 2
48.0	C25	3798+18.00	3798+52.00	WB	Removal of Paint		X		No									0.43		Final
3.0	C25	3782+81.00	3787+49.00	Both	Removal of Paint		X		No				6.27							Stage 1
50.0	C25	3803+49.00	3813+18.00	WB	Removal of Paint		X		No									12.11		Final
4.0	C25	3794+34.00	3798+52.00	Both	Removal of Paint		X		No				5.60							Stage 1
5.0	C25	3798+52.00	3803+49.00	WB	Removal of Paint		X		No								4.17			Stage 1
6.0	C25	3803+49.00	3813+18.00	Both	Removal of Paint		X		No		1.65									Stage 1
Total Marking Type : Removal of Paint	Total 100.15										3.49	38.87	11.87	0.00	11.34	0.00	7.38	26.24	0.96	
36.0	C25	3783+18.00	3786+60.00	EB	Removal of Removable Tape	X		X	No			4.55								Final
39.0	C25	3795+21.00	3798+19.00	EB	Removal of Removable Tape	X		X	No			3.96								Final
40.0	C25	3784+83.00	3786+60.00	WB	Removal of Removable Tape	X			No			2.35								Final
42.0	C25	3795+21.00	3796+75.00	WB	Removal of Removable Tape	X			No			2.05								Final
19.0	C25	3784+83.00	3786+60.00	EB	Removal of Removable Tape			X	No			2.35								Stage 2
22.0	C25	3795+21.00	3796+69.00	EB	Removal of Removable Tape			X	No			1.97								Stage 2
23.0	C25	3783+18.00	3786+60.00	WB	Removal of Removable Tape	X		X	No			4.55								Stage 2
26.0	C25	3795+21.00	3798+18.00	WB	Removal of Removable Tape	X		X	No			3.95								Stage 2
Total Marking Type : Removal of Removable Tape	Total 25.73 (not a bid item)										0.00	25.73	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
7.0	C25	3768+18.00	3783+18.00	EB	Waterborne/Solvent Paint		X		No									18.75		Stage 1
8.0	C25	3783+18.00	3783+18.00	EB	Waterborne/Solvent Paint			X	No										0.48	Stage 1
9.0	C25	3798+18.00	3798+18.00	WB	Waterborne/Solvent Paint	X			No										0.48	Stage 1
10.0	C25	3798+18.00	3813+18.00	WB	Waterborne/Solvent Paint		X		No									18.75		Stage 1
13.0	C25	3786+60.00	3795+21.00	EB	Waterborne/Solvent Paint			X	No			11.45								Stage 1

PAVEMENT MARKING LINE TYPES

Line factors based on 6-inch wide continuous line.
*BCY4 - Place on the same side of the roadway to match existing markings near the project.
**NPY4 - Estimating purposes only. No Passing Zone Lines will be located in the field.
***MNY6 - Factor of 1.00 includes number of 6-inch passes to cover median nose area.

BCY4: Broken Centerline (Yellow) @ 0.17 | BCY6: Broken Centerline (Yellow) @ 0.25 | BLC6: Broken Line Contrast (White/Black) @ 0.50 | BLW4: Broken Lane Line (White) @ 0.17 | BLW6: Broken Lane Line (White) @ 0.25
CBW6: Crosswalk Bar (White) @ 10.00 | CHW8: Channelizing Line (White) @ 1.33 | CHW10: Channelizing Line (White) @ 1.67 | CHY8: Channelizing Line (Yellow) @ 1.33 | CHY10: Channelizing Line (Yellow) @ 1.67
CLW6: Crosswalk Line (White) @ 2.00 | DCY4: Double Centerline (Yellow) @ 1.34 | DCY6: Double Centerline (Yellow) @ 2.00 | DDY4: Double Dotted Line (Yellow) @ 0.44 | DDY6: Double Dotted Line (Yellow) @ 0.67
DLW4: Dotted Line (White) @ 0.22 | DLW6: Dotted Line (White) @ 0.33 | DLY4: Dotted Line (Yellow) @ 0.22 | DLY6: Dotted Line (Yellow) @ 0.33 | ELW4: Edge Line Right (White) @ 0.67
ELW6: Edge Line Right (White) @ 1.00 | ELY4: Edge Line Left (Yellow) @ 0.67 | ELY6: Edge Line Left (Yellow) @ 1.00 | LDW8: Lane Drop (White) @ 0.33 | LDW10: Lane Drop (White) @ 0.42
MNY6: Median Nose (Yellow) @ 1.00 | NPY4: No Passing Zone Line (Yellow) @ 0.84 | NPY6: No Passing Zone Line (Yellow) @ 1.25 | RLW4: Ramp Edge Line Right (White) @ 0.67 | RLW6: Ramp Edge Line Right (White) @ 1.00
RLY4: Ramp Edge Line Left (Yellow) @ 0.67 | RLY6: Ramp Edge Line Left (Yellow) @ 1.00 | SLW2: Stop Line (White) @ 4.00 | SLW4: Solid Lane Line (White) @ 0.67 | SLW6: Solid Lane Line (White) @ 1.00
SPW4: Sloped Curb 4" (White) @ 2.16 | SPW6: Sloped Curb 6" (White) @ 2.28 | SPY4: Sloped Curb 4" (Yellow) @ 2.16 | SPY6: Sloped Curb 6" (Yellow) @ 2.28 | STW6: Standard Curb 6" (Yellow) @ 2.03
STY6: Standard Curb 6" (Yellow) @ 2.03 | YLW2: Yield Line (White) @ 1.15

Line No.	Road ID	Station From	Station To	Lane	Marking Type	Left	Center	Right	Groove Marking Needed?	Groove Qty. (STA)	BCY4* Factored (STA)	CHW8 Factored (STA)	DCY4 Factored (STA)	DCY6 Factored (STA)	ELW4 Factored (STA)	ELW6 Factored (STA)	NPY4** Factored (STA)	NPY6** Factored (STA)	SLW2 Factored (STA)	Remarks
16.0	C25	3786+60.00	3787+45.00	WB	Waterborne/Solvent Paint			X	No			1.13								Stage 1
17.0	C25	3794+36.00	3795+21.00	WB	Waterborne/Solvent Paint			X	No			1.13								Stage 1
43.0	C25	3768+40.00	3778+99.00	Both	Waterborne/Solvent Paint		X		No									13.24		Final
30.0	C25	3786+60.00	3787+45.00	EB	Waterborne/Solvent Paint	X			No			1.13								Stage 2
49.0	C25	3782+81.00	3798+52.00	Both	Waterborne/Solvent Paint		X		No					31.42						Final
31.0	C25	3794+36.00	3795+21.00	EB	Waterborne/Solvent Paint	X			No			1.13								Stage 2
34.0	C25	3786+60.00	3795+21.00	WB	Waterborne/Solvent Paint	X			No			11.45								Stage 2
51.0	C25	3803+49.00	3813+18.00	WB	Waterborne/Solvent Paint		X		No											Final
52.0	C25	3784+82.00	3796+75.00	WB	Waterborne/Solvent Paint	X			No							11.93				Final
53.0	C25	3784+83.00	3796+69.00	EB	Waterborne/Solvent Paint			X	No							11.86				Final
Total											0.00	27.42	0.00	31.42	0.00	23.79	0.00	50.74	0.96	
Total 134.33																				
Marking Type : Waterborne/Solvent Paint																				
12.0	C25	3784+83.00	3786+60.00	EB	Wet Retroreflective Removable Tape			X	No			2.35								Stage 1
14.0	C25	3795+21.00	3796+69.00	EB	Wet Retroreflective Removable Tape			X	No			1.97								Stage 1
15.0	C25	3783+18.00	3786+60.00	WB	Wet Retroreflective Removable Tape	X		X	No			4.55								Stage 1
18.0	C25	3795+21.00	3798+18.00	WB	Wet Retroreflective Removable Tape	X		X	No			3.95								Stage 1
29.0	C25	3783+18.00	3786+60.00	EB	Wet Retroreflective Removable Tape	X		X	No			4.55								Stage 2
32.0	C25	3795+21.00	3798+19.00	EB	Wet Retroreflective Removable Tape	X		X	No			3.96								Stage 2
33.0	C25	3784+83.00	3786+60.00	WB	Wet Retroreflective Removable Tape	X			No			2.35								Stage 2
35.0	C25	3795+21.00	3796+75.00	WB	Wet Retroreflective Removable Tape	X			No			2.05								Stage 2
Total											0.00	25.73	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
Total 25.73																				
Marking Type : Wet Retroreflective Removable Tape																				
Grand Totals											3.49	117.75	11.87	31.42	11.34	23.79	7.38	76.98	1.92	