11/10/2026 11:02 AM

CONTRACTS AND SPECIFICATIONS BUREAU
Proposal

Proposal ID: 06-C006-126 **Letting Date:** December 15, 2026
Call Order: 001
Proposal Work Type: RCB CULVERT REPLACEMENT - TWIN BOX
DBE Goal: 0.0%
Contracting Authority: BENTON COUNTY
Proposal Guaranty: $25,000.00

This proposal includes the following project(s):

Project Number: BROS-C006(126)--8J-06 **County:** BENTON
Project Work Type: RCB CULVERT REPLACEMENT - TWIN BOX **Route:** 16TH AVE.
Location: On 16 AVE, Over SPRING CK, S30 T86 R11
Road System: LOCAL SECONDARY ROAD
Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

IOWA | DOT

Contracts and Specifications Bureau

Contract Time

Proposal ID: 06-C006-126 **Call Order:** 001 **Letting Date:** December 15, 2026

Site ID	Site Details				Liquidated Damages
00	Late Start Date	09/13/2027	40	WORK DAYS	$1,000.00

.

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

IOWA | DOT

Contracts and Specifications Bureau

Notes

Proposal ID: 06-C006-126 **Call Order:** 001 **Letting Date:** December 15, 2026

Notes :

There are no notes for this proposal.

11/10/2026 11:02 AM

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 06-C006-126 **Call Order:** 001 **Letting Date:** December 15, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.

IOWA DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 06-C006-126 **Call Order:** 001 **Letting Date:** December 15, 2026

Note	Description
005.1107.02	*** Revisions to Article 1107.02 *** Article 1107.02, Insurance, is amended by the following modifications and additions. This proposal note becomes null and void January 1, 2027. A. It shall be the Contractor's responsibility to have liability insurance covering all of the construction operations incident to contract completion and the Contractor must have on file with the Contracting Authority a current "Certificate of Insurance" prior to award of contract. The certificate shall identify the insurance company firm name and address, Contractor firm name, policy period, type of policy, limits of coverage, and scope of work covered (single contract or statewide). This requirement shall apply with equal force, whether the work is performed by persons employed directly by the Contractor including a subcontractor, persons employed by a subcontractor, or by an independent contractor. B. In addition to the above, the Contracting Authority shall be included as an insured party, or a separate owner's protective policy shall be filed showing the Contracting Authority as an insured party. C. The liability insurance shall be written by an insurance company (or companies) qualified to do business in Iowa. For independent contractors engaged solely in the transportation of materials, the minimum coverage provided by such insurance shall be not less than that required by Chapter 325A, Code of Iowa, for such truck operators or contract carriers as defined therein. For all other contractors, subcontractors, independent contractors, and the Contracting Authority, the minimum coverage by such insurance shall be as follows: General Liability, Including: BODILY INJURY Independent Contractors $500,000 Each Occurrence Contractual Liability, $500,000 Aggregate Products and Completed PROPERTY DAMAGE Operations $250,000 Each Occurrence $250,000 Aggregate or BODILY INJURY AND PROPERTY DAMAGE - COMBINED SINGLE LIMIT* $750,000 Each Occurrence $750,000 Aggregate *A comprehensive Catastrophe Liability Policy (Umbrella) can be used to aid in

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 06-C006-126 **Call Order:** 001 **Letting Date:** December 15, 2026

Note	Description
	achieving the minimum required limits. D. Failure on the part of the Contractor to comply with the requirements of this article will be considered sufficient cause to suspend the work, withhold estimates, and to deny the Contractor from receiving further contract awards, as provided in Article 1103.01.
500.01	*** WINTER WORK *** The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.
FHWA-1273.09	FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023 23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.
GS-23007	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, OCTOBER 20, 2026 RELEASE

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 06-C006-126 **Call Order:** 001 **Letting Date:** December 15, 2026

Note	Description
IA26-28.4A	PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20260028 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY) Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract. *** Additional Requirement *** Contracts where the Department is the Contracting Authority: The Prime Contractor and each approved Subcontractor shall submit certified payrolls weekly to the Project Engineer. Each Contractor shall use the AASHTOWare Project Civil Rights and Labor (AWP CRL) software to electronically submit Certified Payroll Reports. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall review and approve each Subcontractor's payroll within AWP CRL. Contracts where the Department is not the Contracting Authority: The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.
NoBABA01	*** Build America, Buy America *** Article 1107.06, B, Build America, Buy America, of the Iowa DOT Standard Specifications does not apply to this contract.

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 06-C006-126 **Call Order:** 001 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A TWIN 10' X 8' X 46'-0 REINFORCED BOX CULVERT

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2102-0425070 SPECIAL BACKFILL	80.000 TON	_____._____		_____._____	
0020	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	1,225.000 CY	_____._____		_____._____	
0030	2102-2710090 EXCAVATION, CLASS 10, WASTE	1,075.000 CY	_____._____		_____._____	
0040	2104-2710020 EXCAVATION, CLASS 10, CHANNEL	600.000 CY	_____._____		_____._____	
0050	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	750.000 CY	_____._____		_____._____	
0060	2312-8260051 GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE	135.000 TON	_____._____		_____._____	
0070	2401-6745625 REMOVAL OF EXISTING BRIDGE	 LUMP SUM	LUMP SUM		_____._____	
0080	2402-2720000 EXCAVATION, CLASS 20	750.000 CY	_____._____		_____._____	
0090	2403-0100020 STRUCTURAL CONCRETE (RCB CULVERT)	174.800 CY	_____._____		_____._____	
0100	2404-7775000 REINFORCING STEEL	25,213.000 LB	_____._____		_____._____	
0110	2418-0000010 TEMPORARY STREAM DIVERSION	1.000 EACH	_____._____		_____._____	
0120	2502-8221305 SUBDRAIN OUTLET, DR-305	2.000 EACH	_____._____		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 06-C006-126 **Call Order:** 001 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A TWIN 10' X 8' X 46'-0 REINFORCED BOX CULVERT

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	2507-3250005 ENGINEERING FABRIC	650.000 SY	_____._____		_____._____	
0140	2507-4011100 CONCRETE GROUT FOR REVETMENT OR GABION	24.000 CY	_____._____		_____._____	
0150	2507-6800061 REVETMENT, CLASS E	475.000 TON	_____._____		_____._____	
0160	2526-8285020 CONSTRUCTION SURVEY, CONTROL POINT SURVEY	LUMP SUM	LUMP SUM		_____._____	
0170	2526-8285030 CONSTRUCTION SURVEY, RIGHT OF WAY	LUMP SUM	LUMP SUM		_____._____	
0180	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM		_____._____	
0190	2528-2518000 SAFETY CLOSURE	2.000 EACH	_____._____		_____._____	
0200	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM		_____._____	
0210	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM		_____._____	
0220	2601-2634100 MULCHING	1.800 ACRE	_____._____		_____._____	
0230	2601-2636043 SEEDING AND FERTILIZING (RURAL)	0.900 ACRE	_____._____		_____._____	
0240	2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING	0.900 ACRE	_____._____		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 06-C006-126 **Call Order:** 001 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A TWIN 10' X 8' X 46'-0 REINFORCED BOX CULVERT

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	2602-0000020 SILT FENCE	380.000 LF				
0260	2602-0000030 SILT FENCE FOR DITCH CHECKS	132.000 LF				
0270	2602-0000101 MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	512.000 LF				
0280	2602-0000312 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	410.000 LF				
0290	2602-0010010 MOBILIZATIONS, EROSION CONTROL	1.000 EACH	600.00000		600.00	
0300	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	1.000 EACH	1,200.00000		1,200.00	

Section: 0001 **Total:** _____.____

Total Bid: _____.____