11/10/2026 11:02 AM

IOWA | DOT

CONTRACTS AND SPECIFICATIONS BUREAU
Proposal

Proposal ID: 14-4702-609 **Letting Date:** December 15, 2026
Call Order: 002
Proposal Work Type: BRIDGE REPLACEMENT - CCS
DBE Goal: 0.0%
Contracting Authority: CITY OF MANNING
Proposal Guaranty: $62,500.00

This proposal includes the following project(s):

Project Number: BROS-4702(609)--8J-14 **County:** CARROLL
Project Work Type: BRIDGE REPLACEMENT - CCS **Route:** E ST
Location: In the city of Manning, On E ST, Over Willow Creek
Road System: URBAN
Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

IOWA | DOT

Contracts and Specifications Bureau

Contract Time

Proposal ID: 14-4702-609 **Call Order:** 002 **Letting Date:** December 15, 2026

Site ID	Site Details				Liquidated Damages
00	Late Start Date	06/21/2027	90	WORK DAYS	$1,000.00

.

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

IOWA | DOT

Contracts and Specifications Bureau

Notes

Proposal ID: 14-4702-609 **Call Order:** 002 **Letting Date:** December 15, 2026

Notes :

There are no notes for this proposal.

IOWA DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 14-4702-609 **Call Order:** 002 **Letting Date:** December 15, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.

IOWA DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 14-4702-609 **Call Order:** 002 **Letting Date:** December 15, 2026

Note	Description
005.1107.02	*** Revisions to Article 1107.02 *** Article 1107.02, Insurance, is amended by the following modifications and additions. This proposal note becomes null and void January 1, 2027. A. It shall be the Contractor's responsibility to have liability insurance covering all of the construction operations incident to contract completion and the Contractor must have on file with the Contracting Authority a current "Certificate of Insurance" prior to award of contract. The certificate shall identify the insurance company firm name and address, Contractor firm name, policy period, type of policy, limits of coverage, and scope of work covered (single contract or statewide). This requirement shall apply with equal force, whether the work is performed by persons employed directly by the Contractor including a subcontractor, persons employed by a subcontractor, or by an independent contractor. B. In addition to the above, the Contracting Authority shall be included as an insured party, or a separate owner's protective policy shall be filed showing the Contracting Authority as an insured party. C. The liability insurance shall be written by an insurance company (or companies) qualified to do business in Iowa. For independent contractors engaged solely in the transportation of materials, the minimum coverage provided by such insurance shall be not less than that required by Chapter 325A, Code of Iowa, for such truck operators or contract carriers as defined therein. For all other contractors, subcontractors, independent contractors, and the Contracting Authority, the minimum coverage by such insurance shall be as follows: General Liability, Including: BODILY INJURY Independent Contractors $500,000 Each Occurrence Contractual Liability, $500,000 Aggregate Products and Completed PROPERTY DAMAGE Operations $250,000 Each Occurrence $250,000 Aggregate or BODILY INJURY AND PROPERTY DAMAGE - COMBINED SINGLE LIMIT* $750,000 Each Occurrence $750,000 Aggregate *A comprehensive Catastrophe Liability Policy (Umbrella) can be used to aid in

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 14-4702-609 **Call Order:** 002 **Letting Date:** December 15, 2026

Note	Description
	achieving the minimum required limits. D. Failure on the part of the Contractor to comply with the requirements of this article will be considered sufficient cause to suspend the work, withhold estimates, and to deny the Contractor from receiving further contract awards, as provided in Article 1103.01.
500.01	*** WINTER WORK *** The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.
FHWA-1273.09	FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023 23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.
GS-23007	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, OCTOBER 20, 2026 RELEASE

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 14-4702-609 **Call Order:** 002 **Letting Date:** December 15, 2026

Note	Description
IA26-28.4A	PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20260028 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY) Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract. *** Additional Requirement *** Contracts where the Department is the Contracting Authority: The Prime Contractor and each approved Subcontractor shall submit certified payrolls weekly to the Project Engineer. Each Contractor shall use the AASHTOWare Project Civil Rights and Labor (AWP CRL) software to electronically submit Certified Payroll Reports. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall review and approve each Subcontractor's payroll within AWP CRL. Contracts where the Department is not the Contracting Authority: The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 14-4702-609 **Call Order:** 002 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 90'0 X 30'-0 CONTINOUS CONCRETE SLAB BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2102-2625000 EMBANKMENT-IN-PLACE	196.000 CY	_____	_____	_____	_____
0020	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	190.000 CY	_____	_____	_____	_____
0030	2104-2710020 EXCAVATION, CLASS 10, CHANNEL	1,332.000 CY	_____	_____	_____	_____
0040	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	236.000 CY	_____	_____	_____	_____
0050	2115-0100000 MODIFIED SUBBASE	124.000 CY	_____	_____	_____	_____
0060	2123-7450020 SHOULDER FINISHING, EARTH	3.600 STA	_____	_____	_____	_____
0070	2301-0690203 BRIDGE APPROACH, BR-203	404.000 SY	_____	_____	_____	_____
0080	2301-1033080 STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 8 IN.	623.000 SY	_____	_____	_____	_____
0090	2301-6911722 PORTLAND CEMENT CONCRETE PAVEMENT SAMPLES	LUMP SUM	LUMP SUM		_____	_____
0100	2314-8257000 DUST CONTROL SURFACE TREATMENT	20.500 STA	_____	_____	_____	_____
0110	2401-6745625 REMOVAL OF EXISTING BRIDGE	LUMP SUM	LUMP SUM		_____	_____

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 14-4702-609 **Call Order:** 002 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 90'0 X 30'-0 CONTINOUS CONCRETE SLAB BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	2402-2720000 EXCAVATION, CLASS 20	82.400 CY	_____._____		_____._____	
0130	2403-0100010 STRUCTURAL CONCRETE (BRIDGE)	207.700 CY	_____._____		_____._____	
0140	2404-7775000 REINFORCING STEEL	102.000 LB	_____._____		_____._____	
0150	2404-7775005 REINFORCING STEEL, EPOXY COATED	52,305.000 LB	_____._____		_____._____	
0160	2414-6424119 CONCRETE BARRIER RAILING, AESTHETIC	214.000 LF	_____._____		_____._____	
0170	2414-6445100 STRUCTURAL STEEL PEDESTRIAN HAND RAILING	156.250 LF	_____._____		_____._____	
0180	2416-0100024 APRONS, CONCRETE, 24 IN. DIA.	1.000 EACH	_____._____		_____._____	
0190	2435-0140160 MANHOLE, STORM SEWER, SW-401, 60 IN.	1.000 EACH	_____._____		_____._____	
0200	2435-0250100 INTAKE, SW-501	1.000 EACH	_____._____		_____._____	
0210	2435-0250300 INTAKE, SW-503	1.000 EACH	_____._____		_____._____	
0220	2435-0251224 INTAKE, SW-512, 24 IN.	1.000 EACH	_____._____		_____._____	
0230	2501-0201042 PILES, STEEL, HP 10 X 42	1,485.000 LF	_____._____		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 14-4702-609 **Call Order:** 002 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 90'0 X 30'-0 CONTINOUS CONCRETE SLAB BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price Dollars Cents	Bid Amount Dollars Cents
0240	2501-5478042 CONCRETE ENCASEMENT OF STEEL H PILES, HP 10 X 42 (P10L TYPE 3)	245.900 LF	_____.____	_____.____
0250	2502-8212036 SUBDRAIN, LONGITUDINAL, (SHOULDER) 6 IN. DIA.	360.000 LF	_____.____	_____.____
0260	2502-8221303 SUBDRAIN OUTLET, DR-303	4.000 EACH	_____.____	_____.____
0270	2503-0114215 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 15 IN.	31.000 LF	_____.____	_____.____
0280	2503-0114218 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 18 IN.	47.000 LF	_____.____	_____.____
0290	2503-0114224 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 24 IN.	92.000 LF	_____.____	_____.____
0300	2503-0200036 REMOVE STORM SEWER PIPE LESS THAN OR EQUAL TO 36 IN.	28.000 LF	_____.____	_____.____
0310	2507-4011100 CONCRETE GROUT FOR REVETMENT OR GABION	160.000 CY	_____.____	_____.____
0320	2507-6800061 REVETMENT, CLASS E	850.000 TON	_____.____	_____.____
0330	2510-6745850 REMOVAL OF PAVEMENT	957.000 SY	_____.____	_____.____

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 14-4702-609 **Call Order:** 002 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 90'0 X 30'-0 CONTINOUS CONCRETE SLAB BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0340	2511-6745900 REMOVAL OF SIDEWALK	45.000 SY	_____._____		_____._____	
0350	2511-7526006 SIDEWALK, P.C. CONCRETE, 6 IN.	40.000 SY	_____._____		_____._____	
0360	2511-7528101 DETECTABLE WARNINGS	48.000 SF	_____._____		_____._____	
0370	2515-2475007 DRIVEWAY, P.C. CONCRETE, 7 IN.	80.000 SY	_____._____		_____._____	
0380	2524-6765010 REMOVE AND REINSTALL SIGN AS PER PLAN	1.000 EACH	_____._____		_____._____	
0390	2524-9100030 OBJECT MARKER, TYPE 3	4.000 EACH	_____._____		_____._____	
0400	2526-8285010 CONSTRUCTION SURVEY, MONUMENT PRESERVATION	LUMP SUM	LUMP SUM		_____._____	
0410	2526-8285030 CONSTRUCTION SURVEY, RIGHT OF WAY	LUMP SUM	LUMP SUM		_____._____	
0420	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM		_____._____	
0430	2528-2518000 SAFETY CLOSURE	3.000 EACH	_____._____		_____._____	
0440	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM		_____._____	
0450	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 14-4702-609 **Call Order:** 002 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 90'0 X 30'-0 CONTINOUS CONCRETE SLAB BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0460	2552-0000300 TRENCH COMPACTION TESTING	LUMP SUM	LUMP SUM		_____	_____
0470	2599-9999005 ('EACH' ITEM) REMOVE APRON	3.000 EACH	_____	_____	_____	_____
0480	2601-2634105 MULCHING, BONDED FIBER MATRIX	0.200 ACRE	_____	_____	_____	_____
0490	2601-2636043 SEEDING AND FERTILIZING (RURAL)	0.200 ACRE	_____	_____	_____	_____
0500	2602-0000020 SILT FENCE	200.000 LF	_____	_____	_____	_____
0510	2602-0000071 REMOVAL OF SILT FENCE OR SILT FENCE FOR DITCH CHECKS	200.000 LF	_____	_____	_____	_____
0520	2602-0000320 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 20 IN. DIA.	200.000 LF	_____	_____	_____	_____
0530	2602-0000351 REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	200.000 LF	_____	_____	_____	_____
	Section: 0001		**Total:**		_____	_____

Total Bid: _____.____