11/10/2026 11:02 AM

IOWA | DOT

CONTRACTS AND SPECIFICATIONS BUREAU
Proposal

Proposal ID: 16-4555-606 **Letting Date:** December 15, 2026
Call Order: 003
Proposal Work Type: BRIDGE REPLACEMENT - CCS
DBE Goal: 0.0%
Contracting Authority: CEDAR COUNTY
Proposal Guaranty: $62,500.00

This proposal includes the following project(s):

Project Number: BRS-4555(606)--60-16 **County:** CEDAR
Project Work Type: BRIDGE REPLACEMENT - CCS **Route:** Y14
Location: In the city of Lowden, On Y 14 - Hoover Hwy, Over YANKEE RUN CREEK
Road System: URBAN
Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

IOWA | DOT

Contracts and Specifications Bureau

Contract Time

Proposal ID: 16-4555-606 **Call Order:** 003 **Letting Date:** December 15, 2026

Site ID	Site Details				Liquidated Damages
00	Late Start Date	06/01/2027	75	WORK DAYS	$1,000.00

.

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

IOWA | DOT

Contracts and Specifications Bureau

Notes

Proposal ID: 16-4555-606 **Call Order:** 003 **Letting Date:** December 15, 2026

Notes :

There are no notes for this proposal.

11/10/2026 11:02 AM

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 16-4555-606 **Call Order:** 003 **Letting Date:** December 15, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 16-4555-606 **Call Order:** 003 **Letting Date:** December 15, 2026

Note	Description
005.1107.02	*** Revisions to Article 1107.02 *** Article 1107.02, Insurance, is amended by the following modifications and additions. This proposal note becomes null and void January 1, 2027. A. It shall be the Contractor's responsibility to have liability insurance covering all of the construction operations incident to contract completion and the Contractor must have on file with the Contracting Authority a current "Certificate of Insurance" prior to award of contract. The certificate shall identify the insurance company firm name and address, Contractor firm name, policy period, type of policy, limits of coverage, and scope of work covered (single contract or statewide). This requirement shall apply with equal force, whether the work is performed by persons employed directly by the Contractor including a subcontractor, persons employed by a subcontractor, or by an independent contractor. B. In addition to the above, the Contracting Authority shall be included as an insured party, or a separate owner's protective policy shall be filed showing the Contracting Authority as an insured party. C. The liability insurance shall be written by an insurance company (or companies) qualified to do business in Iowa. For independent contractors engaged solely in the transportation of materials, the minimum coverage provided by such insurance shall be not less than that required by Chapter 325A, Code of Iowa, for such truck operators or contract carriers as defined therein. For all other contractors, subcontractors, independent contractors, and the Contracting Authority, the minimum coverage by such insurance shall be as follows: General Liability, Including: BODILY INJURY Independent Contractors $500,000 Each Occurrence Contractual Liability, $500,000 Aggregate Products and Completed PROPERTY DAMAGE Operations $250,000 Each Occurrence $250,000 Aggregate or BODILY INJURY AND PROPERTY DAMAGE - COMBINED SINGLE LIMIT* $750,000 Each Occurrence $750,000 Aggregate *A comprehensive Catastrophe Liability Policy (Umbrella) can be used to aid in

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 16-4555-606 **Call Order:** 003 **Letting Date:** December 15, 2026

Note	Description
	achieving the minimum required limits. D. Failure on the part of the Contractor to comply with the requirements of this article will be considered sufficient cause to suspend the work, withhold estimates, and to deny the Contractor from receiving further contract awards, as provided in Article 1103.01.
410.11	*** STORM WATER POLLUTION PREVENTION PLAN *** A Storm Water Pollution Prevention Plan has been developed by the Contracting Authority for one or more projects on this contract. See the project plans (or other contract document) for specific Storm Water Pollution Prevention Plan details.
500.01	*** WINTER WORK *** The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.
FHWA-1273.09	FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023 23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.
GS-23007	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, OCTOBER 20, 2026 RELEASE

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 16-4555-606 **Call Order:** 003 **Letting Date:** December 15, 2026

Note	Description
IA26-28.4A	PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20260028 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY) Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract. *** Additional Requirement *** Contracts where the Department is the Contracting Authority: The Prime Contractor and each approved Subcontractor shall submit certified payrolls weekly to the Project Engineer. Each Contractor shall use the AASHTOWare Project Civil Rights and Labor (AWP CRL) software to electronically submit Certified Payroll Reports. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall review and approve each Subcontractor's payroll within AWP CRL. Contracts where the Department is not the Contracting Authority: The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 16-4555-606 **Call Order:** 003 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 140'- 0' X 30'- 6 15° SKEW CONTINUOUS CONCRETE SLAB BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2101-0850001 CLEARING AND GRUBBING	0.400 ACRE	_____._____		_____._____	
0020	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	2,498.000 CY	_____._____		_____._____	
0030	2104-2710020 EXCAVATION, CLASS 10, CHANNEL	3,239.000 CY	_____._____		_____._____	
0040	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	492.000 CY	_____._____		_____._____	
0050	2115-0100000 MODIFIED SUBBASE	271.000 CY	_____._____		_____._____	
0060	2121-7425020 GRANULAR SHOULDERS, TYPE B	118.000 TON	_____._____		_____._____	
0070	2122-5500090 PAVED SHOULDER, HOT MIX ASPHALT MIXTURE, 9 IN.	146.400 SY	_____._____		_____._____	
0080	2301-0690210 BRIDGE APPROACH, TWO LANE	378.900 SY	_____._____		_____._____	
0090	2301-1033100 STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 10 IN.	866.600 SY	_____._____		_____._____	
0100	2314-8257000 DUST CONTROL SURFACE TREATMENT	132.000 STA	_____._____		_____._____	
0110	2315-8275025 SURFACING, DRIVEWAY, CLASS A CRUSHED STONE	30.000 TON	_____._____		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 16-4555-606 **Call Order:** 003 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 140'- 0' X 30'- 6 15° SKEW CONTINUOUS CONCRETE SLAB BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	2401-6745625 REMOVAL OF EXISTING BRIDGE	LUMP SUM	LUMP SUM		_____	_____
0130	2401-6750001 REMOVALS, AS PER PLAN	LUMP SUM	LUMP SUM		_____	_____
0140	2402-2720000 EXCAVATION, CLASS 20	156.000 CY	_____	_____	_____	_____
0150	2403-0100010 STRUCTURAL CONCRETE (BRIDGE)	369.500 CY	_____	_____	_____	_____
0160	2404-7775005 REINFORCING STEEL, EPOXY COATED	96,521.000 LB	_____	_____	_____	_____
0170	2414-6424124 CONCRETE OPEN RAILING, TL-4	302.000 LF	_____	_____	_____	_____
0180	2501-0201042 PILES, STEEL, HP 10 X 42	2,280.000 LF	_____	_____	_____	_____
0190	2501-5478042 CONCRETE ENCASEMENT OF STEEL H PILES, HP 10 X 42 (P10L TYPE 3)	433.400 LF	_____	_____	_____	_____
0200	2501-6335010 PREBORED HOLES	140.000 LF	_____	_____	_____	_____
0210	2505-4008300 STEEL BEAM GUARDRAIL	50.000 LF	_____	_____	_____	_____
0220	2505-4008420 STEEL BEAM GUARDRAIL BARRIER TRANSITION SECTION, BA-221	4.000 EACH	_____	_____	_____	_____
0230	2505-4021010 STEEL BEAM GUARDRAIL END ANCHOR, BOLTED	4.000 EACH	_____	_____	_____	_____

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 16-4555-606 **Call Order:** 003 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 140'- 0' X 30'- 6 15° SKEW CONTINUOUS CONCRETE SLAB BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	2505-4021722 STEEL BEAM GUARDRAIL TANGENT END TERMINAL, BA-225	4.000 EACH	_____	_____	_____	_____
0250	2507-3250005 ENGINEERING FABRIC	391.800 SY	_____	_____	_____	_____
0260	2507-6800061 REVETMENT, CLASS E	2,101.900 TON	_____	_____	_____	_____
0270	2507-8029000 EROSION STONE	495.000 TON	_____	_____	_____	_____
0280	2510-6745850 REMOVAL OF PAVEMENT	1,429.400 SY	_____	_____	_____	_____
0290	2527-9263209 PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	12.300 STA	_____	_____	_____	_____
0300	2528-2518000 SAFETY CLOSURE	4.000 EACH	_____	_____	_____	_____
0310	2528-8445110 TRAFFIC CONTROL	 LUMP SUM	 LUMP SUM		_____	_____
0320	2533-4980005 MOBILIZATION	 LUMP SUM	 LUMP SUM		_____	_____
0330	2601-2634100 MULCHING	2.600 ACRE	_____	_____	_____	_____
0340	2601-2636043 SEEDING AND FERTILIZING (RURAL)	1.300 ACRE	_____	_____	_____	_____
0350	2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING	1.300 ACRE	_____	_____	_____	_____

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 16-4555-606 **Call Order:** 003 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 140'- 0' X 30'- 6 15° SKEW CONTINUOUS CONCRETE SLAB BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price Dollars	 Cents	Bid Amount Dollars	 Cents
0360	2602-0000050 SILT BASINS	4.000 EACH				
0370	2602-0000080 REMOVAL OF SILT BASINS	4.000 EACH				
0380	2602-0000312 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	840.000 LF				
0390	2602-0000351 REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	500.000 LF				
0400	2602-0010010 MOBILIZATIONS, EROSION CONTROL	3.000 EACH	600.00000		1,800.00	
0410	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	1.000 EACH	1,200.00000		1,200.00	

Section: 0001 **Total:** _____.____

Total Bid: _____.____