11/10/2026 11:02 AM

IOWA | DOT

CONTRACTS AND SPECIFICATIONS BUREAU
Proposal

Proposal ID: 33-C033-176 **Letting Date:** December 15, 2026

Call Order: 008

Proposal Work Type: RCB CULVERT REPLACEMENT - TWIN BOX

DBE Goal: 0.0%

Contracting Authority: FAYETTE COUNTY

Proposal Guaranty: $25,000.00

This proposal includes the following project(s):

Project Number:	HDP-C033(166)--71-33	**County:**	FAYETTE
Project Work Type:	RCB CULVERT REPLACEMENT - TWIN BOX	**Route:**	147TH STREET
Location:	On 147TH ST, Over UNAMED CR, S26 T93 R07		
Road System:	URBAN		
Federal Aid - Wages:	Federal Aid - Predetermined Wages are in Effect		

Project Number:	HDP-C033(176)--71-33	**County:**	FAYETTE
Project Work Type:	RCB CULVERT REPLACEMENT - TWIN BOX	**Route:**	DOGWOOD ROAD
Location:	On DOGWOOD RD, Over MINK CR, S9 T93N R07W		
Road System:	URBAN		
Federal Aid - Wages:	Federal Aid - Predetermined Wages are in Effect		

IOWA | DOT

Contracts and Specifications Bureau

Contract Time

Proposal ID: 33-C033-176 **Call Order:** 008 **Letting Date:** December 15, 2026

Site ID	Site Details				Liquidated Damages
00	Late Start Date	07/19/2027	70	WORK DAYS	$1,000.00

.

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

IOWA | DOT

Contracts and Specifications Bureau

Notes

Proposal ID: 33-C033-176 **Call Order:** 008 **Letting Date:** December 15, 2026

Notes :

There are no notes for this proposal.

11/10/2026 11:02 AM

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 33-C033-176 **Call Order:** 008 **Letting Date:** December 15, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 33-C033-176 **Call Order:** 008 **Letting Date:** December 15, 2026

Note	Description
005.1107.02	*** Revisions to Article 1107.02 *** Article 1107.02, Insurance, is amended by the following modifications and additions. This proposal note becomes null and void January 1, 2027. A. It shall be the Contractor's responsibility to have liability insurance covering all of the construction operations incident to contract completion and the Contractor must have on file with the Contracting Authority a current "Certificate of Insurance" prior to award of contract. The certificate shall identify the insurance company firm name and address, Contractor firm name, policy period, type of policy, limits of coverage, and scope of work covered (single contract or statewide). This requirement shall apply with equal force, whether the work is performed by persons employed directly by the Contractor including a subcontractor, persons employed by a subcontractor, or by an independent contractor. B. In addition to the above, the Contracting Authority shall be included as an insured party, or a separate owner's protective policy shall be filed showing the Contracting Authority as an insured party. C. The liability insurance shall be written by an insurance company (or companies) qualified to do business in Iowa. For independent contractors engaged solely in the transportation of materials, the minimum coverage provided by such insurance shall be not less than that required by Chapter 325A, Code of Iowa, for such truck operators or contract carriers as defined therein. For all other contractors, subcontractors, independent contractors, and the Contracting Authority, the minimum coverage by such insurance shall be as follows: General Liability, Including: BODILY INJURY Independent Contractors $500,000 Each Occurrence Contractual Liability, $500,000 Aggregate Products and Completed PROPERTY DAMAGE Operations $250,000 Each Occurrence $250,000 Aggregate or BODILY INJURY AND PROPERTY DAMAGE - COMBINED SINGLE LIMIT* $750,000 Each Occurrence $750,000 Aggregate *A comprehensive Catastrophe Liability Policy (Umbrella) can be used to aid in

IOWA DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 33-C033-176 **Call Order:** 008 **Letting Date:** December 15, 2026

Note	Description
	achieving the minimum required limits. D. Failure on the part of the Contractor to comply with the requirements of this article will be considered sufficient cause to suspend the work, withhold estimates, and to deny the Contractor from receiving further contract awards, as provided in Article 1103.01.
500.01	*** WINTER WORK *** The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.
FHWA-1273.09	FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023 23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.
GS-23007	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, OCTOBER 20, 2026 RELEASE

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 33-C033-176 **Call Order:** 008 **Letting Date:** December 15, 2026

Note	Description
IA26-28.4A	PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20260028 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY) Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract. *** Additional Requirement *** Contracts where the Department is the Contracting Authority: The Prime Contractor and each approved Subcontractor shall submit certified payrolls weekly to the Project Engineer. Each Contractor shall use the AASHTOWare Project Civil Rights and Labor (AWP CRL) software to electronically submit Certified Payroll Reports. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall review and approve each Subcontractor's payroll within AWP CRL. Contracts where the Department is not the Contracting Authority: The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 33-C033-176 **Call Order:** 008 **Letting Date:** December 15, 2026

SECTION: 0001

Items for a Twin 12' x 8' x 35' Reinforced Concrete Box Culvert - (166)

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price Dollars	 Cents	Bid Amount Dollars	 Cents
0010	2401-6745625 REMOVAL OF EXISTING BRIDGE	 LUMP SUM	 LUMP SUM			
0020	2402-2720000 EXCAVATION, CLASS 20	670.000 CY				
0030	2403-0100020 STRUCTURAL CONCRETE (RCB CULVERT)	148.000 CY				
0040	2404-7775005 REINFORCING STEEL, EPOXY COATED	24,685.000 LB				
0050	2418-0000010 TEMPORARY STREAM DIVERSION	1.000 EACH				
0060	2528-2518000 SAFETY CLOSURE	4.000 EACH				
0070	2528-8445110 TRAFFIC CONTROL	 LUMP SUM	 LUMP SUM			
0080	2533-4980005 MOBILIZATION	 LUMP SUM	 LUMP SUM			

Section: 0001 **Total:** _____._____

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 33-C033-176 **Call Order:** 008 **Letting Date:** December 15, 2026

SECTION: 0002

Items for Twin 12' x 10' x 35' Reinforced Concrete Box Culvert - (176)

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0090	2401-6745625 REMOVAL OF EXISTING BRIDGE	LUMP SUM	LUMP SUM			
0100	2402-2720000 EXCAVATION, CLASS 20	890.000 CY				
0110	2403-0100020 STRUCTURAL CONCRETE (RCB CULVERT)	170.400 CY				
0120	2404-7775005 REINFORCING STEEL, EPOXY COATED	27,603.000 LB				
0130	2418-0000010 TEMPORARY STREAM DIVERSION	1.000 EACH				
0140	2507-6800061 REVETMENT, CLASS E	160.000 TON				
0150	2528-2518000 SAFETY CLOSURE	4.000 EACH				
0160	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
0170	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			

Section: 0002 **Total:** _____.____

Total Bid: _____.____