IOWA | DOT

CONTRACTS AND SPECIFICATIONS BUREAU
Proposal

Proposal ID: 78-C078-210 **Letting Date:** December 15, 2026
Call Order: 019
Proposal Work Type: BRIDGE REPLACEMENT - PPCB
DBE Goal: 0.0%
Contracting Authority: POTTAWATTAMIE CO
Proposal Guaranty: $375,000.00

This proposal includes the following project(s):

Project Number: HDP-C078(210)--6B-78 **County:** POTTAWATTAMIE
Project Work Type: BRIDGE REPLACEMENT - PPCB **Route:** MAGNOLIA RD
Location: On MAGNOLIA RD, Over Mosquito Creek, from 260TH E 1 mile
Road System: FARM TO MARKET ROAD
Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

IOWA | DOT

Contracts and Specifications Bureau

Contract Time

Proposal ID: 78-C078-210 **Call Order:** 019 **Letting Date:** December 15, 2026

Site ID	Site Details				Liquidated Damages
00	Late Start Date	04/05/2027	215	WORK DAYS	$2,000.00
	Overall Site.				
01	No Start Date Specified		16	CALENDAR DAYS	$10,500.00
	Closure of I-80 WB ramps. See description below.				
02	No Start Date Specified		16	CALENDAR DAYS	$10,500.00
	Closure of I-80 EB ramps. See description below.				

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

IOWA | DOT

Contracts and Specifications Bureau

Notes

Proposal ID: 78-C078-210 **Call Order:** 019 **Letting Date:** December 15, 2026

Notes :

Site01
This is an incentive/ disincentive restricted site for a critical closure activity. Section 1111 of the Standard Specifications for Incentive/Disincentive (I/D) shall apply.
Incentive/Disincentive/Liquidated Damages per Day: $10,500
Maximum Incentive: $52,500
The Critical Closure Activity is as follows:
Closure of I-80 WB ramps, site is complete when these ramps are open with no further closures to these ramps.

Site02
This is an incentive/ disincentive restricted site for a critical closure activity. Section 1111 of the Standard Specifications for Incentive/Disincentive (I/D) shall apply.
Incentive/Disincentive/Liquidated Damages per Day: $10,500
Maximum Incentive: $52,500
The Critical Closure Activity is as follows:
Closure of I-80 EB ramps, site is complete when these ramps are open with no further closures to these ramps.

11/10/2026 11:14 AM

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 78-C078-210 **Call Order:** 019 **Letting Date:** December 15, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 78-C078-210 **Call Order:** 019 **Letting Date:** December 15, 2026

Note	Description
005.1107.02	*** Revisions to Article 1107.02 *** Article 1107.02, Insurance, is amended by the following modifications and additions. This proposal note becomes null and void January 1, 2027. A. It shall be the Contractor's responsibility to have liability insurance covering all of the construction operations incident to contract completion and the Contractor must have on file with the Contracting Authority a current "Certificate of Insurance" prior to award of contract. The certificate shall identify the insurance company firm name and address, Contractor firm name, policy period, type of policy, limits of coverage, and scope of work covered (single contract or statewide). This requirement shall apply with equal force, whether the work is performed by persons employed directly by the Contractor including a subcontractor, persons employed by a subcontractor, or by an independent contractor. B. In addition to the above, the Contracting Authority shall be included as an insured party, or a separate owner's protective policy shall be filed showing the Contracting Authority as an insured party. C. The liability insurance shall be written by an insurance company (or companies) qualified to do business in Iowa. For independent contractors engaged solely in the transportation of materials, the minimum coverage provided by such insurance shall be not less than that required by Chapter 325A, Code of Iowa, for such truck operators or contract carriers as defined therein. For all other contractors, subcontractors, independent contractors, and the Contracting Authority, the minimum coverage by such insurance shall be as follows: General Liability, Including: BODILY INJURY Independent Contractors $500,000 Each Occurrence Contractual Liability, $500,000 Aggregate Products and Completed PROPERTY DAMAGE Operations $250,000 Each Occurrence $250,000 Aggregate or BODILY INJURY AND PROPERTY DAMAGE - COMBINED SINGLE LIMIT* $750,000 Each Occurrence $750,000 Aggregate *A comprehensive Catastrophe Liability Policy (Umbrella) can be used to aid in

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 78-C078-210 **Call Order:** 019 **Letting Date:** December 15, 2026

Note	Description
	achieving the minimum required limits. D. Failure on the part of the Contractor to comply with the requirements of this article will be considered sufficient cause to suspend the work, withhold estimates, and to deny the Contractor from receiving further contract awards, as provided in Article 1103.01.
500.01	*** WINTER WORK *** The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.
DS-23057	DEVELOPMENTAL SPECIFICATIONS FOR WORK ON RAILROAD RIGHT-OF-WAY (BNSF RAILWAY)
DS-23083	DEVELOPMENTAL SPECIFICATIONS FOR FIBER REINFORCEMENT FOR STRUCTURAL CONCRETE
FHWA-1273.09	FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023 23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.
GS-23007	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, OCTOBER 20, 2026 RELEASE

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 78-C078-210 **Call Order:** 019 **Letting Date:** December 15, 2026

Note	Description
IA26-28.4A	PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20260028 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY) Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract. *** Additional Requirement *** Contracts where the Department is the Contracting Authority: The Prime Contractor and each approved Subcontractor shall submit certified payrolls weekly to the Project Engineer. Each Contractor shall use the AASHTOWare Project Civil Rights and Labor (AWP CRL) software to electronically submit Certified Payroll Reports. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall review and approve each Subcontractor's payroll within AWP CRL. Contracts where the Department is not the Contracting Authority: The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.
SS-23009	SUPPLEMENTAL SPECIFICATIONS FOR HOT MIX ASPHALT INTERLAYER

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 78-C078-210 **Call Order:** 019 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 184'-0 X 62'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2101-0850001 CLEARING AND GRUBBING	0.100 ACRE	_____._____		_____._____	
0020	2101-0850002 CLEARING AND GRUBBING	169.400 UNIT	_____._____		_____._____	
0030	2102-2625000 EMBANKMENT-IN-PLACE	7,430.000 CY	_____._____		_____._____	
0040	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	8,728.000 CY	_____._____		_____._____	
0050	2102-2710080 EXCAVATION, CLASS 10, UNSUITABLE OR UNSTABLE MATERIAL	1,000.000 CY	_____._____		_____._____	
0060	2102-5020010 OBLITERATE OLD ROADBED	7.860 STA	_____._____		_____._____	
0070	2104-2710020 EXCAVATION, CLASS 10, CHANNEL	1,271.000 CY	_____._____		_____._____	
0080	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	5,492.000 CY	_____._____		_____._____	
0090	2109-8225100 SPECIAL COMPACTION OF SUBGRADE	41.700 STA	_____._____		_____._____	
0100	2115-0100000 MODIFIED SUBBASE	2,296.000 CY	_____._____		_____._____	
0110	2121-7425010 GRANULAR SHOULDERS, TYPE A	2,548.000 TON	_____._____		_____._____	
0120	2122-5190007 PAVED SHOULDER, P.C. CONCRETE, 7 IN.	320.400 SY	_____._____		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 78-C078-210 **Call Order:** 019 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 184'-0 X 62'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	2122-5190008 PAVED SHOULDER, P.C. CONCRETE, 8 IN.	646.100 SY	_____._____		_____._____	
0140	2123-7450020 SHOULDER FINISHING, EARTH	52.030 STA	_____._____		_____._____	
0150	2301-0690201 BRIDGE APPROACH, BR-201	845.200 SY	_____._____		_____._____	
0160	2301-1033080 STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 8 IN.	11,989.900 SY	_____._____		_____._____	
0170	2301-6911722 PORTLAND CEMENT CONCRETE PAVEMENT SAMPLES	LUMP SUM	LUMP SUM		_____._____	
0180	2301-9091000 RUMBLE STRIP PANEL (PCC SURFACE)	2.000 EACH	_____._____		_____._____	
0190	2304-0101000 TEMPORARY PAVEMENT	899.300 SY	_____._____		_____._____	
0200	2312-8260051 GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE	1,311.000 TON	_____._____		_____._____	
0210	2315-8275025 SURFACING, DRIVEWAY, CLASS A CRUSHED STONE	477.000 TON	_____._____		_____._____	
0220	2401-6745355 REMOVAL OF CONCRETE FOOTINGS OF HIGHWAY SIGNS	2.000 EACH	_____._____		_____._____	
0230	2401-6745625 REMOVAL OF EXISTING BRIDGE	LUMP SUM	LUMP SUM		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 78-C078-210 **Call Order:** 019 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 184'-0 X 62'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	2402-2720000 EXCAVATION, CLASS 20	850.200 CY	_____._____		_____._____	
0250	2402-2720100 EXCAVATION, CLASS 20, FOR ROADWAY PIPE CULVERT	105.000 CY	_____._____		_____._____	
0260	2402-2721000 EXCAVATION, CLASS 21	599.000 CY	_____._____		_____._____	
0270	2403-0100010 STRUCTURAL CONCRETE (BRIDGE)	1,064.500 CY	_____._____		_____._____	
0280	2403-1000005 FIBER REINFORCEMENT FOR STRUCTURAL CONCRETE	417.500 CY	_____._____		_____._____	
0290	2403-1000010 TRIAL BATCH AND TEST PLACEMENT (FIBER REINFORCED CONCRETE)	LUMP SUM	LUMP SUM		_____._____	
0300	2404-7775000 REINFORCING STEEL	81,037.000 LB	_____._____		_____._____	
0310	2404-7775005 REINFORCING STEEL, EPOXY COATED	103,054.000 LB	_____._____		_____._____	
0320	2404-7775009 REINFORCING STEEL, STAINLESS STEEL	3,108.000 LB	_____._____		_____._____	
0330	2407-0562840 BEAMS, PRETENSIONED PRESTRESSED CONCRETE, BTB40	18.000 EACH	_____._____		_____._____	
0340	2407-0562900 BEAMS, PRETENSIONED PRESTRESSED CONCRETE, BTB100	9.000 EACH	_____._____		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 78-C078-210 **Call Order:** 019 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 184'-0 X 62'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	2408-7800000 STRUCTURAL STEEL	8,421.000 LB	_____._____		_____._____	
0360	2414-6424110 CONCRETE BARRIER RAILING	402.000 LF	_____._____		_____._____	
0370	2416-0100015 APRONS, CONCRETE, 15 IN. DIA.	2.000 EACH	_____._____		_____._____	
0380	2416-0100024 APRONS, CONCRETE, 24 IN. DIA.	10.000 EACH	_____._____		_____._____	
0390	2416-0100036 APRONS, CONCRETE, 36 IN. DIA.	12.000 EACH	_____._____		_____._____	
0400	2416-1160015 CULVERT, CONCRETE ENTRANCE PIPE, 15 IN. DIA.	28.000 LF	_____._____		_____._____	
0410	2416-1160024 CULVERT, CONCRETE ENTRANCE PIPE, 24 IN. DIA.	152.000 LF	_____._____		_____._____	
0420	2416-1160036 CULVERT, CONCRETE ENTRANCE PIPE, 36 IN. DIA.	434.000 LF	_____._____		_____._____	
0430	2416-1180024 CULVERT, CONCRETE ROADWAY PIPE, 24 IN. DIA.	59.000 LF	_____._____		_____._____	
0440	2416-1180036 CULVERT, CONCRETE ROADWAY PIPE, 36 IN. DIA.	68.000 LF	_____._____		_____._____	
0450	2416-1262024 CULVERT, CONCRETE PIPE, 2000D, TRENCHLESS, 24 IN. DIA.	173.000 LF	_____._____		_____._____	
0460	2501-0201057 PILES, STEEL, HP 10 X 57	1,950.000 LF	_____._____		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 78-C078-210 **Call Order:** 019 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 184'-0 X 62'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0470	2501-0201473 PILES, STEEL, HP 14 X 73	2,730.000 LF	_____._____		_____._____	
0480	2501-6335010 PREBORED HOLES	300.000 LF	_____._____		_____._____	
0490	2501-8400172 TEMPORARY SHORING	 LUMP SUM	LUMP SUM		_____._____	
0500	2502-8212036 SUBDRAIN, LONGITUDINAL, (SHOULDER) 6 IN. DIA.	4,624.000 LF	_____._____		_____._____	
0510	2502-8221306 SUBDRAIN OUTLET, DR-306	18.000 EACH	_____._____		_____._____	
0520	2505-4008120 REMOVAL OF STEEL BEAM GUARDRAIL	240.000 LF	_____._____		_____._____	
0530	2505-4008300 STEEL BEAM GUARDRAIL	50.000 LF	_____._____		_____._____	
0540	2505-4008420 STEEL BEAM GUARDRAIL BARRIER TRANSITION SECTION, BA-221	4.000 EACH	_____._____		_____._____	
0550	2505-4021010 STEEL BEAM GUARDRAIL END ANCHOR, BOLTED	4.000 EACH	_____._____		_____._____	
0560	2505-4021722 STEEL BEAM GUARDRAIL TANGENT END TERMINAL, BA-225	4.000 EACH	_____._____		_____._____	
0570	2505-6765006 REMOVE AND REINSTALL FORMED STEEL BEAM GUARDRAIL	146.000 LF	_____._____		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 78-C078-210 **Call Order:** 019 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 184'-0 X 62'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0580	2507-2638650 BRIDGE WING ARMORING - EROSION STONE	16.000 SY	_____._____		_____._____	
0590	2507-3250005 ENGINEERING FABRIC	1,778.000 SY	_____._____		_____._____	
0600	2507-4011100 CONCRETE GROUT FOR REVETMENT OR GABION	33.000 CY	_____._____		_____._____	
0610	2507-6800061 REVETMENT, CLASS E	2,034.000 TON	_____._____		_____._____	
0620	2510-6745850 REMOVAL OF PAVEMENT	11,057.000 SY	_____._____		_____._____	
0630	2515-2475008 DRIVEWAY, P.C. CONCRETE, 8 IN.	1,496.400 SY	_____._____		_____._____	
0640	2515-6745600 REMOVAL OF PAVED DRIVEWAY	1,727.900 SY	_____._____		_____._____	
0650	2517-4225210 RAILROAD APPROACH SECTION, P.C.C.	103.000 SY	_____._____		_____._____	
0660	2519-1002072 FENCE, CHAIN LINK, 72 IN. HEIGHT	170.000 LF	_____._____		_____._____	
0670	2519-4200120 REMOVAL OF FENCE, CHAIN LINK	213.000 LF	_____._____		_____._____	
0680	2524-6765010 REMOVE AND REINSTALL SIGN AS PER PLAN	4.000 EACH	_____._____		_____._____	
0690	2524-6765110 REMOVAL OF TYPE A SIGN	16.000 EACH	_____._____		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 78-C078-210 **Call Order:** 019 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 184'-0 X 62'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0700	2524-9081261 CONCRETE FOOTING FOR BREAKAWAY SIGN POST, 2'-8" DIA. X 6'-0"	2.000 EACH	_____._____		_____._____	
0710	2524-9130011 GUIDANCE MARKER, CHEVRON W1-8 (SPECIAL)	4.000 EACH	_____._____		_____._____	
0720	2524-9276010 PERFORATED SQUARE STEEL TUBE POSTS	164.000 LF	_____._____		_____._____	
0730	2524-9276021 PERFORATED SQUARE STEEL TUBE POST ANCHOR, BREAK-AWAY SOIL INSTALLATION	16.000 EACH	_____._____		_____._____	
0740	2524-9325001 TYPE A SIGNS, SHEET ALUMINUM	121.200 SF	_____._____		_____._____	
0750	2524-9325150 INSTALL TYPE A SIGN	16.000 EACH	_____._____		_____._____	
0760	2527-9263137 PAINTED SYMBOLS AND LEGENDS, WATERBORNE OR SOLVENT-BASED	16.000 EACH	_____._____		_____._____	
0770	2527-9263181 PAVEMENT MARKINGS REMOVED	79.500 STA	_____._____		_____._____	
0780	2527-9263209 PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	176.230 STA	_____._____		_____._____	
0790	2528-2518000 SAFETY CLOSURE	15.000 EACH	_____._____		_____._____	
0800	2528-8400048 TEMPORARY BARRIER RAIL, CONCRETE	5,812.500 LF	_____._____		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 78-C078-210 **Call Order:** 019 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 184'-0 X 62'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0810	2528-8400256 TEMPORARY TRAFFIC SIGNALS	2.000 EACH	_____._____		_____._____	
0820	2528-8445110 TRAFFIC CONTROL	 LUMP SUM	LUMP SUM		_____._____	
0830	2528-8445113 FLAGGERS	100.000 EACH	660.00000		66,000.00	
0840	2528-9290050 PORTABLE DYNAMIC MESSAGE SIGN (PDMS)	14.000 CDAY	_____._____		_____._____	
0850	2533-4980005 MOBILIZATION	 LUMP SUM	LUMP SUM		_____._____	
0860	2551-0000120 TEMP CRASH CUSHION, REDIRECTIVE (R)	15.000 EACH	_____._____		_____._____	
0870	2555-0000010 DELIVER AND STOCKPILE SALVAGED MATERIALS	 LUMP SUM	LUMP SUM		_____._____	
0880	2595-0005105 RAILROAD PROTECTIVE LIABILITY INSURANCE FOR BNSF RAILWAY CO.	 LUMP SUM	LUMP SUM		_____._____	
0890	2601-2632110 FERTILIZING	0.700 ACRE	_____._____		_____._____	
0900	2601-2634100 MULCHING	5.500 ACRE	_____._____		_____._____	
0910	2601-2636017 NATIVE GRASS SEEDING (INSTALL ONLY)	0.700 ACRE	_____._____		_____._____	
0920	2601-2636043 SEEDING AND FERTILIZING (RURAL)	2.700 ACRE	_____._____		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 78-C078-210 **Call Order:** 019 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 184'-0 X 62'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0930	2601-2636044 SEEDING AND FERTILIZING (URBAN)	2.300 ACRE	_____._____		_____._____	
0940	2602-0000030 SILT FENCE FOR DITCH CHECKS	3,020.000 LF	_____._____		_____._____	
0950	2602-0000071 REMOVAL OF SILT FENCE OR SILT FENCE FOR DITCH CHECKS	3,020.000 LF	_____._____		_____._____	
0960	2602-0000101 MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	320.000 LF	_____._____		_____._____	
0970	2602-0000312 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	4,920.000 LF	_____._____		_____._____	
0980	2602-0000351 REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	4,920.000 LF	_____._____		_____._____	
0990	2602-0010010 MOBILIZATIONS, EROSION CONTROL	1.000 EACH	600.00000		600.00	
1000	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	1.000 EACH	1,200.00000		1,200.00	

Section: 0001 **Total:** _____._____

Total Bid: _____._____