11/10/2026 11:14 AM

IOWA | DOT

CONTRACTS AND SPECIFICATIONS BUREAU
Proposal

Proposal ID: 79-C079-074 **Letting Date:** December 15, 2026
Call Order: 020
Proposal Work Type: BRIDGE REPLACEMENT - PPCB
DBE Goal: 0.0%
Contracting Authority: POWESHIEK COUNTY
Proposal Guaranty: $75,000.00

This proposal includes the following project(s):

Project Number: BROS-C079(74)--8J-79 **County:** POWESHIEK
Project Work Type: BRIDGE REPLACEMENT - PPCB **Route:** 240TH ST
Location: On 240TH ST, Over WALNUT CREEK, S1 T81 R13
Road System: LOCAL SECONDARY ROAD
Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

IOWA | DOT

Contracts and Specifications Bureau

Contract Time

Proposal ID: 79-C079-074 **Call Order:** 020 **Letting Date:** December 15, 2026

Site ID	Site Details				Liquidated Damages
00	Late Start Date	04/19/2027	120	WORK DAYS	$1,000.00

.

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

IOWA | DOT

Contracts and Specifications Bureau

Notes

Proposal ID: 79-C079-074 **Call Order:** 020 **Letting Date:** December 15, 2026

Notes :

There are no notes for this proposal.

11/10/2026 11:14 AM

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 79-C079-074 **Call Order:** 020 **Letting Date:** December 15, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.

IOWA DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 79-C079-074 **Call Order:** 020 **Letting Date:** December 15, 2026

Note	Description
005.1107.02	*** Revisions to Article 1107.02 *** Article 1107.02, Insurance, is amended by the following modifications and additions. This proposal note becomes null and void January 1, 2027. A. It shall be the Contractor's responsibility to have liability insurance covering all of the construction operations incident to contract completion and the Contractor must have on file with the Contracting Authority a current "Certificate of Insurance" prior to award of contract. The certificate shall identify the insurance company firm name and address, Contractor firm name, policy period, type of policy, limits of coverage, and scope of work covered (single contract or statewide). This requirement shall apply with equal force, whether the work is performed by persons employed directly by the Contractor including a subcontractor, persons employed by a subcontractor, or by an independent contractor. B. In addition to the above, the Contracting Authority shall be included as an insured party, or a separate owner's protective policy shall be filed showing the Contracting Authority as an insured party. C. The liability insurance shall be written by an insurance company (or companies) qualified to do business in Iowa. For independent contractors engaged solely in the transportation of materials, the minimum coverage provided by such insurance shall be not less than that required by Chapter 325A, Code of Iowa, for such truck operators or contract carriers as defined therein. For all other contractors, subcontractors, independent contractors, and the Contracting Authority, the minimum coverage by such insurance shall be as follows: General Liability, Including: BODILY INJURY Independent Contractors $500,000 Each Occurrence Contractual Liability, $500,000 Aggregate Products and Completed PROPERTY DAMAGE Operations $250,000 Each Occurrence $250,000 Aggregate or BODILY INJURY AND PROPERTY DAMAGE - COMBINED SINGLE LIMIT* $750,000 Each Occurrence $750,000 Aggregate *A comprehensive Catastrophe Liability Policy (Umbrella) can be used to aid in

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 79-C079-074 **Call Order:** 020 **Letting Date:** December 15, 2026

Note	Description
	achieving the minimum required limits. D. Failure on the part of the Contractor to comply with the requirements of this article will be considered sufficient cause to suspend the work, withhold estimates, and to deny the Contractor from receiving further contract awards, as provided in Article 1103.01.
500.01	*** WINTER WORK *** The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.
FHWA-1273.09	FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023 23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.
GS-23007	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, OCTOBER 20, 2026 RELEASE

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 79-C079-074 **Call Order:** 020 **Letting Date:** December 15, 2026

Note	Description
IA26-28.4A	PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20260028 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY) Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract. *** Additional Requirement *** Contracts where the Department is the Contracting Authority: The Prime Contractor and each approved Subcontractor shall submit certified payrolls weekly to the Project Engineer. Each Contractor shall use the AASHTOWare Project Civil Rights and Labor (AWP CRL) software to electronically submit Certified Payroll Reports. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall review and approve each Subcontractor's payroll within AWP CRL. Contracts where the Department is not the Contracting Authority: The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 79-C079-074 **Call Order:** 020 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 188'-10 X 30'-6 PRESTRESSED PRETENSIONED CONCRETE BEAM BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2101-0850001 CLEARING AND GRUBBING	0.070 ACRE	_____._____		_____._____	
0020	2102-2625000 EMBANKMENT-IN-PLACE	8,804.500 CY	_____._____		_____._____	
0030	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	3,155.700 CY	_____._____		_____._____	
0040	2104-2710020 EXCAVATION, CLASS 10, CHANNEL	5,777.600 CY	_____._____		_____._____	
0050	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	1,379.300 CY	_____._____		_____._____	
0060	2312-8260051 GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE	1,319.900 TON	_____._____		_____._____	
0070	2315-8275025 SURFACING, DRIVEWAY, CLASS A CRUSHED STONE	45.000 TON	_____._____		_____._____	
0080	2401-6745625 REMOVAL OF EXISTING BRIDGE	 LUMP SUM	 LUMP SUM		 _____._____	
0090	2402-2720000 EXCAVATION, CLASS 20	137.000 CY	_____._____		_____._____	
0100	2403-0100010 STRUCTURAL CONCRETE (BRIDGE)	272.800 CY	_____._____		_____._____	
0110	2404-7775005 REINFORCING STEEL, EPOXY COATED	69,469.000 LB	_____._____		_____._____	
0120	2407-0551259 BEAMS, PRETENSIONED PRESTRESSED CONCRETE, B59	10.000 EACH	_____._____		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 79-C079-074 **Call Order:** 020 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 188'-10 X 30'-6 PRESTRESSED PRETENSIONED CONCRETE BEAM BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	2407-0551267 BEAMS, PRETENSIONED PRESTRESSED CONCRETE, B67	5.000 EACH	_____._____		_____._____	
0140	2408-7800000 STRUCTURAL STEEL	3,149.000 LB	_____._____		_____._____	
0150	2414-6424124 CONCRETE OPEN RAILING, TL-4	411.700 LF	_____._____		_____._____	
0160	2417-0225018 APRONS, METAL, 18 IN. DIA.	3.000 EACH	_____._____		_____._____	
0170	2417-0225036 APRONS, METAL, 36 IN. DIA.	2.000 EACH	_____._____		_____._____	
0180	2417-0225060 APRONS, METAL, 60 IN. DIA.	2.000 EACH	_____._____		_____._____	
0190	2417-1040018 CULVERT, CORRUGATED METAL ENTRANCE PIPE, 18 IN. DIA.	444.000 LF	_____._____		_____._____	
0200	2417-1040036 CULVERT, CORRUGATED METAL ENTRANCE PIPE, 36 IN. DIA.	60.000 LF	_____._____		_____._____	
0210	2417-1040060 CULVERT, CORRUGATED METAL ENTRANCE PIPE, 60 IN. DIA.	52.000 LF	_____._____		_____._____	
0220	2501-0201057 PILES, STEEL, HP 10 X 57	960.000 LF	_____._____		_____._____	
0230	2501-0201473 PILES, STEEL, HP 14 X 73	1,120.000 LF	_____._____		_____._____	
0240	2501-5478073 CONCRETE ENCASEMENT OF STEEL H PILES, HP 14 X 73 (P10L TYPE 3)	249.200 LF	_____._____		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 79-C079-074 **Call Order:** 020 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 188'-10 X 30'-6 PRESTRESSED PRETENSIONED CONCRETE BEAM BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	2501-6335010 PREBORED HOLES	120.000 LF	_____._____		_____._____	
0260	2502-8215808 SUBDRAIN, TILE, 8 IN. DIA.	10.000 LF	_____._____		_____._____	
0270	2503-3775018 GATE, OUTLET CONTROL, FLAP, 18 IN.	1.000 EACH	_____._____		_____._____	
0280	2507-6800061 REVETMENT, CLASS E	1,000.400 TON	_____._____		_____._____	
0290	2519-3280000 FENCE, FIELD	1,112.000 LF	_____._____		_____._____	
0300	2519-3300400 FIELD FENCE BRACE PANELS	29.000 EACH	_____._____		_____._____	
0310	2519-4200110 REMOVAL OF FENCE, BARBED WIRE	1,983.200 LF	_____._____		_____._____	
0320	2524-9100030 OBJECT MARKER, TYPE 3	4.000 EACH	_____._____		_____._____	
0330	2526-8285010 CONSTRUCTION SURVEY, MONUMENT PRESERVATION	LUMP SUM	LUMP SUM		_____._____	
0340	2526-8285020 CONSTRUCTION SURVEY, CONTROL POINT SURVEY	LUMP SUM	LUMP SUM		_____._____	
0350	2526-8285030 CONSTRUCTION SURVEY, RIGHT OF WAY	LUMP SUM	LUMP SUM		_____._____	
0360	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 79-C079-074 **Call Order:** 020 **Letting Date:** December 15, 2026

SECTION: 0001

ITEMS FOR A 188'-10 X 30'-6 PRESTRESSED PRETENSIONED CONCRETE BEAM BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0370	2528-2518000 SAFETY CLOSURE	4.000 EACH	_____	_____	_____	_____
0380	2528-8445110 TRAFFIC CONTROL	 LUMP SUM	LUMP SUM		_____	_____
0390	2533-4980005 MOBILIZATION	 LUMP SUM	LUMP SUM		_____	_____
0400	2601-2634100 MULCHING	3.300 ACRE	_____	_____	_____	_____
0410	2601-2636043 SEEDING AND FERTILIZING (RURAL)	3.300 ACRE	_____	_____	_____	_____
0420	2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING	3.300 ACRE	_____	_____	_____	_____
0430	2602-0000020 SILT FENCE	390.000 LF	_____	_____	_____	_____
0440	2602-0000030 SILT FENCE FOR DITCH CHECKS	600.000 LF	_____	_____	_____	_____
0450	2602-0000312 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	990.000 LF	_____	_____	_____	_____
0460	2602-0010010 MOBILIZATIONS, EROSION CONTROL	2.000 EACH	600.00000		1,200.00	
0470	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	1.000 EACH	1,200.00000		1,200.00	

Section: 0001 **Total:** _____.____

Total Bid: _____.____