11/10/2026 11:02 AM

IOWA | DOT

CONTRACTS AND SPECIFICATIONS BUREAU
Proposal

Proposal ID: 39-0444-049 **Letting Date:** December 15, 2026
Call Order: 102
Proposal Work Type: PCC SIDEWALK/TRAIL
DBE Goal: 0.0%
Contracting Authority: IOWA DEPARTMENT OF TRANSPORTATION
Proposal Guaranty: $50,000.00

This proposal includes the following project(s):

Project Number: STPN-044-4(049)--2J-39 **County:** GUTHRIE
Project Work Type: PCC SIDEWALK/TRAIL **Route:** IOWA 44
Location: In Guthrie Center (ADA – District 4)
Road System: PRIMARY ROAD (non-NHS)
Federal Aid - Wages: Non-Federal Aid - Predetermined Wages are not in Effect

IOWA | DOT

Contracts and Specifications Bureau

Contract Time

Proposal ID: 39-0444-049 **Call Order:** 102 **Letting Date:** December 15, 2026

Site ID	Site Details		Liquidated Damages
00	8/10/2027	COMPLETION DATE	$1,000.00
	Concrete Work.		
01	8/30/2027	COMPLETION DATE	$1,000.00
	Final Grading, Seeding, and All Other Remaining Work..		

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

IOWA | DOT

Contracts and Specifications Bureau

Notes

Proposal ID: 39-0444-049 **Call Order:** 102 **Letting Date:** December 15, 2026

Notes :

There are no notes for this proposal.

11/10/2026 11:02 AM

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 39-0444-049 **Call Order:** 102 **Letting Date:** December 15, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 39-0444-049 **Call Order:** 102 **Letting Date:** December 15, 2026

Note	Description
005.1107.02	*** Revisions to Article 1107.02 *** Article 1107.02, Insurance, is amended by the following modifications and additions. This proposal note becomes null and void January 1, 2027. A. It shall be the Contractor's responsibility to have liability insurance covering all of the construction operations incident to contract completion and the Contractor must have on file with the Contracting Authority a current "Certificate of Insurance" prior to award of contract. The certificate shall identify the insurance company firm name and address, Contractor firm name, policy period, type of policy, limits of coverage, and scope of work covered (single contract or statewide). This requirement shall apply with equal force, whether the work is performed by persons employed directly by the Contractor including a subcontractor, persons employed by a subcontractor, or by an independent contractor. B. In addition to the above, the Contracting Authority shall be included as an insured party, or a separate owner's protective policy shall be filed showing the Contracting Authority as an insured party. C. The liability insurance shall be written by an insurance company (or companies) qualified to do business in Iowa. For independent contractors engaged solely in the transportation of materials, the minimum coverage provided by such insurance shall be not less than that required by Chapter 325A, Code of Iowa, for such truck operators or contract carriers as defined therein. For all other contractors, subcontractors, independent contractors, and the Contracting Authority, the minimum coverage by such insurance shall be as follows: General Liability, Including: BODILY INJURY Independent Contractors $500,000 Each Occurrence Contractual Liability, $500,000 Aggregate Products and Completed PROPERTY DAMAGE Operations $250,000 Each Occurrence $250,000 Aggregate or BODILY INJURY AND PROPERTY DAMAGE - COMBINED SINGLE LIMIT* $750,000 Each Occurrence $750,000 Aggregate *A comprehensive Catastrophe Liability Policy (Umbrella) can be used to aid in

IOWA DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 39-0444-049 **Call Order:** 102 **Letting Date:** December 15, 2026

Note	Description
	achieving the minimum required limits. D. Failure on the part of the Contractor to comply with the requirements of this article will be considered sufficient cause to suspend the work, withhold estimates, and to deny the Contractor from receiving further contract awards, as provided in Article 1103.01.
410.11	*** STORM WATER POLLUTION PREVENTION PLAN *** A Storm Water Pollution Prevention Plan has been developed by the Contracting Authority for one or more projects on this contract. See the project plans (or other contract document) for specific Storm Water Pollution Prevention Plan details.
DS-23032	DEVELOPMENTAL SPECIFICATIONS FOR ELECTRONIC TICKETING
GS-23007	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, OCTOBER 20, 2026 RELEASE
SS-23003	SUPPLEMENTAL SPECIFICATIONS FOR PORTLAND CEMENT CONCRETE STEPS

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 39-0444-049 **Call Order:** 102 **Letting Date:** December 15, 2026

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price Dollars	 Cents	Bid Amount Dollars	 Cents
0010	2102-2710090 EXCAVATION, CLASS 10, WASTE	470.000 CY		_____.____		_____.____
0020	2102-2713090 EXCAVATION, CLASS 13, WASTE	291.000 CY		_____.____		_____.____
0030	2401-6745650 REMOVAL OF EXISTING STRUCTURES	LUMP SUM	LUMP SUM			_____.____
0040	2435-0600010 MANHOLE ADJUSTMENT, MINOR	2.000 EACH		_____.____		_____.____
0050	2435-0600110 INTAKE ADJUSTMENT, MINOR	2.000 EACH		_____.____		_____.____
0060	2499-7000000 PCC STEPS	25.000 SF		_____.____		_____.____
0070	2510-6745850 REMOVAL OF PAVEMENT	259.800 SY		_____.____		_____.____
0080	2511-6745900 REMOVAL OF SIDEWALK	2,624.400 SY		_____.____		_____.____
0090	2511-7526004 SIDEWALK, P.C. CONCRETE, 4 IN.	2,372.400 SY		_____.____		_____.____
0100	2511-7526006 SIDEWALK, P.C. CONCRETE, 6 IN.	834.700 SY		_____.____		_____.____
0110	2511-7528101 DETECTABLE WARNINGS	397.800 SF		_____.____		_____.____
0120	2512-1725256 CURB AND GUTTER, P.C. CONCRETE, 2.5 FT.	889.600 LF		_____.____		_____.____
0130	2515-2475006 DRIVEWAY, P.C. CONCRETE, 6 IN.	999.000 SY		_____.____		_____.____

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 39-0444-049 **Call Order:** 102 **Letting Date:** December 15, 2026

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0140	2515-6745600 REMOVAL OF PAVED DRIVEWAY	926.300 SY				
0150	2516-8625000 COMBINED CONCRETE SIDEWALK AND RETAINING WALL	13.900 CY				
0160	2516-8725065 SPECIAL RETAINING WALL, AS PER PLAN	52.900 SF				
0170	2524-6765010 REMOVE AND REINSTALL SIGN AS PER PLAN	20.000 EACH				
0180	2526-8285020 CONSTRUCTION SURVEY, CONTROL POINT SURVEY	LUMP SUM	LUMP SUM			
0190	2526-8285030 CONSTRUCTION SURVEY, RIGHT OF WAY	LUMP SUM	LUMP SUM			
0200	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM			
0210	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
0220	2528-8445113 FLAGGERS	30.000 EACH	660.00000		19,800.00	
0230	2529-5070110 PATCHES, FULL-DEPTH FINISH, BY AREA	38.100 SY				
0240	2529-5070120 PATCHES, FULL-DEPTH FINISH, BY COUNT	4.000 EACH				

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 39-0444-049 **Call Order:** 102 **Letting Date:** December 15, 2026

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM		_____._____	
0260	2552-0000300 TRENCH COMPACTION TESTING	LUMP SUM	LUMP SUM		_____._____	
0270	2554-0205600 WATER SERVICE CURB STOP AND BOX, ADJUSTMENT AND INSTALLATION	10.000 EACH	_____._____		_____._____	
0280	2554-0212030 VALVE BOX REPLACEMENT	8.000 EACH	_____._____		_____._____	
0290	2599-9999005 ('EACH' ITEM) REFER TO D SHEET	2.000 EACH	_____._____		_____._____	
0300	2599-9999009 ('LINEAR FEET' ITEM) PC CONCRETE BEAM CURB	426.000 LF	_____._____		_____._____	
0310	2599-9999009 ('LINEAR FEET' ITEM) TRENCH DRAIN	6.000 LF	_____._____		_____._____	
0320	2599-9999014 ('SQUARE FEET' ITEM) REFER TO B SHEET	51.000 SF	_____._____		_____._____	
0330	2601-2634105 MULCHING, BONDED FIBER MATRIX	1.000 ACRE	_____._____		_____._____	
0340	2601-2636044 SEEDING AND FERTILIZING (URBAN)	1.000 ACRE	_____._____		_____._____	
0350	2601-2638352 SLOPE PROTECTION, WOOD EXCELSIOR MAT	114.000 SQ	_____._____		_____._____	
0360	2601-2642120 STABILIZING CROP - SEEDING AND FERTILIZING (URBAN)	1.000 ACRE	_____._____		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 39-0444-049 **Call Order:** 102 **Letting Date:** December 15, 2026

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price Dollars	 Cents	Bid Amount Dollars	 Cents
0370	2602-0000312 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	870.000 LF	_____	._____	_____	._____
0380	2602-0000351 REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	870.000 LF	_____	._____	_____	._____
0390	2602-0000500 OPEN-THROAT CURB INTAKE SEDIMENT FILTER, EC-602	40.000 LF	_____	._____	_____	._____
0400	2602-0000510 MAINTENANCE OF OPEN-THROAT CURB INTAKE SEDIMENT FILTER	7.000 EACH	_____	._____	_____	._____
0410	2602-0000520 REMOVAL OF OPEN-THROAT CURB INTAKE SEDIMENT FILTER	7.000 EACH	_____	._____	_____	._____
0420	2602-0000530 GRATE INTAKE SEDIMENT FILTER BAG, EC-604	16.000 EACH	_____	._____	_____	._____
0430	2602-0000540 MAINTENANCE OF GRATE INTAKE SEDIMENT FILTER BAG	16.000 EACH	_____	._____	_____	._____
0440	2602-0000550 REMOVAL OF GRATE INTAKE SEDIMENT FILTER BAG	16.000 EACH	_____	._____	_____	._____
0450	2602-0010010 MOBILIZATIONS, EROSION CONTROL	4.000 EACH	600.00000		2,400.00	
0460	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	1.000 EACH	1,200.00000		1,200.00	

Section: 0001 **Total:** _____._____

Total Bid: _____._____