11/10/2026 11:02 AM

IOWA | DOT

CONTRACTS AND SPECIFICATIONS BUREAU
Proposal

Proposal ID: 57-0016-044 **Letting Date:** December 15, 2026
Call Order: 104
Proposal Work Type: PCC PAVEMENT - GRADE & REPLACE
DBE Goal: 0.0%
Contracting Authority: IOWA DEPARTMENT OF TRANSPORTATION
Proposal Guaranty: $250,000.00

This proposal includes the following project(s):

Project Number: NHSX-001-6(044)--3H-57 **County:** LINN
Project Work Type: PCC PAVEMENT - GRADE & REPLACE **Route:** IOWA 1
Location: In Mt Vernon, from SCL to NCL
Road System: PRIMARY ROAD (on NHS)
Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

Project Number: NHSN-001-6(045)--2R-57 **County:** LINN
Project Work Type: PCC SIDEWALK/TRAIL **Route:** IOWA 1
Location: In Mt Vernon, from SCL to NCL
Road System: PRIMARY ROAD (on NHS)
Federal Aid - Wages: Non-Federal Aid - Predetermined Wages are in Effect

IOWA | DOT

Contracts and Specifications Bureau

Contract Time

Proposal ID: 57-0016-044 **Call Order:** 104 **Letting Date:** December 15, 2026

Site ID	Site Details				Liquidated Damages
00	Late Start Date	06/01/2027	250	WORK DAYS	$1,800.00
	Overall Site.				
01	Late Start Date	06/01/2027	100	WORK DAYS	$4,000.00
	Completion of Phases 5 and 6.				
02	Late Start Date	04/03/2028	120	WORK DAYS	$4,000.00
	Completion of Phases 1, 2, 3, and 4C.				

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

IOWA DOT

Contracts and Specifications Bureau

Notes

Proposal ID: 57-0016-044 **Call Order:** 104 **Letting Date:** December 15, 2026

Notes :

*** Site Restrictions ***

- When Site 01 is complete, working days will be suspended on Site 00 on days when all travel lanes on IA 1 are open to traffic until Site 02 begins.
- IA 1 shall not be in a detoured condition during winter. Winter is defined as Nov15-April 1.

11/10/2026 11:02 AM

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 57-0016-044 **Call Order:** 104 **Letting Date:** December 15, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.

IOWA DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 57-0016-044 **Call Order:** 104 **Letting Date:** December 15, 2026

Note	Description
005.1107.02	*** Revisions to Article 1107.02 *** Article 1107.02, Insurance, is amended by the following modifications and additions. This proposal note becomes null and void January 1, 2027. A. It shall be the Contractor's responsibility to have liability insurance covering all of the construction operations incident to contract completion and the Contractor must have on file with the Contracting Authority a current "Certificate of Insurance" prior to award of contract. The certificate shall identify the insurance company firm name and address, Contractor firm name, policy period, type of policy, limits of coverage, and scope of work covered (single contract or statewide). This requirement shall apply with equal force, whether the work is performed by persons employed directly by the Contractor including a subcontractor, persons employed by a subcontractor, or by an independent contractor. B. In addition to the above, the Contracting Authority shall be included as an insured party, or a separate owner's protective policy shall be filed showing the Contracting Authority as an insured party. C. The liability insurance shall be written by an insurance company (or companies) qualified to do business in Iowa. For independent contractors engaged solely in the transportation of materials, the minimum coverage provided by such insurance shall be not less than that required by Chapter 325A, Code of Iowa, for such truck operators or contract carriers as defined therein. For all other contractors, subcontractors, independent contractors, and the Contracting Authority, the minimum coverage by such insurance shall be as follows: General Liability, Including: BODILY INJURY Independent Contractors $500,000 Each Occurrence Contractual Liability, $500,000 Aggregate Products and Completed PROPERTY DAMAGE Operations $250,000 Each Occurrence $250,000 Aggregate or BODILY INJURY AND PROPERTY DAMAGE - COMBINED SINGLE LIMIT* $750,000 Each Occurrence $750,000 Aggregate *A comprehensive Catastrophe Liability Policy (Umbrella) can be used to aid in

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 57-0016-044 **Call Order:** 104 **Letting Date:** December 15, 2026

Note	Description
	achieving the minimum required limits. D. Failure on the part of the Contractor to comply with the requirements of this article will be considered sufficient cause to suspend the work, withhold estimates, and to deny the Contractor from receiving further contract awards, as provided in Article 1103.01.
410.11	*** STORM WATER POLLUTION PREVENTION PLAN *** A Storm Water Pollution Prevention Plan has been developed by the Contracting Authority for one or more projects on this contract. See the project plans (or other contract document) for specific Storm Water Pollution Prevention Plan details.
500.01	*** WINTER WORK *** The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.
720.121	*** POINT 25 Utility Data *** This Estimating Proposal has an attachment of the "POINT 25 Utility Data". This attachment is a part of the proposal form.
DS-23004	DEVELOPMENTAL SPECIFICATIONS FOR CONSTRUCTION PROGRESS SCHEDULE
DS-23032	DEVELOPMENTAL SPECIFICATIONS FOR ELECTRONIC TICKETING
DS-23079	DEVELOPMENTAL SPECIFICATIONS FOR PREFORMED THERMOPLASTIC PAVEMENT MARKINGS
DS-23090	DEVELOPMENTAL SPECIFICATIONS FOR MULTI-COMPONENT LIQUID PAVEMENT MARKINGS

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 57-0016-044 **Call Order:** 104 **Letting Date:** December 15, 2026

Note	Description
DS-23094	DEVELOPMENTAL SPECIFICATIONS FOR MAINTENANCE WORK ON RAILROAD RIGHT-OF-WAY (UNION PACIFIC RAILROAD)
FHWA-1273.09	FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023 23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.
GS-23007	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, OCTOBER 20, 2026 RELEASE
IA26-28.4A	PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20260028 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY) Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract. *** Additional Requirement *** Contracts where the Department is the Contracting Authority: The Prime Contractor and each approved Subcontractor shall submit certified payrolls weekly to the Project Engineer. Each Contractor shall use the AASHTOWare Project Civil Rights and Labor (AWP CRL) software to electronically submit Certified Payroll Reports. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall review and approve each Subcontractor’s payroll within AWP CRL. Contracts where the Department is not the Contracting Authority: The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-0016-044 **Call Order:** 104 **Letting Date:** December 15, 2026

SECTION: 0001

ROADWAY ITEMS - NHSX-001-6(044)--3H-57

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2101-0850002 CLEARING AND GRUBBING	99.500 UNIT	_____.____		_____.____	
0020	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	912.000 CY	_____.____		_____.____	
0030	2102-2710080 EXCAVATION, CLASS 10, UNSUITABLE OR UNSTABLE MATERIAL	850.000 CY	_____.____		_____.____	
0040	2102-2710090 EXCAVATION, CLASS 10, WASTE	8,150.000 CY	_____.____		_____.____	
0050	2102-2713090 EXCAVATION, CLASS 13, WASTE	81.000 CY	_____.____		_____.____	
0060	2105-8425005 TOPSOIL, FURNISH AND SPREAD	270.000 CY	_____.____		_____.____	
0070	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	1,050.000 CY	_____.____		_____.____	
0080	2107-0875000 COMPACTION WITH MOISTURE AND DENSITY CONTROL	850.000 CY	_____.____		_____.____	
0090	2113-0001100 SUBGRADE STABILIZATION MATERIAL, POLYMER GRID	4,896.000 SY	_____.____		_____.____	
0100	2115-0100000 MODIFIED SUBBASE	7,166.000 CY	_____.____		_____.____	
0110	2123-7450020 SHOULDER FINISHING, EARTH	94.000 STA	_____.____		_____.____	
0120	2210-0475290 MACADAM STONE BASE	1,492.000 TON	_____.____		_____.____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-0016-044 **Call Order:** 104 **Letting Date:** December 15, 2026

SECTION: 0001

ROADWAY ITEMS - NHSX-001-6(044)--3H-57

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	2301-1033095 STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 9.5 IN.	15,525.000 SY	_____	_____	_____	_____
0140	2303-0000100 HOT MIX ASPHALT MIXTURE, COMMERCIAL MIX (INCLUDES ASPHALT BINDER), AS PER PLAN	36.000 TON	_____	_____	_____	_____
0150	2315-8275025 SURFACING, DRIVEWAY, CLASS A CRUSHED STONE	1,219.000 TON	_____	_____	_____	_____
0160	2401-6745910 REMOVAL OF SIGN	1.000 EACH	_____	_____	_____	_____
0170	2416-0100012 APRONS, CONCRETE, 12 IN. DIA.	3.000 EACH	_____	_____	_____	_____
0180	2416-1202218 CULVERT, 3000D LOW CLEARANCE CONCRETE ROADWAY PIPE, EQUIVALENT DIAMETER 18 IN.	28.000 LF	_____	_____	_____	_____
0190	2435-0130148 MANHOLE, SANITARY SEWER, SW-301, 48 IN.	4.000 EACH	_____	_____	_____	_____
0200	2435-0140148 MANHOLE, STORM SEWER, SW-401, 48 IN.	1.000 EACH	_____	_____	_____	_____
0210	2435-0140160 MANHOLE, STORM SEWER, SW-401, 60 IN.	1.000 EACH	_____	_____	_____	_____
0220	2435-0140172 MANHOLE, STORM SEWER, SW-401, 72 IN.	1.000 EACH	_____	_____	_____	_____

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-0016-044 **Call Order:** 104 **Letting Date:** December 15, 2026

SECTION: 0001

ROADWAY ITEMS - NHSX-001-6(044)--3H-57

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0230	2435-0250700 INTAKE, SW-507	5.000 EACH	_____._____		_____._____	
0240	2435-0251000 INTAKE, SW-510	4.000 EACH	_____._____		_____._____	
0250	2435-0251224 INTAKE, SW-512, 24 IN.	3.000 EACH	_____._____		_____._____	
0260	2435-0400000 EXTERNAL DROP CONNECTION, SW-307	1.000 EACH	_____._____		_____._____	
0270	2435-0600010 MANHOLE ADJUSTMENT, MINOR	13.000 EACH	_____._____		_____._____	
0280	2435-0600120 INTAKE ADJUSTMENT, MAJOR	14.000 EACH	_____._____		_____._____	
0290	2435-0700020 CONNECTION TO EXISTING INTAKE	4.000 EACH	_____._____		_____._____	
0300	2502-8212034 SUBDRAIN, LONGITUDINAL, (SHOULDER) 4 IN. DIA.	8,695.000 LF	_____._____		_____._____	
0310	2502-8212108 SUBDRAIN, PLASTIC PIPE, 8 IN.	163.000 LF	_____._____		_____._____	
0320	2502-8221303 SUBDRAIN OUTLET, DR-303	31.000 EACH	_____._____		_____._____	
0330	2503-0114212 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 12 IN.	90.000 LF	_____._____		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-0016-044 **Call Order:** 104 **Letting Date:** December 15, 2026

SECTION: 0001

ROADWAY ITEMS - NHSX-001-6(044)--3H-57

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0340	2503-0114215 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 15 IN.	112.000 LF	_____._____		_____._____	
0350	2503-0114224 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 24 IN.	255.000 LF	_____._____		_____._____	
0360	2503-0200036 REMOVE STORM SEWER PIPE LESS THAN OR EQUAL TO 36 IN.	454.000 LF	_____._____		_____._____	
0370	2504-0114010 SANITARY SEWER GRAVITY MAIN, TRENCHED, POLYVINYL CHLORIDE PIPE (PVC), 10 IN.	682.000 LF	_____._____		_____._____	
0380	2504-0114012 SANITARY SEWER GRAVITY MAIN, TRENCHED, POLYVINYL CHLORIDE PIPE (PVC), 12 IN.	83.000 LF	_____._____		_____._____	
0390	2504-0200406 SANITARY SEWER SERVICE STUB, POLYVINYL CHLORIDE PIPE (PVC), 6 IN.	285.000 LF	_____._____		_____._____	
0400	2504-0240036 REMOVE SANITARY SEWER PIPE LESS THAN OR EQUAL TO 36 IN.	765.000 LF	_____._____		_____._____	
0410	2510-6745850 REMOVAL OF PAVEMENT	16,726.000 SY	_____._____		_____._____	
0420	2510-6750600 REMOVAL OF INTAKES AND UTILITY ACCESSES	13.000 EACH	_____._____		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-0016-044 **Call Order:** 104 **Letting Date:** December 15, 2026

SECTION: 0001

ROADWAY ITEMS - NHSX-001-6(044)--3H-57

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price Dollars	 Cents	Bid Amount Dollars	 Cents
0430	2511-7526004 SIDEWALK, P.C. CONCRETE, 4 IN.	247.000 SY	_____	_____	_____	_____
0440	2511-7526006 SIDEWALK, P.C. CONCRETE, 6 IN.	19.000 SY	_____	_____	_____	_____
0450	2511-7528101 DETECTABLE WARNINGS	20.000 SF	_____	_____	_____	_____
0460	2512-1725306 CURB AND GUTTER, P.C. CONCRETE, 3.0 FT.	73.000 LF	_____	_____	_____	_____
0470	2515-2475006 DRIVEWAY, P.C. CONCRETE, 6 IN.	2,522.000 SY	_____	_____	_____	_____
0480	2515-2475008 DRIVEWAY, P.C. CONCRETE, 8 IN.	281.000 SY	_____	_____	_____	_____
0490	2515-6745600 REMOVAL OF PAVED DRIVEWAY	2,852.000 SY	_____	_____	_____	_____
0500	2520-3350015 FIELD OFFICE	1.000 EACH	_____	_____	_____	_____
0510	2524-6765010 REMOVE AND REINSTALL SIGN AS PER PLAN	60.000 EACH	_____	_____	_____	_____
0520	2526-8285010 CONSTRUCTION SURVEY, MONUMENT PRESERVATION	 LUMP SUM	 LUMP SUM		_____	_____
0530	2526-8285020 CONSTRUCTION SURVEY, CONTROL POINT SURVEY	 LUMP SUM	 LUMP SUM		_____	_____
0540	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	 LUMP SUM	 LUMP SUM		_____	_____

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-0016-044 **Call Order:** 104 **Letting Date:** December 15, 2026

SECTION: 0001

ROADWAY ITEMS - NHSX-001-6(044)--3H-57

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0550	2527-9263155 PRE-CUT SYMBOLS AND LEGENDS, PREFORMED THERMOPLASTIC MARKING MATERIAL	6.000 EACH	_____	_____	_____	_____
0560	2527-9263190 SYMBOLS AND LEGENDS REMOVED	1.000 EACH	_____	_____	_____	_____
0570	2527-9263209 PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	52.670 STA	_____	_____	_____	_____
0580	2527-9263225 PERMANENT TAPE MARKINGS, PREFORMED THERMOPLASTIC MARKING MATERIAL	2.600 STA	_____	_____	_____	_____
0590	2527-9270112 GROOVES CUT FOR PAVEMENT MARKINGS	55.270 STA	_____	_____	_____	_____
0600	2527-9270120 GROOVES CUT FOR SYMBOLS AND LEGENDS	6.000 EACH	_____	_____	_____	_____
0610	2528-2518000 SAFETY CLOSURE	41.000 EACH	_____	_____	_____	_____
0620	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM		_____	_____
0630	2528-8445113 FLAGGERS	80.000 EACH	660.00000		52,800.00	
0640	2528-9290050 PORTABLE DYNAMIC MESSAGE SIGN (PDMS)	56.000 CDAY	_____	_____	_____	_____
0650	2529-2242304 CD JOINT ASSEMBLY	15.000 EACH	_____	_____	_____	_____

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-0016-044 **Call Order:** 104 **Letting Date:** December 15, 2026

SECTION: 0001

ROADWAY ITEMS - NHSX-001-6(044)--3H-57

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0660	2529-2242320 CT JOINT	10.000 EACH	_____._____		_____._____	
0670	2529-5070110 PATCHES, FULL-DEPTH FINISH, BY AREA	21.000 SY	_____._____		_____._____	
0680	2529-5070111 PATCHES, FULL-DEPTH FINISH, BY AREA (50 FEET OR GREATER IN LENGTH)	99.000 SY	_____._____		_____._____	
0690	2529-5070120 PATCHES, FULL-DEPTH FINISH, BY COUNT	4.000 EACH	_____._____		_____._____	
0700	2529-8174010 SUBBASE (PATCHES)	120.000 SY	_____._____		_____._____	
0710	2533-4980005 MOBILIZATION	 LUMP SUM	LUMP SUM		_____._____	
0720	2549-0006210 SPOT REPAIR BY PIPE REPLACEMENT, BY COUNT	1.000 EACH	_____._____		_____._____	
0730	2554-0114004 WATER MAIN, TRENCHED, POLYVINYL CHLORIDE PIPE (PVC), 4 IN.	5.000 LF	_____._____		_____._____	
0740	2554-0114006 WATER MAIN, TRENCHED, POLYVINYL CHLORIDE PIPE (PVC), 6 IN.	8.000 LF	_____._____		_____._____	
0750	2554-0114008 WATER MAIN, TRENCHED, POLYVINYL CHLORIDE PIPE (PVC), 8 IN.	3.000 LF	_____._____		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-0016-044 **Call Order:** 104 **Letting Date:** December 15, 2026

SECTION: 0001

ROADWAY ITEMS - NHSX-001-6(044)--3H-57

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0760	2554-0124008 WATER MAIN, TRENCHLESS, POLYVINYL CHLORIDE PIPE (PVC), 8 IN.	1,355.000 LF	_____.____		_____.____	
0770	2554-0202200 FITTINGS BY COUNT, DUCTILE IRON, BEND 45, 8	1.000 EACH	_____.____		_____.____	
0780	2554-0202200 FITTINGS BY COUNT, DUCTILE IRON, CAP 4	3.000 EACH	_____.____		_____.____	
0790	2554-0202200 FITTINGS BY COUNT, DUCTILE IRON, REDUCER 8X6	1.000 EACH	_____.____		_____.____	
0800	2554-0202200 FITTINGS BY COUNT, DUCTILE IRON, TEE 6X6X6	1.000 EACH	_____.____		_____.____	
0810	2554-0202200 FITTINGS BY COUNT, DUCTILE IRON, TEE 8X8X4	1.000 EACH	_____.____		_____.____	
0820	2554-0202200 FITTINGS BY COUNT, DUCTILE IRON, TEE 8X8X8	1.000 EACH	_____.____		_____.____	
0830	2554-0205110 WATER SERVICE STUB, COPPER, 1 IN.	640.000 LF	_____.____		_____.____	
0840	2554-0205650 WATER SERVICE CURB STOP, COVER ONLY	23.000 EACH	_____.____		_____.____	
0850	2554-0207004 VALVE, GATE, DIP, 4 IN.	1.000 EACH	_____.____		_____.____	
0860	2554-0207006 VALVE, GATE, DIP, 6 IN.	2.000 EACH	_____.____		_____.____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-0016-044 **Call Order:** 104 **Letting Date:** December 15, 2026

SECTION: 0001

ROADWAY ITEMS - NHSX-001-6(044)--3H-57

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price Dollars	 Cents	Bid Amount Dollars	 Cents
0870	2554-0207008 VALVE, GATE, DIP, 8 IN.	6.000 EACH	_____	_____	_____	_____
0880	2554-0210201 FIRE HYDRANT ASSEMBLY, WM-201	4.000 EACH	_____	_____	_____	_____
0890	2554-0210205 FIRE HYDRANT ASSEMBLY REMOVAL	3.000 EACH	_____	_____	_____	_____
0900	2554-0211002 FLUSHING DEVICE (BLOWOFF), 2 IN.	2.000 EACH	_____	_____	_____	_____
0910	2554-0212040 VALVE BOX ADJUSTMENT, MINOR	10.000 EACH	_____	_____	_____	_____
0920	2554-0212050 VALVE BOX REMOVAL	2.000 EACH	_____	_____	_____	_____
0930	2595-0005150 RAILROAD PROTECTIVE LIABILITY INSURANCE FOR UNION PACIFIC RAILROAD CO.	LUMP SUM	LUMP SUM		_____	_____
0940	2599-9999010 ('LUMP SUM' ITEM) CONNECTION TO EXISTING DOWNSPOUTS	LUMP SUM	LUMP SUM		_____	_____
0950	2599-9999010 ('LUMP SUM' ITEM) REMOVE AND REPLACE LANDSCAPE WALL	LUMP SUM	LUMP SUM		_____	_____
0960	2599-9999014 ('SQUARE FEET' ITEM) REMOVE AND REPLACE BRICK PAVERS	99.000 SF	_____	_____	_____	_____
0970	2601-2634105 MULCHING, BONDED FIBER MATRIX	2.000 ACRE	_____	_____	_____	_____
0980	2601-2636044 SEEDING AND FERTILIZING (URBAN)	2.000 ACRE	_____	_____	_____	_____

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-0016-044 **Call Order:** 104 **Letting Date:** December 15, 2026

SECTION: 0001

ROADWAY ITEMS - NHSX-001-6(044)--3H-57

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0990	2601-2640350 SPECIAL DITCH CONTROL, WOOD EXCELSIOR MAT	14.800 SQ	_____._____		_____._____	
1000	2602-0000150 STABILIZED CONSTRUCTION ENTRANCE, EC-303	124.000 LF	_____._____		_____._____	
1010	2602-0000309 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 9 IN. DIA.	978.000 LF	_____._____		_____._____	
1020	2602-0000351 REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	978.000 LF	_____._____		_____._____	
1030	2602-0000500 OPEN-THROAT CURB INTAKE SEDIMENT FILTER, EC-602	128.000 LF	_____._____		_____._____	
1040	2602-0000520 REMOVAL OF OPEN-THROAT CURB INTAKE SEDIMENT FILTER	24.000 EACH	_____._____		_____._____	
1050	2602-0010010 MOBILIZATIONS, EROSION CONTROL	8.000 EACH	600.00000		4,800.00	
1060	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	4.000 EACH	1,200.00000		4,800.00	

Section: 0001 **Total:** _____._____

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-0016-044 **Call Order:** 104 **Letting Date:** December 15, 2026

SECTION: 0002

SIDEWALK ITEMS - NHSN-001-6(045)--2R-57

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price Dollars	 Cents	Bid Amount Dollars	 Cents
1070	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	66.000 CY		_____._____		_____._____
1080	2511-6745900 REMOVAL OF SIDEWALK	4,674.000 SY		_____._____		_____._____
1090	2511-7526004 SIDEWALK, P.C. CONCRETE, 4 IN.	3,943.000 SY		_____._____		_____._____
1100	2511-7526006 SIDEWALK, P.C. CONCRETE, 6 IN.	2,109.000 SY		_____._____		_____._____
1110	2511-7528101 DETECTABLE WARNINGS	597.000 SF		_____._____		_____._____
1120	2533-4980005 MOBILIZATION	 LUMP SUM	 LUMP SUM			_____._____
1130	2601-2634105 MULCHING, BONDED FIBER MATRIX	1.300 ACRE		_____._____		_____._____
1140	2601-2636044 SEEDING AND FERTILIZING (URBAN)	1.300 ACRE		_____._____		_____._____
1150	2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING	1.300 ACRE		_____._____		_____._____
1160	2602-0010010 MOBILIZATIONS, EROSION CONTROL	1.000 EACH	 600.00000		 600.00	
1170	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	1.000 EACH	 1,200.00000		 1,200.00	

Section: 0002 **Total:** _____._____

Total Bid: _____._____