11/10/2026 11:19 AM

IOWA | DOT

CONTRACTS AND SPECIFICATIONS BUREAU
Proposal

Proposal ID: 88-1710-612 **Letting Date:** December 15, 2026
Call Order: 113
Proposal Work Type: PCC PAVEMENT - REPLACE
DBE Goal: 0.0%
Contracting Authority: CITY OF CRESTON
Proposal Guaranty: $62,500.00

This proposal includes the following project(s):

Project Number: STBG-SWAP-1710(612)--SG-88 **County:** UNION
Project Work Type: PCC PAVEMENT - REPLACE **Route:** NEW YORK AVENUE
Location: In the city of Creston, on New York Ave from Sumner Ave to Adams St
Road System: URBAN
Federal Aid - Wages: Non-Federal Aid - Predetermined Wages are not in Effect

IOWA | DOT

Contracts and Specifications Bureau

Contract Time

Proposal ID: 88-1710-612 **Call Order:** 113 **Letting Date:** December 15, 2026

Site ID	Site Details				Liquidated Damages
00	Late Start Date	07/12/2027	60	WORK DAYS	$1,000.00

.

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

IOWA | DOT

Contracts and Specifications Bureau

Notes

Proposal ID: 88-1710-612 **Call Order:** 113 **Letting Date:** December 15, 2026

Notes :

There are no notes for this proposal.

11/10/2026 11:19 AM

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 88-1710-612 **Call Order:** 113 **Letting Date:** December 15, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.

IOWA DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 88-1710-612 **Call Order:** 113 **Letting Date:** December 15, 2026

Note	Description
005.1107.02	*** Revisions to Article 1107.02 *** Article 1107.02, Insurance, is amended by the following modifications and additions. This proposal note becomes null and void January 1, 2027. A. It shall be the Contractor's responsibility to have liability insurance covering all of the construction operations incident to contract completion and the Contractor must have on file with the Contracting Authority a current "Certificate of Insurance" prior to award of contract. The certificate shall identify the insurance company firm name and address, Contractor firm name, policy period, type of policy, limits of coverage, and scope of work covered (single contract or statewide). This requirement shall apply with equal force, whether the work is performed by persons employed directly by the Contractor including a subcontractor, persons employed by a subcontractor, or by an independent contractor. B. In addition to the above, the Contracting Authority shall be included as an insured party, or a separate owner's protective policy shall be filed showing the Contracting Authority as an insured party. C. The liability insurance shall be written by an insurance company (or companies) qualified to do business in Iowa. For independent contractors engaged solely in the transportation of materials, the minimum coverage provided by such insurance shall be not less than that required by Chapter 325A, Code of Iowa, for such truck operators or contract carriers as defined therein. For all other contractors, subcontractors, independent contractors, and the Contracting Authority, the minimum coverage by such insurance shall be as follows: General Liability, Including: BODILY INJURY Independent Contractors $500,000 Each Occurrence Contractual Liability, $500,000 Aggregate Products and Completed PROPERTY DAMAGE Operations $250,000 Each Occurrence $250,000 Aggregate or BODILY INJURY AND PROPERTY DAMAGE - COMBINED SINGLE LIMIT* $750,000 Each Occurrence $750,000 Aggregate *A comprehensive Catastrophe Liability Policy (Umbrella) can be used to aid in

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 88-1710-612 **Call Order:** 113 **Letting Date:** December 15, 2026

Note	Description
	achieving the minimum required limits. D. Failure on the part of the Contractor to comply with the requirements of this article will be considered sufficient cause to suspend the work, withhold estimates, and to deny the Contractor from receiving further contract awards, as provided in Article 1103.01.
410.11	*** STORM WATER POLLUTION PREVENTION PLAN *** A Storm Water Pollution Prevention Plan has been developed by the Contracting Authority for one or more projects on this contract. See the project plans (or other contract document) for specific Storm Water Pollution Prevention Plan details.
500.01	*** WINTER WORK *** The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.
GS-23007	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, OCTOBER 20, 2026 RELEASE

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 88-1710-612 **Call Order:** 113 **Letting Date:** December 15, 2026

SECTION: 0001

Roadway Items

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	2,797.000 CY	_____._____		_____._____	
0020	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	1,422.000 CY	_____._____		_____._____	
0030	2107-0875000 COMPACTION WITH MOISTURE AND DENSITY CONTROL	1,550.000 CY	_____._____		_____._____	
0040	2115-0100000 MODIFIED SUBBASE	1,550.000 CY	_____._____		_____._____	
0050	2123-7450020 SHOULDER FINISHING, EARTH	26.000 STA	_____._____		_____._____	
0060	2301-1033080 STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 8 IN.	8,361.000 SY	_____._____		_____._____	
0070	2301-6911722 PORTLAND CEMENT CONCRETE PAVEMENT SAMPLES	 LUMP SUM	 LUMP SUM		 _____._____	
0080	2435-0250100 INTAKE, SW-501	2.000 EACH	_____._____		_____._____	
0090	2503-0110015 STORM SEWER GRAVITY MAIN, TRENCHED, 15 IN.	91.000 LF	_____._____		_____._____	
0100	2503-0200036 REMOVE STORM SEWER PIPE LESS THAN OR EQUAL TO 36 IN.	63.000 LF	_____._____		_____._____	
0110	2510-6745850 REMOVAL OF PAVEMENT	8,434.000 SY	_____._____		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 88-1710-612 **Call Order:** 113 **Letting Date:** December 15, 2026

SECTION: 0001

Roadway Items

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	2510-6750600 REMOVAL OF INTAKES AND UTILITY ACCESSES	2.000 EACH	_____._____		_____._____	
0130	2511-6745900 REMOVAL OF SIDEWALK	1,718.000 SY	_____._____		_____._____	
0140	2511-7526005 SIDEWALK, P.C. CONCRETE, 5 IN.	1,999.000 SY	_____._____		_____._____	
0150	2511-7526006 SIDEWALK, P.C. CONCRETE, 6 IN.	405.000 SY	_____._____		_____._____	
0160	2511-7528101 DETECTABLE WARNINGS	174.000 SF	_____._____		_____._____	
0170	2515-2475006 DRIVEWAY, P.C. CONCRETE, 6 IN.	1,329.000 SY	_____._____		_____._____	
0180	2515-6745600 REMOVAL OF PAVED DRIVEWAY	1,094.000 SY	_____._____		_____._____	
0190	2527-9263137 PAINTED SYMBOLS AND LEGENDS, WATERBORNE OR SOLVENT-BASED	2.000 EACH	_____._____		_____._____	
0200	2528-2518000 SAFETY CLOSURE	12.000 EACH	_____._____		_____._____	
0210	2528-8445110 TRAFFIC CONTROL	 LUMP SUM	 LUMP SUM		_____._____	
0220	2533-4980005 MOBILIZATION	 LUMP SUM	 LUMP SUM		_____._____	
0230	2552-0000300 TRENCH COMPACTION TESTING	 LUMP SUM	 LUMP SUM		_____._____	
0240	2554-0214000 FIRE HYDRANT ADJUSTMENT	1.000 EACH	_____._____		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 88-1710-612 **Call Order:** 113 **Letting Date:** December 15, 2026

SECTION: 0001
Roadway Items

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	2599-9999005 ('EACH' ITEM) Connect to Existing Storm Sewer	1.000 EACH	_____._____		_____._____	
0260	2601-2634100 MULCHING	1.750 ACRE	_____._____		_____._____	
0270	2601-2636044 SEEDING AND FERTILIZING (URBAN)	1.750 ACRE	_____._____		_____._____	
0280	2602-0010010 MOBILIZATIONS, EROSION CONTROL	1.000 EACH	600.00000		600.00	

Section: 0001 **Total:** _____._____

Total Bid: _____._____