IOWA DOT

CONTRACTS AND SPECIFICATIONS BUREAU
Proposal

Proposal ID: 15-C015-091 **Letting Date:** December 15, 2026
Call Order: 153
Proposal Work Type: HMA RESURFACING/COLD IN-PLACE RECYCLING
DBE Goal: 0.0%
Contracting Authority: CASS COUNTY
Proposal Guaranty: $125,000.00

This proposal includes the following project(s):

Project Number: FM-C015(91)--55-15 **County:** CASS
Project Work Type: HMA RESURFACING/COLD IN-PLACE RECYCLING **Route:** N28
Location: On N-28, from Iowa Hwy 83 N 6.7 miles to EOP near I-80 north ramp
Road System: FARM TO MARKET ROAD
Federal Aid - Wages: Non-Federal Aid - Predetermined Wages are not in Effect

IOWA | DOT

Contracts and Specifications Bureau

Contract Time

Proposal ID: 15-C015-091 **Call Order:** 153 **Letting Date:** December 15, 2026

Site ID	Site Details				Liquidated Damages
00	Late Start Date	08/16/2027	45	WORK DAYS	$1,000.00

.

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

IOWA | DOT

Contracts and Specifications Bureau

Notes

Proposal ID: 15-C015-091 **Call Order:** 153 **Letting Date:** December 15, 2026

Notes :

There are no notes for this proposal.

11/10/2026 11:02 AM

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 15-C015-091 **Call Order:** 153 **Letting Date:** December 15, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 15-C015-091 **Call Order:** 153 **Letting Date:** December 15, 2026

Note	Description
005.1107.02	*** Revisions to Article 1107.02 *** Article 1107.02, Insurance, is amended by the following modifications and additions. This proposal note becomes null and void January 1, 2027. A. It shall be the Contractor's responsibility to have liability insurance covering all of the construction operations incident to contract completion and the Contractor must have on file with the Contracting Authority a current "Certificate of Insurance" prior to award of contract. The certificate shall identify the insurance company firm name and address, Contractor firm name, policy period, type of policy, limits of coverage, and scope of work covered (single contract or statewide). This requirement shall apply with equal force, whether the work is performed by persons employed directly by the Contractor including a subcontractor, persons employed by a subcontractor, or by an independent contractor. B. In addition to the above, the Contracting Authority shall be included as an insured party, or a separate owner's protective policy shall be filed showing the Contracting Authority as an insured party. C. The liability insurance shall be written by an insurance company (or companies) qualified to do business in Iowa. For independent contractors engaged solely in the transportation of materials, the minimum coverage provided by such insurance shall be not less than that required by Chapter 325A, Code of Iowa, for such truck operators or contract carriers as defined therein. For all other contractors, subcontractors, independent contractors, and the Contracting Authority, the minimum coverage by such insurance shall be as follows: General Liability, Including: BODILY INJURY Independent Contractors $500,000 Each Occurrence Contractual Liability, $500,000 Aggregate Products and Completed PROPERTY DAMAGE Operations $250,000 Each Occurrence $250,000 Aggregate or BODILY INJURY AND PROPERTY DAMAGE - COMBINED SINGLE LIMIT* $750,000 Each Occurrence $750,000 Aggregate *A comprehensive Catastrophe Liability Policy (Umbrella) can be used to aid in

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 15-C015-091 **Call Order:** 153 **Letting Date:** December 15, 2026

Note	Description
	achieving the minimum required limits. D. Failure on the part of the Contractor to comply with the requirements of this article will be considered sufficient cause to suspend the work, withhold estimates, and to deny the Contractor from receiving further contract awards, as provided in Article 1103.01.
500.01	*** WINTER WORK *** The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.
GS-23007	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, OCTOBER 20, 2026 RELEASE

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 15-C015-091 **Call Order:** 153 **Letting Date:** December 15, 2026

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price Dollars	 Cents	Bid Amount Dollars	 Cents
0010	2121-7425020 GRANULAR SHOULDERS, TYPE B	7,000.000 TON	_____	_____	_____	_____
0020	2214-5145150 PAVEMENT SCARIFICATION, NOMINAL THICKNESS	2,946.000 SY	_____	_____	_____	_____
0030	2303-1032500 HOT MIX ASPHALT STANDARD TRAFFIC, INTERMEDIATE COURSE, 1/2 IN. MIX	7,200.000 TON	_____	_____	_____	_____
0040	2303-1033500 HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT	7,000.000 TON	_____	_____	_____	_____
0050	2303-1258283 ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC	850.000 TON	_____	_____	_____	_____
0060	2303-6911000 HOT MIX ASPHALT PAVEMENT SAMPLES	 LUMP SUM	 LUMP SUM		_____	_____
0070	2303-7000610 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR HMA MIXTURE LABORATORY VOIDS (FORMULA - BY PAY FACTOR)	20,000.000 EACH	 1.00000		 20,000.00	
0080	2303-7000620 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR HMA MIXTURE FIELD VOIDS (FORMULA - BY PAY FACTOR)	20,000.000 EACH	 1.00000		 20,000.00	
0090	2303-9091010 RUMBLE STRIP PANEL (HMA SURFACE)	2.000 EACH	_____	_____	_____	_____

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 15-C015-091 **Call Order:** 153 **Letting Date:** December 15, 2026

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0100	2318-1001100 COLD IN-PLACE RECYCLED ASPHALT PAVEMENT	78,895.000 SY	_____	_____	_____	_____
0110	2318-1001220 ASPHALT STABILIZING AGENT (FOAMED ASPHALT)	316.000 TON	_____	_____	_____	_____
0120	2527-9263209 PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	210.600 STA	_____	_____	_____	_____
0130	2528-8445110 TRAFFIC CONTROL	 LUMP SUM	 LUMP SUM		 _____	 _____
0140	2528-8445113 FLAGGERS	50.000 EACH	 660.00000		 33,000.00	
0150	2528-8445115 PILOT CARS	10.000 EACH	 990.00000		 9,900.00	
0160	2533-4980005 MOBILIZATION	 LUMP SUM	 LUMP SUM		 _____	 _____

Section: 0001 **Total:** _____._____

Total Bid: _____._____