IOWA | DOT

CONTRACTS AND SPECIFICATIONS BUREAU
Proposal

Proposal ID: 97-C097-156 **Letting Date:** December 15, 2026

Call Order: 161

Proposal Work Type: HMA RESURFACING/COLD IN-PLACE RECYCLING

DBE Goal: 0.0%

Contracting Authority: WOODBURY COUNTY

Proposal Guaranty: $250,000.00

This proposal includes the following project(s):

Project Number: L-160--73-97 **County:** WOODBURY

Project Work Type: HMA RESURFACING **Route:** LENOX AVE.

Location: On Lenox Ave NE 0.4 miles to D38 and 210th St 0.5 mi W of IA 31

Road System: LOCAL SECONDARY ROAD

Federal Aid - Wages: Non-Federal Aid - Predetermined Wages are not in Effect

Project Number: FM-C097(156)--55-97 **County:** WOODBURY

Project Work Type: HMA RESURFACING/COLD IN-PLACE RECYCLING **Route:** D38

Location: On 220th Street, from East City limits of Anthon E 6 miles to Safford Avenue

Road System: FARM TO MARKET ROAD

Federal Aid - Wages: Non-Federal Aid - Predetermined Wages are not in Effect

Project Number: FM-C097(157)--55-97 **County:** WOODBURY

Project Work Type: HMA RESURFACING/COLD IN-PLACE RECYCLING **Route:** L27

Location: On L 27, from D 50 S 6 miles to D 54

Road System: FARM TO MARKET ROAD

Federal Aid - Wages: Non-Federal Aid - Predetermined Wages are not in Effect

IOWA | DOT

Contracts and Specifications Bureau

Contract Time

Proposal ID: 97-C097-156 **Call Order:** 161 **Letting Date:** December 15, 2026

Site ID	Site Details				Liquidated Damages
00	Late Start Date	06/14/2027	90	WORK DAYS	$1,800.00

.

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

IOWA | DOT

Contracts and Specifications Bureau

Notes

Proposal ID: 97-C097-156 **Call Order:** 161 **Letting Date:** December 15, 2026

Notes :

There are no notes for this proposal.

11/10/2026 11:20 AM

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 97-C097-156 **Call Order:** 161 **Letting Date:** December 15, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 97-C097-156 **Call Order:** 161 **Letting Date:** December 15, 2026

Note	Description
005.1107.02	*** Revisions to Article 1107.02 *** Article 1107.02, Insurance, is amended by the following modifications and additions. This proposal note becomes null and void January 1, 2027. A. It shall be the Contractor's responsibility to have liability insurance covering all of the construction operations incident to contract completion and the Contractor must have on file with the Contracting Authority a current "Certificate of Insurance" prior to award of contract. The certificate shall identify the insurance company firm name and address, Contractor firm name, policy period, type of policy, limits of coverage, and scope of work covered (single contract or statewide). This requirement shall apply with equal force, whether the work is performed by persons employed directly by the Contractor including a subcontractor, persons employed by a subcontractor, or by an independent contractor. B. In addition to the above, the Contracting Authority shall be included as an insured party, or a separate owner's protective policy shall be filed showing the Contracting Authority as an insured party. C. The liability insurance shall be written by an insurance company (or companies) qualified to do business in Iowa. For independent contractors engaged solely in the transportation of materials, the minimum coverage provided by such insurance shall be not less than that required by Chapter 325A, Code of Iowa, for such truck operators or contract carriers as defined therein. For all other contractors, subcontractors, independent contractors, and the Contracting Authority, the minimum coverage by such insurance shall be as follows: General Liability, Including: BODILY INJURY Independent Contractors $500,000 Each Occurrence Contractual Liability, $500,000 Aggregate Products and Completed PROPERTY DAMAGE Operations $250,000 Each Occurrence $250,000 Aggregate or BODILY INJURY AND PROPERTY DAMAGE - COMBINED SINGLE LIMIT* $750,000 Each Occurrence $750,000 Aggregate *A comprehensive Catastrophe Liability Policy (Umbrella) can be used to aid in

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 97-C097-156 **Call Order:** 161 **Letting Date:** December 15, 2026

Note	Description
	achieving the minimum required limits. D. Failure on the part of the Contractor to comply with the requirements of this article will be considered sufficient cause to suspend the work, withhold estimates, and to deny the Contractor from receiving further contract awards, as provided in Article 1103.01.
500.01	*** WINTER WORK *** The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.
GS-23007	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, OCTOBER 20, 2026 RELEASE

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 97-C097-156 **Call Order:** 161 **Letting Date:** December 15, 2026

SECTION: 0001

ROADWAY ITEMS - L-160--73-97

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2121-7425020 GRANULAR SHOULDERS, TYPE B	326.010 TON	_____._____		_____._____	
0020	2212-0475095 CLEANING AND PREPARATION OF BASE	1.008 MILE	_____._____		_____._____	
0030	2214-5145150 PAVEMENT SCARIFICATION, NOMINAL THICKNESS	13,020.330 SY	_____._____		_____._____	
0040	2303-1032500 HOT MIX ASPHALT STANDARD TRAFFIC, INTERMEDIATE COURSE, 1/2 IN. MIX	1,077.000 TON	_____._____		_____._____	
0050	2303-1033500 HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT	1,096.000 TON	_____._____		_____._____	
0060	2303-1258343 ASPHALT BINDER, PG 58-34S, STANDARD TRAFFIC	131.000 TON	_____._____		_____._____	
0070	2303-6911000 HOT MIX ASPHALT PAVEMENT SAMPLES	 LUMP SUM	LUMP SUM		_____._____	
0080	2303-7000610 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR HMA MIXTURE LABORATORY VOIDS (FORMULA - BY PAY FACTOR)	2,173.000 EACH		1.00000		2,173.00
0090	2303-7000620 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR HMA MIXTURE FIELD VOIDS (FORMULA - BY PAY FACTOR)	2,173.000 EACH		1.00000		2,173.00

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 97-C097-156 **Call Order:** 161 **Letting Date:** December 15, 2026

SECTION: 0001

ROADWAY ITEMS - L-160--73-97

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0100	2527-9263209 PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	42.400 STA	_____	_____	_____	_____
0110	2528-2518000 SAFETY CLOSURE	4.000 EACH	_____	_____	_____	_____
0120	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM		_____	_____
0130	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
	Section: 0001		**Total:**		_____	_____

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 97-C097-156 **Call Order:** 161 **Letting Date:** December 15, 2026

SECTION: 0002

ROADWAY ITEMS - FM-C097(156)--55-97

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0140	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	320.740 CY	_____._____		_____._____	
0150	2121-7425020 GRANULAR SHOULDERS, TYPE B	2,935.000 TON	_____._____		_____._____	
0160	2212-0475095 CLEANING AND PREPARATION OF BASE	0.492 MILE	_____._____		_____._____	
0170	2214-5145150 PAVEMENT SCARIFICATION, NOMINAL THICKNESS	78,918.000 SY	_____._____		_____._____	
0180	2303-1032500 HOT MIX ASPHALT STANDARD TRAFFIC, INTERMEDIATE COURSE, 1/2 IN. MIX	7,868.000 TON	_____._____		_____._____	
0190	2303-1033500 HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT	7,383.000 TON	_____._____		_____._____	
0200	2303-1258343 ASPHALT BINDER, PG 58-34S, STANDARD TRAFFIC	915.100 TON	_____._____		_____._____	
0210	2303-6911000 HOT MIX ASPHALT PAVEMENT SAMPLES	 LUMP SUM	LUMP SUM		_____._____	
0220	2303-7000610 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR HMA MIXTURE LABORATORY VOIDS (FORMULA - BY PAY FACTOR)	15,251.000 EACH	1.00000		15,251.00	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 97-C097-156 **Call Order:** 161 **Letting Date:** December 15, 2026

SECTION: 0002

ROADWAY ITEMS - FM-C097(156)--55-97

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0230	2303-7000620 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR HMA MIXTURE FIELD VOIDS (FORMULA - BY PAY FACTOR)	15,251.000 EACH		1.00000		15,251.00
0240	2303-9091010 RUMBLE STRIP PANEL (HMA SURFACE)	2.000 EACH	_____._____		_____._____	
0250	2318-1001100 COLD IN-PLACE RECYCLED ASPHALT PAVEMENT	72,563.000 SY	_____._____		_____._____	
0260	2318-1001220 ASPHALT STABILIZING AGENT (FOAMED ASPHALT)	319.280 TON	_____._____		_____._____	
0270	2401-6745359 REMOVAL OF CONCRETE FOUNDATIONS OF LIGHT POLES	1.000 EACH	_____._____		_____._____	
0280	2401-6745635 REMOVAL OF EXISTING HANDRAIL	LUMP SUM	LUMP SUM		_____._____	
0290	2435-0251110 INTAKE, SW-511 MODIFIED	2.000 EACH	_____._____		_____._____	
0300	2435-0251310 INTAKE, SW-513 MODIFIED	1.000 EACH	_____._____		_____._____	
0310	2435-0600010 MANHOLE ADJUSTMENT, MINOR	5.000 EACH	_____._____		_____._____	
0320	2503-0111012 STORM SEWER GRAVITY MAIN, TRENCHED, HIGH DENSITY POLYETHYLENE PIPE (HDPE), 12 IN.	68.000 LF	_____._____		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 97-C097-156 **Call Order:** 161 **Letting Date:** December 15, 2026

SECTION: 0002

ROADWAY ITEMS - FM-C097(156)--55-97

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0330	2503-0200036 REMOVE STORM SEWER PIPE LESS THAN OR EQUAL TO 36 IN.	50.000 LF	_____	_____	_____	_____
0340	2505-4008120 REMOVAL OF STEEL BEAM GUARDRAIL	260.000 LF	_____	_____	_____	_____
0350	2505-4008420 STEEL BEAM GUARDRAIL BARRIER TRANSITION SECTION, BA-221	4.000 EACH	_____	_____	_____	_____
0360	2505-4021010 STEEL BEAM GUARDRAIL END ANCHOR, BOLTED	4.000 EACH	_____	_____	_____	_____
0370	2505-4021722 STEEL BEAM GUARDRAIL TANGENT END TERMINAL, BA-225	4.000 EACH	_____	_____	_____	_____
0380	2510-6745850 REMOVAL OF PAVEMENT	240.000 SY	_____	_____	_____	_____
0390	2511-7526004 SIDEWALK, P.C. CONCRETE, 4 IN.	30.000 SY	_____	_____	_____	_____
0400	2511-7526006 SIDEWALK, P.C. CONCRETE, 6 IN.	206.000 SY	_____	_____	_____	_____
0410	2511-7528101 DETECTABLE WARNINGS	150.000 SF	_____	_____	_____	_____
0420	2523-0000100 LIGHTING POLES	1.000 EACH	_____	_____	_____	_____
0430	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM		_____	_____

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 97-C097-156 **Call Order:** 161 **Letting Date:** December 15, 2026

SECTION: 0002

ROADWAY ITEMS - FM-C097(156)--55-97

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price Dollars	 Cents	Bid Amount Dollars	 Cents
0440	2527-9263209 PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	518.920 STA	_____	._____	_____	._____
0450	2528-2518000 SAFETY CLOSURE	32.000 EACH	_____	._____	_____	._____
0460	2528-8445110 TRAFFIC CONTROL	 LUMP SUM	LUMP SUM		_____	._____
0470	2528-8445113 FLAGGERS	70.000 EACH	660.00000		46,200.00	
0480	2528-8445115 PILOT CARS	35.000 EACH	990.00000		34,650.00	
0490	2533-4980005 MOBILIZATION	 LUMP SUM	LUMP SUM		_____	._____
0500	2599-9999009 ('LINEAR FEET' ITEM) STORM SEWER, TRENCHED, HDPE, 6 IN.	29.000 LF	_____	._____	_____	._____
0510	2601-2636044 SEEDING AND FERTILIZING (URBAN)	0.030 ACRE	_____	._____	_____	._____
0520	2602-0000309 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 9 IN. DIA.	100.000 LF	_____	._____	_____	._____
	Section: 0002		**Total:**		_____	._____

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 97-C097-156 **Call Order:** 161 **Letting Date:** December 15, 2026

SECTION: 0003

ROADWAY ITEMS - FM-C097(157)--55-97

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0530	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	262.000 CY	_____._____		_____._____	
0540	2121-7425020 GRANULAR SHOULDERS, TYPE B	5,124.000 TON	_____._____		_____._____	
0550	2303-1032500 HOT MIX ASPHALT STANDARD TRAFFIC, INTERMEDIATE COURSE, 1/2 IN. MIX	8,058.000 TON	_____._____		_____._____	
0560	2303-1033500 HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT	7,403.000 TON	_____._____		_____._____	
0570	2303-1258343 ASPHALT BINDER, PG 58-34S, STANDARD TRAFFIC	927.000 TON	_____._____		_____._____	
0580	2303-6911000 HOT MIX ASPHALT PAVEMENT SAMPLES	 LUMP SUM	LUMP SUM		_____._____	
0590	2303-7000610 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR HMA MIXTURE LABORATORY VOIDS (FORMULA - BY PAY FACTOR)	15,461.000 EACH		1.00000		15,461.00
0600	2303-7000620 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR HMA MIXTURE FIELD VOIDS (FORMULA - BY PAY FACTOR)	15,461.000 EACH		1.00000		15,461.00
0610	2303-9091010 RUMBLE STRIP PANEL (HMA SURFACE)	4.000 EACH	_____._____		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 97-C097-156 **Call Order:** 161 **Letting Date:** December 15, 2026

SECTION: 0003

ROADWAY ITEMS - FM-C097(157)--55-97

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price Dollars	 Cents	Bid Amount Dollars	 Cents
0620	2318-1001100 COLD IN-PLACE RECYCLED ASPHALT PAVEMENT	78,198.000 SY	_____	.____	_____	.____
0630	2318-1001220 ASPHALT STABILIZING AGENT (FOAMED ASPHALT)	258.000 TON	_____	.____	_____	.____
0640	2527-9263209 PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	733.030 STA	_____	.____	_____	.____
0650	2528-2518000 SAFETY CLOSURE	13.000 EACH	_____	.____	_____	.____
0660	2528-8445110 TRAFFIC CONTROL	 LUMP SUM	 LUMP SUM		_____	.____
0670	2533-4980005 MOBILIZATION	 LUMP SUM	 LUMP SUM		_____	.____
	Section: 0003		**Total:**		_____	.____

Total Bid: _____.____