



CONTRACTS AND SPECIFICATIONS BUREAU Proposal

Proposal ID: 77-0354-250

Letting Date: January 21, 2026

Call Order: 105

Proposal Work Type: PCC PAVEMENT - GRADE AND NEW

DBE Goal: 0.0%

Contracting Authority: IOWA DEPARTMENT OF TRANSPORTATION

Proposal Guaranty: \$1,500,000.00

This proposal includes the following project(s):

Project Number: IM-NHS-035-4(250)95--03-77

County: POLK

Project Work Type: PCC PAVEMENT - GRADE AND NEW

Route: I-35

Location: N of NE 36th St in Ankeny to N of Rest Are (NB)

Road System: INTERSTATE ROAD

Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

Project Number: IM-035-4(251)95--13-77

County: POLK

Project Work Type: TRAFFIC SIGNS

Route: I-35

Location: N of NE 36th St in Ankeny to N of Rest Are (NB)

Road System: INTERSTATE ROAD

Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

Project Number: IM-035-4(308)97--13-77

County: POLK

Project Work Type: LIGHTING

Route: I-35

Location: Co Rd F22 Interchange and Rest Area (NB)

Road System: INTERSTATE ROAD

Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

Contract Time

Proposal ID: 77-0354-250

Call Order: 105

Letting Date: January 21, 2026

Site ID	Site Details			Liquidated Damages
00	Specified Start Date	04/06/2026	15 WORK DAYS	\$3,000.00
	Stg 1A&1B SB lanes. See below.			
01		11/20/2026	COMPLETION DATE	\$3,000.00
	Stg 1A&1B for new NB lanes. See below.			
02	Late Start Date	04/15/2027	30 WORK DAYS	\$3,000.00
	Stg. 2A&2B. See below.			

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

Contracts and Specifications Bureau

Notes

Proposal ID: 77-0354-250**Call Order:** 105**Letting Date:** January 21, 2026

Notes :*****Note*****

The work on this contract will require close coordination with contract ID 77-0354-347, which was in the December 2025 letting. Both this project and the (347) project will require NB traffic to be shifted to the existing SB lanes as shown in the J sheets from the BOP of this project to the EOP of the (347) project. Shifting of NB traffic will occur simultaneously through the entire corridor and will require very close coordination between the contractors and the Engineer.

Except for Ramp C at 36th Street, all exit and entrance ramps throughout the corridor will be required to be staged to allow traffic to access I-35 at all times throughout the project. I-35 traffic will remain in the it's normal configuration through the winter months of 2025/2026.

*****Site 00*****

This site covers the traffic control work for stages 1A and 1B as shown in the J sheets to accommodate both directions of traffic in the SB lanes.

*****Site 01*****

This site covers the grading and paving work for stages 1A and 1B for the new NB lanes per J sheets. Site will be considered complete when NB lanes are open to traffic.

*****Site 02*****

This site covers work on site 2A and 2B, which includes clean up and seeding.



12/9/2025 10:24 AM

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 77-0354-250

Call Order: 105

Letting Date: January 21, 2026

Note	Description
001.2023	<p>*** STANDARD SPECIFICATIONS -- SERIES 2023 ***</p> <p>The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.</p>
005.1107.15A	<p>*** Revisions to Article 1107.15 ***</p> <p>Article 1107.15, Contractor's Responsibility for Utility Facility and Services is amended by the following modifications and additions:</p> <p>All necessary utility arrangements have not been completed. Specific information regarding the excepted work areas are shown on the attached Right of Way Certificate. Additional compensation may be allowed for delays, inconvenience, or damage sustained by the Contractor due to interference from these utility appurtenances or their operation or relocation that occurs past the Expected Date of Physical Occupancy shown on the Right of Way Certificate.</p>

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 77-0354-250

Call Order: 105

Letting Date: January 21, 2026

Note	Description
005.23005.01	<p>*** REVISIONS TO GS-23005 ***</p> <p>1102.17, B, 2, Equal Employment Opportunity.</p> <p>Replace the Article: In hiring and employment practices, the absence of discrimination on the basis of race, religion, sex, sexual orientation, color, national origin, age, disability, or other protected classification under Federal, state, or local law.</p> <p>1102.17, B, 8, Segregated Facilities.</p> <p>Replace the first sentence: Employee facilities that are separated on the basis of race, religion, color, national origin, age, sex, sexual orientation, or disability either by explicit directive or by fact because of habit, local custom, or any other reason.</p> <p>1102.17, C, 1, The EEO/AA Operating Statement.</p> <p>Replace the Article: "It is the policy of this Company to ensure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, sexual orientation, color, national origin, age, or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, pre-apprenticeship, and/or on-the-job training."</p> <p>1102.17, F, Personnel Actions.</p> <p>Replace the first sentence: Wages, working conditions, employee benefits, and personnel actions of every type including hiring, upgrading, promotion, transfer, demotion, layoff, and termination shall be made without regard to race, color, religion, sex, sexual orientation, national origin, age, or disability.</p>
410.11	<p>*** STORM WATER POLLUTION PREVENTION PLAN ***</p> <p>A Storm Water Pollution Prevention Plan has been developed by the Contracting Authority for one or more projects on this contract. See the project plans (or other contract document) for specific Storm Water Pollution Prevention Plan details.</p>

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 77-0354-250

Call Order: 105

Letting Date: January 21, 2026

Note	Description
500.01	*** WINTER WORK *** The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.
DS-23032	DEVELOPMENTAL SPECIFICATIONS FOR ELECTRONIC TICKETING
DS-23060	DEVELOPMENTAL SPECIFICATIONS FOR DIAMOND GRINDING RUMBLE STRIPS
DS-23069	DEVELOPMENTAL SPECIFICATIONS FOR MULTI-COMPONENT LIQUID PAVEMENT MARKINGS
DS-23071	DEVELOPMENTAL SPECIFICATIONS FOR MOBILE REFLECTOMETER MEASUREMENTS
DS-23077	DEVELOPMENTAL SPECIFICATIONS FOR QUALITY MANAGEMENT CONCRETE (QM-C)
FHWA-1273.09	FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023 23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.
GS-23005	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION



12/9/2025 10:24 AM

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 77-0354-250

Call Order: 105

Letting Date: January 21, 2026

Note	Description
IA25-81.0	<p>PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20250081 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY)</p> <p>Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract.</p> <p>*** Additional Requirement ***</p> <p>The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.</p>



12/9/2025 10:24 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 77-0354-250

Call Order: 105

Letting Date: January 21, 2026

SECTION: 0001

Traffic Sign Items - IM-035-4(251)95--13-77

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2401-6745355 REMOVAL OF CONCRETE FOOTINGS OF HIGHWAY SIGNS	17.000 EACH				
0020	2402-2720000 EXCAVATION, CLASS 20	228.200 CY				
0030	2403-0100000 STRUCTURAL CONCRETE (MISCELLANEOUS)	67.600 CY				
0040	2404-7775005 REINFORCING STEEL, EPOXY COATED	12,702.000 LB				
0050	2423-1051300 STEEL CANTILEVER SIGN TRUSS, 30 FT. ARM	1.000 EACH				
0060	2423-1051360 STEEL CANTILEVER SIGN TRUSS, 36 FT. ARM	1.000 EACH				
0070	2524-6765210 REMOVAL OF TYPE A SIGN ASSEMBLY	10.000 EACH				
0080	2524-6765220 REMOVAL OF TYPE B SIGN ASSEMBLY	17.000 EACH				
0090	2524-9081275 CONCRETE FOOTING FOR BREAKAWAY SIGN POST, 2'-8" DIA. X 7'-6"	12.000 EACH				
0100	2524-9081290 CONCRETE FOOTING FOR BREAKAWAY SIGN POST, 2'-8" DIA. X 9'-0"	3.000 EACH				



12/9/2025 10:24 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 77-0354-250

Call Order: 105

Letting Date: January 21, 2026

SECTION: 0001

Traffic Sign Items - IM-035-4(251)95--13-77

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0110	2524-9089100 DELINEATOR, RIGID - TYPE I	14.000 EACH				
0120	2524-9089110 DELINEATOR, RIGID - TYPE IA	74.000 EACH				
0130	2524-9089200 DELINEATOR, RIGID - TYPE II	80.000 EACH				
0140	2524-9210007 REFERENCE LOCATION SIGNS	76.000 EACH				
0150	2524-9276010 PERFORATED SQUARE STEEL TUBE POSTS	188.000 LF				
0160	2524-9276027 PERFORATED SQUARE STEEL TUBE POST ANCHOR, TRIANGULAR SLIP BASE ASSEMBLY	30.000 EACH				
0170	2524-9281210 STEEL BREAKAWAY SIGN POSTS FOR TYPE A OR B SIGNS, W 8 X 21	201.200 LF				
0180	2524-9281426 STEEL BREAKAWAY SIGN POSTS FOR TYPE A OR B SIGNS, W 12 X 26	69.300 LF				
0190	2524-9325001 TYPE A SIGNS, SHEET ALUMINUM	355.500 SF				
0200	2524-9380001 TYPE B SIGNS, EXTRUDED ALUMINUM STRUCTURAL PANEL	1,029.400 SF				
0210	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			



12/9/2025 10:24 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 77-0354-250

Call Order: 105

Letting Date: January 21, 2026

SECTION: 0001

Traffic Sign Items - IM-035-4(251)95--13-77

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0220	2599-9999005 (‘EACH’ ITEM) ANCHOR BOLT ASSEMBLY - INSTALL AND SURVEY	2.000 EACH	_____.	_____	_____.	_____
0230	2599-9999005 (‘EACH’ ITEM) EXIT GORE DELINEATOR POST	14.000 EACH	_____.	_____	_____.	_____
0240	2599-9999005 (‘EACH’ ITEM) MASSH-400 SIGN POST	5.000 EACH	_____.	_____	_____.	_____
0250	2599-9999008 (‘POUNDS’ ITEM) ANCHOR BOLT ASSEMBLY - FURNISH	4,126.000 LB	_____.	_____	_____.	_____
Section: 0001			Total:		_____.	_____



12/9/2025 10:24 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 77-0354-250

Call Order: 105

Letting Date: January 21, 2026

SECTION: 0002

Lighting Items - IM-035-4(308)97--13-77

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0260	2401-6745359 REMOVAL OF CONCRETE FOUNDATIONS OF LIGHT POLES	8.000 EACH				
0270	2401-6745765 REMOVAL OF LIGHT POLES	8.000 EACH				
0280	2523-0000100 LIGHTING POLES	20.000 EACH				
0290	2523-0000200 ELECTRICAL CIRCUITS	7,700.000 LF				
0300	2523-0000310 HANDHOLES AND JUNCTION BOXES	6.000 EACH				
0310	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
0320	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
0330	2555-0000010 DELIVER AND STOCKPILE SALVAGED MATERIALS	LUMP SUM	LUMP SUM			
0340	2599-9999010 (‘LUMP SUM’ ITEM) DEMOLITION OF ELECTRIC CIRCUITS	LUMP SUM	LUMP SUM			
Section: 0002			Total:			



12/9/2025 10:24 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 77-0354-250

Call Order: 105

Letting Date: January 21, 2026

SECTION: 0003

Roadway Items - IM-NHS-035-4(250)95--03-77

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	2101-0850001 CLEARING AND GRUBBING	21.760 ACRE				
0360	2102-0425070 SPECIAL BACKFILL	271.000 TON				
0370	2102-2624980 CONTRACTOR FURNISHED SELECT TREATMENT	113,436.500 CY				
0380	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	19,583.500 CY				
0390	2102-2710090 EXCAVATION, CLASS 10, WASTE	149,195.000 CY				
0400	2102-2712015 EXCAVATION, CLASS 12, BOULDERS OR ROCK FRAGMENTS	25.000 CY				
0410	2102-4560000 LOCATING TILE LINES	509.000 STA				
0420	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	38,422.000 CY				
0430	2107-0875100 COMPACTION WITH MOISTURE CONTROL	14,949.000 CY				
0440	2111-8174100 GRANULAR SUBBASE	179,954.400 SY				
0450	2113-0001100 SUBGRADE STABILIZATION MATERIAL, POLYMER GRID	165,660.600 SY				
0460	2115-0100000 MODIFIED SUBBASE	6,321.100 CY				



12/9/2025 10:24 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 77-0354-250

Call Order: 105

Letting Date: January 21, 2026

SECTION: 0003

Roadway Items - IM-NHS-035-4(250)95--03-77

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0470	2122-5190008 PAVED SHOULDER, P.C. CONCRETE, 8 IN.	496.600 SY				
0480	2122-5190115 PAVED SHOULDER, P.C. CONCRETE, 11.5 IN.	8,731.600 SY				
0490	2123-7450000 SHOULDER CONSTRUCTION, EARTH	429.400 STA				
0500	2210-0475290 MACADAM STONE BASE	49.190 TON				
0510	2301-0690203 BRIDGE APPROACH, BR-203	666.600 SY				
0520	2301-1004115 STANDARD OR SLIP-FORM PORTLAND CEMENT CONCRETE PAVEMENT, QM-C, CLASS 3I DURABILITY, 11.5 IN.	180,548.000 SY				
0530	2301-7000110 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR PCC PAVEMENT THICKNESS (BY SCHEDULE)	211,241.160 EACH		1.00000	211,241.16	
0540	2304-0100000 DETOUR PAVEMENT	544.400 SY				
0550	2312-8260051 GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE	28.980 TON				
0560	2317-7000110 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR PCC PAVEMENT SMOOTHNESS (BY SCHEDULE)	135,411.000 EACH		1.00000	135,411.00	



12/9/2025 10:24 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 77-0354-250

Call Order: 105

Letting Date: January 21, 2026

SECTION: 0003

Roadway Items - IM-NHS-035-4(250)95--03-77

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0570	2401-6745650 REMOVAL OF EXISTING STRUCTURES	LUMP SUM	LUMP SUM			
0580	2502-8212034 SUBDRAIN, LONGITUDINAL, (SHOULDER) 4 IN. DIA.	62,109.200 LF				
0590	2502-8221306 SUBDRAIN OUTLET, DR-306	302.000 EACH				
0600	2505-4008120 REMOVAL OF STEEL BEAM GUARDRAIL	315.000 LF				
0610	2505-4008130 REMOVAL OF CABLE GUARDRAIL	310.000 LF				
0620	2505-4008300 STEEL BEAM GUARDRAIL	325.000 LF				
0630	2505-4021020 STEEL BEAM GUARDRAIL END ANCHOR, W-BEAM	3.000 EACH				
0640	2505-4021720 STEEL BEAM GUARDRAIL TANGENT END TERMINAL, BA-205	3.000 EACH				
0650	2505-6000111 HIGH TENSION CABLE GUARDRAIL	25,398.500 LF				
0660	2505-6000121 HIGH TENSION CABLE GUARDRAIL, END ANCHOR	9.000 EACH				
0670	2510-6745850 REMOVAL OF PAVEMENT	75,159.600 SY				
0680	2520-3350010 FIELD LABORATORY	1.000 EACH				



12/9/2025 10:24 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 77-0354-250

Call Order: 105

Letting Date: January 21, 2026

SECTION: 0003

Roadway Items - IM-NHS-035-4(250)95--03-77

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0690	2526-8285000 CONSTRUCTION SURVEY	LUMP SUM	LUMP SUM			
0700	2527-5000005 MOBILE REFLECTOMETER MEASUREMENTS	235,285.000 LF				
0710	2527-9263181 PAVEMENT MARKINGS REMOVED	1,073.970 STA				
0720	2527-9263209 PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	1,375.690 STA				
0730	2527-9263216 PAINTED PAVEMENT MARKINGS, MULTI-COMPONENT LIQUID	1,586.620 STA				
0740	2527-9263231 REMOVABLE TAPE MARKINGS, WET RETROREFLECTIVE	524.070 STA				
0750	2527-9270112 GROOVES CUT FOR PAVEMENT MARKINGS	1,586.620 STA				
0760	2528-2518000 SAFETY CLOSURE	25.000 EACH				
0770	2528-3800000 MODULAR GLARE SCREEN SYSTEM	28,506.000 LF				
0780	2528-8400048 TEMPORARY BARRIER RAIL, CONCRETE	43,735.900 LF				
0790	2528-8400157 TEMPORARY FLOODLIGHTING LUMINAIRE	16.000 EACH				



12/9/2025 10:24 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 77-0354-250

Call Order: 105

Letting Date: January 21, 2026

SECTION: 0003

Roadway Items - IM-NHS-035-4(250)95--03-77

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0800	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
0810	2528-9109020 TEMPORARY LANE SEPARATOR SYSTEM	6,065.000 LF				
0820	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
0830	2548-0000250 DIAMOND GROUND SHOULDER RUMBLE STRIPS, PCC SURFACE	1,183.330 STA				
0840	2551-0000130 TEMP CRASH CUSHION, SEVERE USE (SU)	15.000 EACH				
Section: 0003			Total:			



12/9/2025 10:24 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 77-0354-250

Call Order: 105

Letting Date: January 21, 2026

SECTION: 0004

Drainage Items - IM-NHS-035-4(250)95--03-77

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0850	2402-0425040 FLOODED BACKFILL	2.000 CY	_____	_____	_____	_____
0860	2402-2720000 EXCAVATION, CLASS 20	41.000 CY	_____	_____	_____	_____
0870	2416-0101036 REMOVE AND REINSTALL CONCRETE PIPE APRONS LESS THAN OR EQUAL TO 36 IN.	9.000 EACH	_____	_____	_____	_____
0880	2416-1180024 CULVERT, CONCRETE ROADWAY PIPE, 24 IN. DIA.	20.000 LF	_____	_____	_____	_____
0890	2599-9999009 (‘LINEAR FEET’ ITEM) REMOVAL OF CULVERT	55.000 LF	_____	_____	_____	_____
Section: 0004			Total:		_____	_____



12/9/2025 10:24 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 77-0354-250

Call Order: 105

Letting Date: January 21, 2026

SECTION: 0005

Roadside Items - IM-NHS-035-4(250)95--03-77

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0900	2507-3250005 ENGINEERING FABRIC	2,913.200 SY				
0910	2507-6800061 REVTMENT, CLASS E	832.100 TON				
0920	2507-8029000 EROSION STONE	1,009.800 TON				
0930	2601-2634100 MULCHING	92.000 ACRE				
0940	2601-2636043 SEEDING AND FERTILIZING (RURAL)	30.800 ACRE				
0950	2601-2638352 SLOPE PROTECTION, WOOD EXCELSIOR MAT	251.000 SQ				
0960	2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING	30.600 ACRE				
0970	2601-2643110 WATERING FOR SOD, SPECIAL DITCH CONTROL, OR SLOPE PROTECTION	50.200 MGAL		75.00000		3,765.00
0980	2601-2643300 MOBILIZATION FOR WATERING	3.000 EACH		450.00000		1,350.00
0990	2602-0000020 SILT FENCE	31,888.000 LF				
1000	2602-0000030 SILT FENCE FOR DITCH CHECKS	2,346.000 LF				
1010	2602-0000050 SILT BASINS	56.000 EACH				



12/9/2025 10:24 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 77-0354-250

Call Order: 105

Letting Date: January 21, 2026

SECTION: 0005

Roadside Items - IM-NHS-035-4(250)95--03-77

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1020	2602-0000071 REMOVAL OF SILT FENCE OR SILT FENCE FOR DITCH CHECKS	34,234.000 LF	_____	_____	_____	_____
1030	2602-0000101 MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	3,423.000 LF	_____	_____	_____	_____
1040	2602-0000150 STABILIZED CONSTRUCTION ENTRANCE, EC-303	1,000.000 LF	_____	_____	_____	_____
1050	2602-0000312 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	2,980.000 LF	_____	_____	_____	_____
1060	2602-0000320 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 20 IN. DIA.	2,980.000 LF	_____	_____	_____	_____
1070	2602-0000351 REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	5,960.000 LF	_____	_____	_____	_____
1080	2602-0010010 MOBILIZATIONS, EROSION CONTROL	1.000 EACH		600.00000		600.00
1090	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	1.000 EACH		1,200.00000		1,200.00

Section: 0005

Total: _____

Total Bid: _____