



**CONTRACTS AND SPECIFICATIONS BUREAU
Proposal**

Proposal ID: 97-0201-204

Letting Date: January 21, 2026

Call Order: 110

Proposal Work Type: PCC PAVEMENT - REPLACE

DBE Goal: 0.0%

Contracting Authority: IOWA DEPARTMENT OF TRANSPORTATION

Proposal Guaranty: \$1,250,000.00

This proposal includes the following project(s):

Project Number: NHSX-020-1(204)--3H-97

County: WOODBURY

Project Work Type: PCC PAVEMENT - REPLACE

Route: U.S. 20

Location: 0.4 mi E of Franklin Ave to E of Humboldt Ave near Merville (WB)

Road System: PRIMARY ROAD (on NHS)

Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

Contracts and Specifications Bureau

Contract Time

Proposal ID: 97-0201-204

Call Order: 110

Letting Date: January 21, 2026

Site ID	Site Details			Liquidated Damages
00	Late Start Date	04/13/2026	60 WORK DAYS	\$2,500.00
Overall Site. See description below.				
01	Late Start Date	04/13/2026	130 WORK DAYS	\$2,500.00
Stage1, 2A & 2B. See below.				
02	Late Start Date	04/19/2027	110 WORK DAYS	\$2,500.00
Stages 3A & 3B. See below.				
03	No Start Date Specified		28 CALENDAR DAYS	\$1,000.00
Partial Closure IA 140/US20, Stg. 2A See below.				
04	No Start Date Specified		28 CALENDAR DAYS	\$1,000.00
Closure of Grundy Ave N. Stg 2A. See below.				
05	No Start Date Specified		28 CALENDAR DAYS	\$1,000.00
Partial Closure 1A 40 & IA140/US 20, Stg. 2B See below.				
06	No Start Date Specified		28 CALENDAR DAYS	\$2,500.00
Closure of Grundy Ave S, Stg 3A. See below.				
07	No Start Date Specified		28 CALENDAR DAYS	\$1,000.00
Closure of Merville Black Top. Stg. 3A See below.				



12/9/2025 10:25 AM

Contracts and Specifications Bureau

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

Contracts and Specifications Bureau

Notes

Proposal ID: 97-0201-204**Call Order:** 110**Letting Date:** January 21, 2026

Notes :*****Winter Work*****

Winter Free time will be allowed in the winter of 2025/2026 and 2026/2027. However, no lane closures, lane shifts, sideroad closures, or shoulder closures will be allowed during the winter free time without permission from the engineer.

No Winter Free time will be allowed during the winter of 2026/2027 if site 01 is not complete and traffic returned to normal operations for the winter.

*****Site 00*****

This site is for work not covered in site 01 or site 02. This includes erosion control, seeding, and other items that do not require US 20 lane closure, shoulder closure, or sideroad closure. Days will not be charged to Site 00 if days are being charged to Site 01 or Site 02. This site will be suspended at the end of the 2026 construction season once work stops, and then start again once work resumes in 2027.

*****Site 01*****

This site is for work in stages 1, 2A and 2B. This site requires all US 20 lanes, shoulders, turn lanes, median crossings, side road connections, and entrances to be completed and open to traffic with no further closures. All painting, guardrail, shoulders, and signs need to be in place for the site to be considered complete.

*****Site 02*****

This site is for work in stages 3A and 3B. This site requires all US 20 lanes, shoulders, turn lanes, median crossings, side road connections, and entrances to be completed and open to traffic with no further closures. All painting, guardrail, shoulders, and signs need to be in place for the site to be considered complete.

*****Site 03*****

This site is an Incentive/Disincentive site per Section 1111 of the Standard Specifications with the following details. Incentive/Disincentive/Liquidated Damages \$1,000 per day. This site covers the partial closure of IA 140 and the IA 140/US 20 intersection in stage 2A. The critical activity is the completion of IA 140 and the IA 140/US 20 interchange in stage 2A. The completion of this site requires the work on IA 140 and the IA 140/US interchange in stage 2A is completed, and IA 140 traffic is shifted back to the original lane configuration, and the intersection is opened. All shoulders, painting, and signs must be completed.

See Proposal Specification List note 656.0217 for the rest of the sites.



12/9/2025 10:25 AM

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 97-0201-204

Call Order: 110

Letting Date: January 21, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 97-0201-204

Call Order: 110

Letting Date: January 21, 2026

Note	Description
005.23005.01	<p>*** REVISIONS TO GS-23005 ***</p> <p>1102.17, B, 2, Equal Employment Opportunity.</p> <p>Replace the Article: In hiring and employment practices, the absence of discrimination on the basis of race, religion, sex, sexual orientation, color, national origin, age, disability, or other protected classification under Federal, state, or local law.</p> <p>1102.17, B, 8, Segregated Facilities.</p> <p>Replace the first sentence: Employee facilities that are separated on the basis of race, religion, color, national origin, age, sex, sexual orientation, or disability either by explicit directive or by fact because of habit, local custom, or any other reason.</p> <p>1102.17, C, 1, The EEO/AA Operating Statement.</p> <p>Replace the Article: "It is the policy of this Company to ensure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, sexual orientation, color, national origin, age, or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, pre-apprenticeship, and/or on-the-job training."</p> <p>1102.17, F, Personnel Actions.</p> <p>Replace the first sentence: Wages, working conditions, employee benefits, and personnel actions of every type including hiring, upgrading, promotion, transfer, demotion, layoff, and termination shall be made without regard to race, color, religion, sex, sexual orientation, national origin, age, or disability.</p>
410.11	<p>*** STORM WATER POLLUTION PREVENTION PLAN ***</p> <p>A Storm Water Pollution Prevention Plan has been developed by the Contracting Authority for one or more projects on this contract. See the project plans (or other contract document) for specific Storm Water Pollution Prevention Plan details.</p>



12/9/2025 10:25 AM

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 97-0201-204

Call Order: 110

Letting Date: January 21, 2026

Note	Description
500.2027	*** NO WINTER FREE TIME *** The free time allowed between November 15 and April 1 will not be permitted on this project during the winter of 2027-2028. The Contractor shall work during the winter on all working days as defined in article 1101.03 'working day'.

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 97-0201-204

Call Order: 110

Letting Date: January 21, 2026

Note	Description
656.0217	<p>*** Site 04 ***</p> <p>This site is an Incentive/Disincentive site per Section 1111 of the Standard Specifications with the following details. Incentive/Disincentive/Liquidated Damages \$1,000 per day. This site covers the closure of Grundy Ave N in stage 2A. The critical closure is the completion of Gundy Ave N and the portion of US 20 that allows access to US 20 in stage 2A. The completion of this site requires the work on Grundy Ave N and the portion of U20 that allows access to US 20 in stage 2A is completed, and Grundy Ave N is open to US 20. Appropriate traffic control must be in place for the site to be considered complete.</p> <p>*** Site 05 ***</p> <p>This site is an Incentive/Disincentive site per Section 1111 of the Standard Specifications with the following details. Incentive/Disincentive/Liquidated Damages \$1,000 per day. This site covers the partial closure of IA 140 and the IA 140/US 20 intersection in stage 2B. The critical activity is the completion of IA 140 and the IA 140/US 20 interchange in stage 2B. The completion of this site requires the work on IA 140 and the IA 140/US interchange in stage 2B is completed, and IA 140 traffic is shifted back to the original lane configuration, and the intersection is opened. All shoulders, painting, and signs must be completed.</p> <p>*** Site 06 ***</p> <p>This site is an Incentive/Disincentive site per Section 1111 of the Standard Specifications with the following details. Incentive/Disincentive/Liquidated Damages \$2,500 per day. This site covers the closure of Grundy Ave S in stage 3A. The critical closure is the completion of Gundy Ave S and the portion of US 20 that allows access to US 20 in stage 3A. The completion of this site requires the work on Grundy Ave S, and the portion of U20 that allows access to US 20 in stage 2A is completed, and Grundy Ave S is open to US 20. Appropriate traffic control must be in place for the site to be considered complete.</p> <p>*** Site 07 ***</p> <p>This site is an Incentive/Disincentive site per Section 1111 of the Standard Specifications with the following details. Incentive/Disincentive/Liquidated Damages \$1,000 per day. This site covers the closure of Movable Black Top in stage 3A. The critical closure is the completion of Movable Black Top and the portion of US 20 that allows access to US 20 in stage 3A. The completion of this site requires the work on Movable Black Top and the portion of U20 that allows access to US 20 in stage 2A is completed, and Movable Black Top is open to US 20. Appropriate traffic control must be in place for the site to be considered complete.</p>



12/9/2025 10:25 AM

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 97-0201-204

Call Order: 110

Letting Date: January 21, 2026

Note	Description
DS-23032	DEVELOPMENTAL SPECIFICATIONS FOR ELECTRONIC TICKETING
DS-23060	DEVELOPMENTAL SPECIFICATIONS FOR DIAMOND GRINDING RUMBLE STRIPS
DS-23077	DEVELOPMENTAL SPECIFICATIONS FOR QUALITY MANAGEMENT CONCRETE (QM-C)
DS-23079	DEVELOPMENTAL SPECIFICATIONS FOR PREFORMED THERMOPLASTIC PAVEMENT MARKINGS
FHWA-1273.09	FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023 23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.
GS-23005	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION
IA25-81.0	<p>PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20250081 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY)</p> <p>Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract.</p> <p>*** Additional Requirement ***</p> <p>The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.</p>



12/9/2025 10:25 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 97-0201-204

Call Order: 110

Letting Date: January 21, 2026

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2102-0425070 SPECIAL BACKFILL	119,348.600 TON				
0020	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	100,931.000 CY				
0030	2102-2710090 EXCAVATION, CLASS 10, WASTE	36,071.000 CY				
0040	2102-2712015 EXCAVATION, CLASS 12, BOULDERS OR ROCK FRAGMENTS	5.000 CY				
0050	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	53,164.000 CY				
0060	2107-0875000 COMPACTION WITH MOISTURE AND DENSITY CONTROL	49,848.000 CY				
0070	2111-8174100 GRANULAR SUBBASE	179,850.700 SY				
0080	2115-0100000 MODIFIED SUBBASE	2,606.800 CY				
0090	2121-7425010 GRANULAR SHOULDERS, TYPE A	13,916.600 TON				
0100	2122-5190008 PAVED SHOULDER, P.C. CONCRETE, 8 IN.	220.100 SY				
0110	2122-5190010 PAVED SHOULDER, P.C. CONCRETE, 10 IN.	48,272.400 SY				
0120	2123-7450000 SHOULDER CONSTRUCTION, EARTH	761.000 STA				



12/9/2025 10:25 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 97-0201-204

Call Order: 110

Letting Date: January 21, 2026

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	2301-1003100 STANDARD OR SLIP-FORM PORTLAND CEMENT CONCRETE PAVEMENT, QM-C, CLASS 3 DURABILITY, 10 IN.	113,719.900 SY				
0140	2301-7000110 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR PCC PAVEMENT THICKNESS (BY SCHEDULE)	125,070.240 EACH		1.00000	125,070.24	
0150	2301-9091000 RUMBLE STRIP PANEL (PCC SURFACE)	8.000 EACH				
0160	2304-0100000 DETOUR PAVEMENT	3,570.800 SY				
0170	2312-8260051 GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE	95.500 TON				
0180	2315-8275025 SURFACING, DRIVEWAY, CLASS A CRUSHED STONE	252.300 TON				
0190	2317-7000110 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR PCC PAVEMENT SMOOTHNESS (BY SCHEDULE)	80,172.980 EACH		1.00000	80,172.98	
0200	2402-0425040 FLOODED BACKFILL	2,158.940 CY				
0210	2402-2720100 EXCAVATION, CLASS 20, FOR ROADWAY PIPE CULVERT	3,829.280 CY				
0220	2416-0100024 APRONS, CONCRETE, 24 IN. DIA.	22.000 EACH				



12/9/2025 10:25 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 97-0201-204

Call Order: 110

Letting Date: January 21, 2026

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0230	2416-0100030 APRONS, CONCRETE, 30 IN. DIA.	4.000 EACH	_____	_____	_____	_____
0240	2416-0100036 APRONS, CONCRETE, 36 IN. DIA.	2.000 EACH	_____	_____	_____	_____
0250	2416-0100048 APRONS, CONCRETE, 48 IN. DIA.	4.000 EACH	_____	_____	_____	_____
0260	2416-0100054 APRONS, CONCRETE, 54 IN. DIA.	2.000 EACH	_____	_____	_____	_____
0270	2416-1180024 CULVERT, CONCRETE ROADWAY PIPE, 24 IN. DIA.	726.000 LF	_____	_____	_____	_____
0280	2416-1180030 CULVERT, CONCRETE ROADWAY PIPE, 30 IN. DIA.	40.000 LF	_____	_____	_____	_____
0290	2416-1180036 CULVERT, CONCRETE ROADWAY PIPE, 36 IN. DIA.	168.000 LF	_____	_____	_____	_____
0300	2416-1180048 CULVERT, CONCRETE ROADWAY PIPE, 48 IN. DIA.	346.000 LF	_____	_____	_____	_____
0310	2416-1180054 CULVERT, CONCRETE ROADWAY PIPE, 54 IN. DIA.	182.000 LF	_____	_____	_____	_____
0320	2417-2307036 DRAIN, CORRUGATED METAL SLOTTED PIPE, 36 IN., W/6 IN. GRATE	116.000 LF	_____	_____	_____	_____
0330	2417-5895018 BEVELED PIPE AND GUARD, 18 INCH	2.000 EACH	_____	_____	_____	_____
0340	2422-0360024 APRONS, UNCLASSIFIED, 24 IN. DIA.	2.000 EACH	_____	_____	_____	_____



12/9/2025 10:25 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 97-0201-204

Call Order: 110

Letting Date: January 21, 2026

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	2422-1722024 CULVERT, UNCLASSIFIED ENTRANCE PIPE, 24 IN. DIA.	33.000 LF				
0360	2422-1723018 CULVERT, UNCLASSIFIED ROADWAY PIPE, 18 IN. DIA.	380.000 LF				
0370	2502-6745952 REMOVAL OF SUBDRAIN	4,477.000 LF				
0380	2502-8212034 SUBDRAIN, LONGITUDINAL, (SHOULDER) 4 IN. DIA.	77,339.900 LF				
0390	2502-8221306 SUBDRAIN OUTLET, DR-306	316.000 EACH				
0400	2505-4008120 REMOVAL OF STEEL BEAM GUARDRAIL	650.000 LF				
0410	2505-4008130 REMOVAL OF CABLE GUARDRAIL	1,265.000 LF				
0420	2505-4008300 STEEL BEAM GUARDRAIL	412.500 LF				
0430	2505-4008410 STEEL BEAM GUARDRAIL BARRIER TRANSITION SECTION, BA-201	4.000 EACH				
0440	2505-4021010 STEEL BEAM GUARDRAIL END ANCHOR, BOLTED	4.000 EACH				
0450	2505-4021720 STEEL BEAM GUARDRAIL TANGENT END TERMINAL, BA-205	4.000 EACH				



12/9/2025 10:25 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 97-0201-204

Call Order: 110

Letting Date: January 21, 2026

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0460	2505-6000111 HIGH TENSION CABLE GUARDRAIL	1,275.000 LF				
0470	2505-6000121 HIGH TENSION CABLE GUARDRAIL, END ANCHOR	4.000 EACH				
0480	2506-4984000 FLOWABLE MORTAR	113.140 CY				
0490	2510-6745850 REMOVAL OF PAVEMENT	123,391.600 SY				
0500	2520-3350015 FIELD OFFICE	1.000 EACH				
0510	2526-8285000 CONSTRUCTION SURVEY	LUMP SUM	LUMP SUM			
0520	2527-9263137 PAINTED SYMBOLS AND LEGENDS, WATERBORNE OR SOLVENT-BASED	16.000 EACH				
0530	2527-9263155 PRE-CUT SYMBOLS AND LEGENDS, PREFORMED THERMOPLASTIC MARKING MATERIAL	8.000 EACH				
0540	2527-9263181 PAVEMENT MARKINGS REMOVED	2,121.550 STA				
0550	2527-9263190 SYMBOLS AND LEGENDS REMOVED	16.000 EACH				
0560	2527-9263209 PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	3,621.480 STA				



12/9/2025 10:25 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 97-0201-204

Call Order: 110

Letting Date: January 21, 2026

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0570	2527-9263225 PERMANENT TAPE MARKINGS, PREFORMED THERMOPLASTIC MARKING MATERIAL	10.100 STA				
0580	2527-9263231 REMOVABLE TAPE MARKINGS, WET RETROREFLECTIVE	222.610 STA				
0590	2527-9270112 GROOVES CUT FOR PAVEMENT MARKINGS	1,520.210 STA				
0600	2527-9270120 GROOVES CUT FOR SYMBOLS AND LEGENDS	8.000 EACH				
0610	2528-2518000 SAFETY CLOSURE	99.000 EACH				
0620	2528-8400157 TEMPORARY FLOODLIGHTING LUMINAIRE	8.000 EACH				
0630	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
0640	2528-9109020 TEMPORARY LANE SEPARATOR SYSTEM	9,074.000 LF				
0650	2528-9290050 PORTABLE DYNAMIC MESSAGE SIGN (PDMS)	90.000 CDAY				
0660	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
0670	2548-0000260 DIAMOND GROUND SHOULDER SINUSOIDAL RUMBLE STRIPS, PCC SURFACE	775.030 STA				



12/9/2025 10:25 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 97-0201-204

Call Order: 110

Letting Date: January 21, 2026

SECTION: 0001

ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0680	2555-0000010 DELIVER AND STOCKPILE SALVAGED MATERIALS	LUMP SUM	LUMP SUM		_____.	
Section: 0001			Total:		_____.	



12/9/2025 10:25 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 97-0201-204

Call Order: 110

Letting Date: January 21, 2026

SECTION: 0002

TRAFFIC SIGNS ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0690	2524-6765010 REMOVE AND REINSTALL SIGN AS PER PLAN	11.000 EACH				
0700	2524-6765210 REMOVAL OF TYPE A SIGN ASSEMBLY	95.000 EACH				
0710	2524-9089110 DELINEATOR, RIGID - TYPE IA	128.000 EACH				
0720	2524-9089200 DELINEATOR, RIGID - TYPE II	8.000 EACH				
0730	2524-9210007 REFERENCE LOCATION SIGNS	8.000 EACH				
0740	2524-9276010 PERFORATED SQUARE STEEL TUBE POSTS	2,007.000 LF				
0750	2524-9276024 PERFORATED SQUARE STEEL TUBE POST ANCHOR, BREAK-AWAY CONCRETE INSTALLATION	4.000 EACH				
0760	2524-9276027 PERFORATED SQUARE STEEL TUBE POST ANCHOR, TRIANGULAR SLIP BASE ASSEMBLY	143.000 EACH				
0770	2524-9290009 SIGN MOUNTING BRACKETS, SPECIAL	12.000 EACH				
0780	2524-9325001 TYPE A SIGNS, SHEET ALUMINUM	1,526.000 SF				
0790	2524-9380001 TYPE B SIGNS, EXTRUDED ALUMINUM STRUCTURAL PANEL	67.000 SF				



12/9/2025 10:25 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 97-0201-204

Call Order: 110

Letting Date: January 21, 2026

SECTION: 0002

TRAFFIC SIGNS ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0800	2599-9999005 ('EACH' ITEM) Remove and Re-install Solar-poweredFlashing Beacons	11.000 EACH				
Section: 0002			Total:			



12/9/2025 10:25 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 97-0201-204

Call Order: 110

Letting Date: January 21, 2026

SECTION: 0003

EROSION CONTROL ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0810	2507-3250005 ENGINEERING FABRIC	629.900 SY				
0820	2507-8029000 EROSION STONE	377.900 TON				
0830	2601-2634100 MULCHING	38.900 ACRE				
0840	2601-2636043 SEEDING AND FERTILIZING (RURAL)	27.700 ACRE				
0850	2601-2636044 SEEDING AND FERTILIZING (URBAN)	2.200 ACRE				
0860	2601-2638352 SLOPE PROTECTION, WOOD EXCELSIOR MAT	3,736.000 SQ				
0870	2601-2640350 SPECIAL DITCH CONTROL, WOOD EXCELSIOR MAT	1,260.000 SQ				
0880	2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING	27.700 ACRE				
0890	2601-2642120 STABILIZING CROP - SEEDING AND FERTILIZING (URBAN)	2.200 ACRE				
0900	2601-2643110 WATERING FOR SOD, SPECIAL DITCH CONTROL, OR SLOPE PROTECTION	999.200 MGAL		75.00000		74,940.00
0910	2601-2643300 MOBILIZATION FOR WATERING	3.000 EACH		450.00000		1,350.00
0920	2602-0000020 SILT FENCE	1,423.000 LF				



12/9/2025 10:25 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 97-0201-204

Call Order: 110

Letting Date: January 21, 2026

SECTION: 0003

EROSION CONTROL ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0930	2602-0000030 SILT FENCE FOR DITCH CHECKS	4,302.000 LF				
0940	2602-0000071 REMOVAL OF SILT FENCE OR SILT FENCE FOR DITCH CHECKS	5,725.000 LF				
0950	2602-0000101 MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	573.000 LF				
0960	2602-0000150 STABILIZED CONSTRUCTION ENTRANCE, EC-303	1,200.000 LF				
0970	2602-0000312 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	23,160.000 LF				
0980	2602-0000320 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 20 IN. DIA.	23,160.000 LF				
0990	2602-0000351 REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	51,540.000 LF				
1000	2602-0000370 DITCH CHECK SEDIMENT CONTROL DEVICE, 20 IN. DIA.	5,220.000 LF				
1010	2602-0010010 MOBILIZATIONS, EROSION CONTROL	1.000 EACH		600.00000		600.00
1020	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	1.000 EACH		1,200.00000		1,200.00
Section: 0003			Total:			

Total Bid: _____.