



<b>CONTRACTS AND SPECIFICATIONS BUREAU Proposal</b>
---

---

**Proposal ID:** 42-3720-616

**Letting Date:** July 21, 2026

**Call Order:** 006

**Proposal Work Type:** BRIDGE REPLACEMENT - PPCB

**DBE Goal:** 0.0%

**Contracting Authority:** HARDIN COUNTY

**Proposal Guaranty:** \$250,000.00

---

**This proposal includes the following project(s):**

---

**Project Number:** BRS-3720(616)--60-42

**County:** HARDIN

**Project Work Type:** BRIDGE REPLACEMENT - PPCB

**Route:** SOUTH AVE.

**Location:** In the city of Iowa Falls, On SOUTH AVE, Over IOWA RIVER, S17 T89 R20

**Road System:** URBAN

**Federal Aid - Wages:** Federal Aid - Predetermined Wages are in Effect

---

**Contract Time**

**Proposal ID:** 42-3720-616

**Call Order:** 006

**Letting Date:** July 21, 2026

Site ID	Site Details			Liquidated Damages
00	Late Start Date	04/05/2027	140 WORK DAYS	\$1,800.00

(\*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

**Notes**

---

**Proposal ID:** 42-3720-616

**Call Order:** 006

**Letting Date:** July 21, 2026

---

**Notes :**

There are no notes for this proposal.

## Contracts and Specifications Bureau

## Proposal Specifications List

Proposal ID: 42-3720-616

Call Order: 006

Letting Date: July 21, 2026

Note	Description
001.2023	<p>*** STANDARD SPECIFICATIONS -- SERIES 2023 ***</p> <p>The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.</p>
410.11	<p>*** STORM WATER POLLUTION PREVENTION PLAN ***</p> <p>A Storm Water Pollution Prevention Plan has been developed by the Contracting Authority for one or more projects on this contract. See the project plans (or other contract document) for specific Storm Water Pollution Prevention Plan details.</p>
500.07.2026	<p>*** WINTER WORK ***</p> <p>Winter Work will be allowed during the winter 2026/2027. No working days will be charged between November 15, 2026 and April 1, 2027.</p>
500.2027	<p>*** NO WINTER FREE TIME ***</p> <p>The free time allowed between November 15 and April 1 will not be permitted on this project during the winter of 2027-2028. The Contractor shall work during the winter on all working days as defined in article 1101.03 'working day'.</p>
FHWA-1273.09	<p>FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023</p> <p>23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.</p>
GS-23006	<p>GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION</p>



6/10/2026 11:26 AM

**Contracts and Specifications Bureau**

**Proposal Specifications List**

**Proposal ID:** 42-3720-616

**Call Order:** 006

**Letting Date:** July 21, 2026

Note	Description
IA26-28.3	<p>PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20260028 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY)</p> <p>Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract.</p> <p>*** Additional Requirement ***</p> <p>The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.</p>



6/10/2026 11:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 42-3720-616

Call Order: 006

Letting Date: July 21, 2026

SECTION: 0001

ITEMS FOR A 224'-0 X 40'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2101-0850001 CLEARING AND GRUBBING	0.200 ACRE				
0020	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	510.000 CY				
0030	2102-2710090 EXCAVATION, CLASS 10, WASTE	6,099.000 CY				
0040	2104-2710020 EXCAVATION, CLASS 10, CHANNEL	4,180.000 CY				
0050	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	600.000 CY				
0060	2115-0100000 MODIFIED SUBBASE	210.000 CY				
0070	2121-7425020 GRANULAR SHOULDERS, TYPE B	200.000 TON				
0080	2123-7450020 SHOULDER FINISHING, EARTH	5.900 STA				
0090	2213-7100400 RELOCATION OF MAIL BOXES	1.000 EACH				
0100	2301-0685550 BRIDGE APPROACH PAVEMENT, AS PER PLAN	427.700 SY				
0110	2301-1033080 STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 8 IN.	1,034.600 SY				



6/10/2026 11:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 42-3720-616

Call Order: 006

Letting Date: July 21, 2026

SECTION: 0001

ITEMS FOR A 224'-0 X 40'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	2315-8275025 SURFACING, DRIVEWAY, CLASS A CRUSHED STONE	15.000 TON				
0130	2401-6745625 REMOVAL OF EXISTING BRIDGE	LUMP SUM	LUMP SUM			
0140	2402-0425040 FLOODED BACKFILL	1,614.000 CY				
0150	2402-2720000 EXCAVATION, CLASS 20	1,711.000 CY				
0160	2402-2720100 EXCAVATION, CLASS 20, FOR ROADWAY PIPE CULVERT	145.000 CY				
0170	2402-2721000 EXCAVATION, CLASS 21	1,434.000 CY				
0180	2402-2722000 EXCAVATION, CLASS 22	664.000 CY				
0190	2403-0100010 STRUCTURAL CONCRETE (BRIDGE)	1,218.500 CY				
0200	2404-7775000 REINFORCING STEEL	124,922.000 LB				
0210	2404-7775005 REINFORCING STEEL, EPOXY COATED	119,789.000 LB				
0220	2407-0562855 BEAMS, PRETENSIONED PRESTRESSED CONCRETE, BTB55	5.000 EACH				
0230	2407-0562870 BEAMS, PRETENSIONED PRESTRESSED CONCRETE, BTB70	5.000 EACH				



6/10/2026 11:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 42-3720-616

Call Order: 006

Letting Date: July 21, 2026

SECTION: 0001

ITEMS FOR A 224'-0 X 40'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	2407-0562895 BEAMS, PRETENSIONED PRESTRESSED CONCRETE, BTB95	5.000 EACH	_____	_____	_____	_____
0250	2408-7800000 STRUCTURAL STEEL	7,544.000 LB	_____	_____	_____	_____
0260	2414-6424124 CONCRETE OPEN RAILING, TL-4	541.200 LF	_____	_____	_____	_____
0270	2416-0100018 APRONS, CONCRETE, 18 IN. DIA.	2.000 EACH	_____	_____	_____	_____
0280	2416-1240018 CULVERT, 3000D CONCRETE ROADWAY PIPE, 18 IN. DIA.	68.000 LF	_____	_____	_____	_____
0290	2501-0201057 PILES, STEEL, HP 10 X 57	595.000 LF	_____	_____	_____	_____
0300	2505-4008120 REMOVAL OF STEEL BEAM GUARDRAIL	182.000 LF	_____	_____	_____	_____
0310	2507-2638650 BRIDGE WING ARMORING - EROSION STONE	30.000 SY	_____	_____	_____	_____
0320	2507-3250005 ENGINEERING FABRIC	1,200.000 SY	_____	_____	_____	_____
0330	2507-6800061 REVETMENT, CLASS E	800.000 TON	_____	_____	_____	_____
0340	2507-6875002 REVETMENT, REMOVE AND REPLACE	90.000 CY	_____	_____	_____	_____
0350	2510-6745850 REMOVAL OF PAVEMENT	1,685.100 SY	_____	_____	_____	_____





6/10/2026 11:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 42-3720-616

Call Order: 006

Letting Date: July 21, 2026

SECTION: 0001

ITEMS FOR A 224'-0 X 40'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0360	2515-2475006 DRIVEWAY, P.C. CONCRETE, 6 IN.	71.300 SY				
0370	2515-6745600 REMOVAL OF PAVED DRIVEWAY	71.300 SY				
0380	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM			
0390	2527-9263209 PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	15.970 STA				
0400	2528-2518000 SAFETY CLOSURE	3.000 EACH				
0410	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
0420	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
0430	2599-9999005 (‘EACH’ ITEM) WEEP HOLE ASSEMBLY, 4 DIA.	6.000 EACH				
0440	2599-9999020 (‘TONS’ ITEM) POROUS BACKFILL	755.000 TON				
0450	2601-2634100 MULCHING	1.400 ACRE				
0460	2601-2636043 SEEDING AND FERTILIZING (RURAL)	0.500 ACRE				
0470	2601-2636044 SEEDING AND FERTILIZING (URBAN)	0.200 ACRE				



6/10/2026 11:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 42-3720-616

Call Order: 006

Letting Date: July 21, 2026

SECTION: 0001

ITEMS FOR A 224'-0 X 40'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0480	2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING	0.500 ACRE				
0490	2601-2642120 STABILIZING CROP - SEEDING AND FERTILIZING (URBAN)	0.200 ACRE				
0500	2602-0010010 MOBILIZATIONS, EROSION CONTROL	1.000 EACH		600.00000		600.00
0510	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	1.000 EACH		1,200.00000		1,200.00
Section: 0001			Total:			
			Total Bid:			