



CONTRACTS AND SPECIFICATIONS BUREAU Proposal

Proposal ID: 61-C061-130

Letting Date: July 21, 2026

Call Order: 007

Proposal Work Type: BRIDGE REPLACEMENT - OTHER

DBE Goal: 0.0%

Contracting Authority: MADISON COUNTY

Proposal Guaranty: \$125,000.00

This proposal includes the following project(s):

Project Number: HDP-C061(130)--6B-61

County: MADISON

Project Work Type: BRIDGE REPLACEMENT - OTHER

Route: R35

Location: On R 35, Over MIDDLE RIVER, S25 T76 R26

Road System: FARM TO MARKET ROAD

Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

Contract Time

Proposal ID: 61-C061-130

Call Order: 007

Letting Date: July 21, 2026

Site ID	Site Details			Liquidated Damages
00	Late Start Date	04/05/2027	125 WORK DAYS	\$1,000.00

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

Notes

Proposal ID: 61-C061-130

Call Order: 007

Letting Date: July 21, 2026

Notes :

There are no notes for this proposal.

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 61-C061-130

Call Order: 007

Letting Date: July 21, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.
410.11	*** STORM WATER POLLUTION PREVENTION PLAN *** A Storm Water Pollution Prevention Plan has been developed by the Contracting Authority for one or more projects on this contract. See the project plans (or other contract document) for specific Storm Water Pollution Prevention Plan details.
500.07.2026	*** WINTER WORK *** Winter Work will be allowed during the winter 2026/2027. No working days will be charged between November 15, 2026 and April 1, 2027.
FHWA-1273.09	FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023 23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.
GS-23006	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION



6/10/2026 11:26 AM

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 61-C061-130

Call Order: 007

Letting Date: July 21, 2026

Note	Description
IA26-28.3	<p>PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20260028 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY)</p> <p>Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract.</p> <p>*** Additional Requirement ***</p> <p>The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.</p>



6/10/2026 11:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 61-C061-130

Call Order: 007

Letting Date: July 21, 2026

SECTION: 0001

Items for a 243'-0 x 30'-6 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2101-0850001 CLEARING AND GRUBBING	0.700 ACRE				
0020	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	327.000 CY				
0030	2102-2710090 EXCAVATION, CLASS 10, WASTE	379.000 CY				
0040	2104-2710020 EXCAVATION, CLASS 10, CHANNEL	2,400.000 CY				
0050	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	1,100.000 CY				
0060	2111-8174100 GRANULAR SUBBASE	1,092.000 SY				
0070	2121-7425020 GRANULAR SHOULDERS, TYPE B	185.000 TON				
0080	2122-5190501 PAVED SHOULDER, PORTLAND CEMENT CONCRETE (PAVED SHOULDER PANEL FOR BRIDGE END DRAIN)	49.200 SY				
0090	2123-7450020 SHOULDER FINISHING, EARTH	6.300 STA				
0100	2301-0690210 BRIDGE APPROACH, TWO LANE	336.000 SY				
0110	2303-1031750 HOT MIX ASPHALT STANDARD TRAFFIC, BASE COURSE, 3/4 IN. MIX	239.000 TON				



6/10/2026 11:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 61-C061-130

Call Order: 007

Letting Date: July 21, 2026

SECTION: 0001

Items for a 243'-0 x 30'-6 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	2303-1032750 HOT MIX ASPHALT STANDARD TRAFFIC, INTERMEDIATE COURSE, 3/4 IN. MIX	79.000 TON				
0130	2303-1033750 HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 3/4 IN. MIX, NO SPECIAL FRICTION REQUIREMENT	79.000 TON				
0140	2303-1258283 ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC	23.800 TON				
0150	2312-8260051 GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE	140.000 TON				
0160	2401-6745625 REMOVAL OF EXISTING BRIDGE	LUMP SUM	LUMP SUM			
0170	2402-2720000 EXCAVATION, CLASS 20	230.000 CY				
0180	2402-2721000 EXCAVATION, CLASS 21	508.000 CY				
0190	2402-2722000 EXCAVATION, CLASS 22	47.000 CY				
0200	2403-0100010 STRUCTURAL CONCRETE (BRIDGE)	503.000 CY				
0210	2404-7775000 REINFORCING STEEL	23,878.000 LB				
0220	2404-7775005 REINFORCING STEEL, EPOXY COATED	84,847.000 LB				



6/10/2026 11:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 61-C061-130

Call Order: 007

Letting Date: July 21, 2026

SECTION: 0001

Items for a 243'-0 x 30'-6 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0230	2407-0551380 BEAMS, PRETENSIONED PRESTRESSED CONCRETE, C80	15.000 EACH				
0240	2408-7800000 STRUCTURAL STEEL	4,122.000 LB				
0250	2414-6424124 CONCRETE OPEN RAILING, TL-4	540.000 LF				
0260	2501-0201057 PILES, STEEL, HP 10 X 57	855.000 LF				
0270	2501-6335010 PREBORED HOLES	180.000 LF				
0280	2503-0500402 BRIDGE END DRAIN, DR-402	4.000 EACH				
0290	2505-4008120 REMOVAL OF STEEL BEAM GUARDRAIL	248.000 LF				
0300	2505-4008410 STEEL BEAM GUARDRAIL BARRIER TRANSITION SECTION, BA-201	4.000 EACH				
0310	2505-4021010 STEEL BEAM GUARDRAIL END ANCHOR, BOLTED	4.000 EACH				
0320	2505-4021711 STEEL BEAM GUARDRAIL FLARED END TERMINAL, LS-626	4.000 EACH				
0330	2507-3250005 ENGINEERING FABRIC	2,100.000 SY				
0340	2507-6800061 REVETMENT, CLASS E	1,400.000 TON				



6/10/2026 11:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 61-C061-130

Call Order: 007

Letting Date: July 21, 2026

SECTION: 0001

Items for a 243'-0 x 30'-6 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	2510-6745850 REMOVAL OF PAVEMENT	836.000 SY				
0360	2528-2518000 SAFETY CLOSURE	4.000 EACH				
0370	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
0380	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
0390	2601-2634100 MULCHING	2.800 ACRE				
0400	2601-2636043 SEEDING AND FERTILIZING (RURAL)	1.400 ACRE				
0410	2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING	1.400 ACRE				
0420	2602-0000020 SILT FENCE	900.000 LF				
0430	2602-0000030 SILT FENCE FOR DITCH CHECKS	224.000 LF				
0440	2602-0000101 MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	1,124.000 LF				
0450	2602-0000312 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	420.000 LF				
0460	2602-0000320 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 20 IN. DIA.	200.000 LF				



6/10/2026 11:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 61-C061-130

Call Order: 007

Letting Date: July 21, 2026

SECTION: 0001

Items for a 243'-0 x 30'-6 Pretensioned Prestressed Concrete Beam Bridge

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0470	2602-0010010 MOBILIZATIONS, EROSION CONTROL	1.000 EACH		600.00000		600.00
0480	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	1.000 EACH		1,200.00000		1,200.00

Section: 0001

Total: _____.

Total Bid: _____.