



CONTRACTS AND SPECIFICATIONS BUREAU Proposal

Proposal ID: 82-0587-646

Letting Date: July 21, 2026

Call Order: 106

Proposal Work Type: PCC SIDEWALK/TRAIL

DBE Goal: 0.0%

Contracting Authority: CITY OF BETTENDORF

Proposal Guaranty: \$50,000.00

This proposal includes the following project(s):

Project Number: TAP-T-0587(646)--8V-82

County: SCOTT

Project Work Type: PCC SIDEWALK/TRAIL

Route: MIDDLE RD TRAIL

Location: In the city of Bettendorf, Trail along MIDDLE RD, from Hopewell to Forest Grove

Road System: UNDEFINED - OFF SYSTEM

Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

Contract Time

Proposal ID: 82-0587-646

Call Order: 106

Letting Date: July 21, 2026

Site ID	Site Details			Liquidated Damages
00	Late Start Date	08/31/2026	40 WORK DAYS	\$1,000.00

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

Notes

Proposal ID: 82-0587-646

Call Order: 106

Letting Date: July 21, 2026

Notes :

There are no notes for this proposal.

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 82-0587-646

Call Order: 106

Letting Date: July 21, 2026

Note	Description
001.2023	<p>*** STANDARD SPECIFICATIONS -- SERIES 2023 ***</p> <p>The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.</p>
410.11	<p>*** STORM WATER POLLUTION PREVENTION PLAN ***</p> <p>A Storm Water Pollution Prevention Plan has been developed by the Contracting Authority for one or more projects on this contract. See the project plans (or other contract document) for specific Storm Water Pollution Prevention Plan details.</p>
500.01	<p>*** WINTER WORK ***</p> <p>The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.</p>
FHWA-1273.09	<p>FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023</p> <p>23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.</p>
GS-23006	<p>GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION</p>
IA26-1.1	<p>PREDETERMINED WAGE RATES - GENERAL DECISION NUMBER IA20260001 FOR HEAVY AND HIGHWAY CONSTRUCTION -- SCOTT COUNTY IN IOWA</p> <p>*** Additional Requirement ***</p> <p>The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.</p>



6/10/2026 11:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 82-0587-646

Call Order: 106

Letting Date: July 21, 2026

SECTION: 0001

PCC SIDEWALK/TRAIL ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2101-0850002 CLEARING AND GRUBBING	68.500 UNIT				
0020	2102-0425070 SPECIAL BACKFILL SUBGRADE STABILIZATION	47.000 TON				
0030	2102-2625001 EMBANKMENT-IN-PLACE, CONTRACTOR FURNISHED	12,200.000 CY				
0040	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	130.000 CY				
0050	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	2,630.000 CY				
0060	2107-0875000 COMPACTION WITH MOISTURE AND DENSITY CONTROL	12,330.000 CY				
0070	2111-8174100 GRANULAR SUBBASE	3,880.000 SY				
0080	2113-0001100 SUBGRADE STABILIZATION MATERIAL, POLYMER GRID	90.000 SY				
0090	2121-7425010 GRANULAR SHOULDERS, TYPE A	33.100 TON				
0100	2123-7450020 SHOULDER FINISHING, EARTH	26.300 STA				
0110	2301-1033100 STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 10 IN.	90.100 SY				



6/10/2026 11:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 82-0587-646

Call Order: 106

Letting Date: July 21, 2026

SECTION: 0001

PCC SIDEWALK/TRAIL ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	2303-1031500 HOT MIX ASPHALT STANDARD TRAFFIC, BASE COURSE, 1/2 IN. MIX	18.400 TON	_____	_____	_____	_____
0130	2303-1033380 HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 3/8 IN. MIX, NO SPECIAL FRICTION REQUIREMENT	19.000 TON	_____	_____	_____	_____
0140	2303-1258283 ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC	2.300 TON	_____	_____	_____	_____
0150	2402-2720100 EXCAVATION, CLASS 20, FOR ROADWAY PIPE CULVERT	218.000 CY	_____	_____	_____	_____
0160	2416-0100048 APRONS, CONCRETE, 48 IN. DIA.	1.000 EACH	_____	_____	_____	_____
0170	2416-1240048 CULVERT, 3000D CONCRETE ROADWAY PIPE, 48 IN. DIA.	187.000 LF	_____	_____	_____	_____
0180	2417-0225012 APRONS, METAL, 12 IN. DIA.	1.000 EACH	_____	_____	_____	_____
0190	2417-0225015 APRONS, METAL, 15 IN. DIA.	2.000 EACH	_____	_____	_____	_____
0200	2417-1040015 CULVERT, CORRUGATED METAL ENTRANCE PIPE, 15 IN. DIA.	24.000 LF	_____	_____	_____	_____
0210	2435-0140160 MANHOLE, STORM SEWER, SW-401, 60 IN.	1.000 EACH	_____	_____	_____	_____
0220	2435-0251218 INTAKE, SW-512, 18 IN.	1.000 EACH	_____	_____	_____	_____



6/10/2026 11:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 82-0587-646

Call Order: 106

Letting Date: July 21, 2026

SECTION: 0001

PCC SIDEWALK/TRAIL ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0230	2502-8212204 SUBDRAIN, PERFORATED PLASTIC PIPE, 4 IN. DIA.	2,604.000 LF				
0240	2502-8221303 SUBDRAIN OUTLET, DR-303	1.000 EACH				
0250	2502-8221305 SUBDRAIN OUTLET, DR-305	8.000 EACH				
0260	2503-0111012 STORM SEWER GRAVITY MAIN, TRENCHED, HIGH DENSITY POLYETHYLENE PIPE (HDPE), 12 IN.	63.000 LF				
0270	2503-0114430 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 30 IN.	71.000 LF				
0280	2503-0200036 REMOVE STORM SEWER PIPE LESS THAN OR EQUAL TO 36 IN.	178.000 LF				
0290	2507-3250005 ENGINEERING FABRIC	76.200 SY				
0300	2507-6800061 REVTMENT, CLASS E	55.000 TON				
0310	2510-6745850 REMOVAL OF PAVEMENT	90.100 SY				
0320	2510-6750600 REMOVAL OF INTAKES AND UTILITY ACCESSES	6.000 EACH				
0330	2511-0302500 RECREATIONAL TRAIL, PORTLAND CEMENT CONCRETE, 5 IN.	2,922.000 SY				



6/10/2026 11:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 82-0587-646

Call Order: 106

Letting Date: July 21, 2026

SECTION: 0001

PCC SIDEWALK/TRAIL ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0340	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM			
0350	2527-9263209 PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	6.210 STA				
0360	2528-2518000 SAFETY CLOSURE	2.000 EACH				
0370	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
0380	2528-9290050 PORTABLE DYNAMIC MESSAGE SIGN (PDMS)	10.000 CDAY				
0390	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
0400	2552-0000210 TRENCH FOUNDATION	18.200 TON				
0410	2552-0000300 TRENCH COMPACTION TESTING	LUMP SUM	LUMP SUM			
0420	2599-9999003 (‘CUBIC YARDS’ ITEM) PIPE APRON, PCC, CIP HEADWALL	6.700 CY				
0430	2601-2636070 HYDRAULIC SEEDING	2.500 ACRE				
0440	2602-0000020 SILT FENCE	3,546.000 LF				
0450	2602-0000030 SILT FENCE FOR DITCH CHECKS	2,748.000 LF				



6/10/2026 11:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 82-0587-646

Call Order: 106

Letting Date: July 21, 2026

SECTION: 0001

PCC SIDEWALK/TRAIL ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0460	2602-0000071 REMOVAL OF SILT FENCE OR SILT FENCE FOR DITCH CHECKS	6,294.000 LF				
0470	2602-0000101 MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	629.400 LF				
0480	2602-0000309 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 9 IN. DIA.	180.000 LF				
0490	2602-0000351 REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	180.000 LF				
0500	2602-0010010 MOBILIZATIONS, EROSION CONTROL	3.000 EACH		600.00000		1,800.00
Section: 0001			Total:			
			Total Bid:			