



**CONTRACTS AND SPECIFICATIONS BUREAU  
Proposal**

**Proposal ID:** 50-164

**Letting Date:** July 21, 2026

**Call Order:** 302

**Proposal Work Type:** BASE STABILIZATION

**DBE Goal:** 0.0%

**Contracting Authority:** JASPER COUNTY

**Proposal Guaranty:** \$25,000.00

**This proposal includes the following project(s):**

**Project Number:** L-164--73-50

**County:** JASPER

**Project Work Type:** BASE STABILIZATION

**Route:** N 95TH AVE

**Location:** On N 95TH AVE W, from W 76th St N E 0.6 miles to Baxter CL

**Road System:** LOCAL SECONDARY ROAD

**Federal Aid - Wages:** Non-Federal Aid - Predetermined Wages are not in Effect

**Project Number:** FM-C050(162)--55-50

**County:** JASPER

**Project Work Type:** BASE STABILIZATION

**Route:** W 76TH ST

**Location:** On W 76th St N (S 52), from Hwy F-17 W N 0.5 miles to End

**Road System:** FARM TO MARKET ROAD

**Federal Aid - Wages:** Non-Federal Aid - Predetermined Wages are not in Effect

**Contract Time**

**Proposal ID:** 50-164

**Call Order:** 302

**Letting Date:** July 21, 2026

Site ID	Site Details			Liquidated Damages
00	Late Start Date	08/24/2026	15 WORK DAYS	\$1,000.00

(\*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

**Notes**

---

**Proposal ID:** 50-164

**Call Order:** 302

**Letting Date:** July 21, 2026

---

**Notes :**

There are no notes for this proposal.



6/10/2026 11:26 AM

**Contracts and Specifications Bureau**

**Proposal Specifications List**

**Proposal ID:** 50-164

**Call Order:** 302

**Letting Date:** July 21, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.
500.01	*** WINTER WORK *** The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.
GS-23006	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION
SP-231076	SPECIAL PROVISIONS FOR OTTA SEAL CONSTRUCTION  Jasper County FM-C050(162)--55-50 L-164--73-50
SP-231078	SPECIAL PROVISIONS FOR CEMENT STABILIZATION  Jasper County FM-C050(162)--55-50 L-164--73-50



6/10/2026 11:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 50-164

Call Order: 302

Letting Date: July 21, 2026

SECTION: 0001

ROADWAY ITEMS - L-164--73-50

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2102-2625000 EMBANKMENT-IN-PLACE	250.000 CY				
0020	2102-2713070 EXCAVATION, CLASS 13, ROADWAY AND BORROW	150.000 CY				
0030	2212-0475095 CLEANING AND PREPARATION OF BASE	1.740 MILE				
0040	2213-7100400 RELOCATION OF MAIL BOXES	4.000 EACH				
0050	2214-7450050 BLADING AND SHAPING SHOULDER MATERIAL	30.815 STA				
0060	2307-0600000 BINDER BITUMEN DOUBLE OTTA SEAL	6,162.970 GAL				
0070	2307-0600000 BINDER BITUMEN MC-70 PRIME COAT	1,643.460 GAL				
0080	2312-8260051 GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE	205.430 TON				
0090	2315-8275025 SURFACING, DRIVEWAY, CLASS A CRUSHED STONE	32.000 TON				
0100	2526-8285010 CONSTRUCTION SURVEY, MONUMENT PRESERVATION	LUMP SUM	LUMP SUM			
0110	2526-8285020 CONSTRUCTION SURVEY, CONTROL POINT SURVEY	LUMP SUM	LUMP SUM			



6/10/2026 11:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 50-164

Call Order: 302

Letting Date: July 21, 2026

SECTION: 0001

ROADWAY ITEMS - L-164--73-50

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	2528-2518000 SAFETY CLOSURE	1.000 EACH				
0130	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
0140	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
0150	2599-9999018 ( 'SQUARE YARDS' ITEM) CONSTRUCTION OF CEMENT TREATED SUBGRADE	8,902.100 SY				
0160	2599-9999020 ( 'TONS' ITEM) AGGREGATE INTERLAYER, HMA MILLINGS, 1 THICKNESS	316.360 TON				
0170	2599-9999020 ( 'TONS' ITEM) CEMENT	259.580 TON				
0180	2601-2634100 MULCHING	0.300 ACRE				
0190	2601-2636043 SEEDING AND FERTILIZING (RURAL)	0.300 ACRE				
Section: 0001			Total:			



6/10/2026 11:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 50-164

Call Order: 302

Letting Date: July 21, 2026

SECTION: 0002

ROADWAY ITEMS - FM-C050(162)--55-50

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0200	2212-0475095 CLEANING AND PREPARATION OF BASE	1.250 MILE				
0210	2213-7100400 RELOCATION OF MAIL BOXES	5.000 EACH				
0220	2214-7450050 BLADING AND SHAPING SHOULDER MATERIAL	21.600 STA				
0230	2307-0600000 BINDER BITUMEN DOUBLE OTTA SEAL	4,414.500 GAL				
0240	2307-0600000 BINDER BITUMEN MC-70 PRIME COAT	1,177.200 GAL				
0250	2312-8260051 GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE	147.150 TON				
0260	2315-8275025 SURFACING, DRIVEWAY, CLASS A CRUSHED STONE	32.000 TON				
0270	2526-8285010 CONSTRUCTION SURVEY, MONUMENT PRESERVATION	LUMP SUM	LUMP SUM			
0280	2526-8285020 CONSTRUCTION SURVEY, CONTROL POINT SURVEY	LUMP SUM	LUMP SUM			
0290	2528-2518000 SAFETY CLOSURE	3.000 EACH				
0300	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			



6/10/2026 11:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 50-164

Call Order: 302

Letting Date: July 21, 2026

SECTION: 0002

ROADWAY ITEMS - FM-C050(162)--55-50

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0310	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
0320	2599-9999018 (‘SQUARE YARDS’ ITEM) CONSTRUCTION OF CEMENT TREATED SUBGRADE	6,376.500 SY				
0330	2599-9999020 (‘TONS’ ITEM) AGGREGATE INTERLAYER, HMA MILLINGS, 1 THICKNESS	226.650 TON				
0340	2599-9999020 (‘TONS’ ITEM) CEMENT	185.930 TON				
0350	2601-2634100 MULCHING	0.100 ACRE				
0360	2601-2636043 SEEDING AND FERTILIZING (RURAL)	0.100 ACRE				
Section: 0002			Total:			
			Total Bid:			