



CONTRACTS AND SPECIFICATIONS BUREAU Proposal

Proposal ID: 54-0211-046-A

Letting Date: June 16, 2026

Call Order: 003

Proposal Work Type: BRIDGE REPLACEMENT - CCS

DBE Goal: 0.0%

Contracting Authority: IOWA DEPARTMENT OF TRANSPORTATION

Proposal Guaranty: \$150,000.00

This proposal includes the following project(s):

Project Number: BRF-021-1(46)--38-54

County: KEOKUK

Project Work Type: BRIDGE REPLACEMENT - CCS

Route: IOWA 21

Location: Cedar Creek 1.1 mi N of IA 92

Road System: PRIMARY ROAD (non-NHS)

Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

Contract Time

Proposal ID: 54-0211-046-A

Call Order: 003

Letting Date: June 16, 2026

Site ID	Site Details			Liquidated Damages
00	Late Start Date	04/26/2027	90 WORK DAYS	\$1,200.00
	No Lane Closures or Detour.			
01	No Start Date Specified		50 CALENDAR DAYS	\$9,000.00
	Closure of IA 21. See Description Below.			
02	No Start Date Specified		3 CALENDAR DAYS	\$1,200.00
	Lane Closure with Flaggers.			

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

The following sections are alternates:

0003	AA	1	ALTERNATE 'AA' OPTION 1: PCC SHOULDER, BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN
0004	AA	2	ALTERNATE 'AA' OPTION 2: HMA SHOULDER, BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN

Contracts and Specifications Bureau

Notes

Proposal ID: 54-0211-046-A**Call Order:** 003**Letting Date:** June 16, 2026

Notes :

*** Work Restrictions ***

Project shall not start before Oct. 1, 2026.

Site 01

This is an incentive/ disincentive restricted site for a critical closure activity. Section 1111 of the Standard Specifications for Incentive/Disincentive (I/D) shall apply.

Incentive/ Disincentive/ Liquidated Damages Per Day: \$9,000

The Critical Closure Activity is as follows:

Any work requiring closures of IA 21. The site will be considered complete when IA 21 is open to two lanes of traffic each direction, 12' wide, with no further lane closures in both directions except for those outlined in Site 02.

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 54-0211-046-A

Call Order: 003

Letting Date: June 16, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.
410.11	*** STORM WATER POLLUTION PREVENTION PLAN *** A Storm Water Pollution Prevention Plan has been developed by the Contracting Authority for one or more projects on this contract. See the project plans (or other contract document) for specific Storm Water Pollution Prevention Plan details.
500.01	*** WINTER WORK *** The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.
720.121	*** POINT 25 Utility Data *** This Estimating Proposal has an attachment of the "POINT 25 Utility Data". This attachment is a part of the proposal form.
DS-23004	DEVELOPMENTAL SPECIFICATIONS FOR CONSTRUCTION PROGRESS SCHEDULE
DS-23025	DEVELOPMENTAL SPECIFICATIONS FOR MASS CONCRETE – CONTROL OF HEAT OF HYDRATION
DS-23032	DEVELOPMENTAL SPECIFICATIONS FOR ELECTRONIC TICKETING
DS-23048	DEVELOPMENTAL SPECIFICATIONS FOR PORTABLE POP-UP NETWORK FOR INSPECTION USE
DS-23083	DEVELOPMENTAL SPECIFICATIONS FOR FIBER REINFORCEMENT FOR STRUCTURAL CONCRETE

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 54-0211-046-A

Call Order: 003

Letting Date: June 16, 2026

Note	Description
FHWA-1273.09	<p>FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023</p> <p>23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.</p>
GS-23006	<p>GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION</p>
IA26-28.0	<p>PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20260028 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY)</p> <p>Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract.</p> <p>*** Additional Requirement ***</p> <p>The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.</p>
SP-230389	<p>SPECIAL PROVISIONS FOR PREFABRICATED BRIDGE SUPERSTRUCTURE MOVE</p> <p>Keokuk County BRF-021-1(46)--38-54</p>



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 54-0211-046-A

Call Order: 003

Letting Date: June 16, 2026

SECTION: 0001

DESIGN NO. 0326; 140'-0 X 40'-0 CONTINUOUS CONCRETE SLAB BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2104-2710020 EXCAVATION, CLASS 10, CHANNEL	1,006.000 CY				
0020	2401-6745625 REMOVAL OF EXISTING BRIDGE	LUMP SUM	LUMP SUM			
0030	2402-2720000 EXCAVATION, CLASS 20	150.000 CY				
0040	2403-0100010 STRUCTURAL CONCRETE (BRIDGE)	612.500 CY				
0050	2403-1000005 FIBER REINFORCEMENT FOR STRUCTURAL CONCRETE	447.400 CY				
0060	2403-1000010 TRIAL BATCH AND TEST PLACEMENT (FIBER REINFORCED CONCRETE)	LUMP SUM	LUMP SUM			
0070	2404-7775000 REINFORCING STEEL	36,843.000 LB				
0080	2404-7775005 REINFORCING STEEL, EPOXY COATED	126,486.000 LB				
0090	2404-7775009 REINFORCING STEEL, STAINLESS STEEL	3,712.000 LB				
0100	2408-7800000 STRUCTURAL STEEL	1,878.000 LB				
0110	2414-6424110 CONCRETE BARRIER RAILING	307.000 LF				
0120	2433-0001060 CONCRETE DRILLED SHAFT, 60 IN. DIAMETER	209.000 LF				



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 54-0211-046-A

Call Order: 003

Letting Date: June 16, 2026

SECTION: 0001

DESIGN NO. 0326; 140'-0 X 40'-0 CONTINUOUS CONCRETE SLAB BRIDGE

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	2433-0003000 DEMONSTRATION SHAFT	41.500 LF				
0140	2501-0201042 PILES, STEEL, HP 10 X 42	840.000 LF				
0150	2501-6335010 PREBORED HOLES	160.000 LF				
0160	2507-3250005 ENGINEERING FABRIC	1,641.000 SY				
0170	2507-6800061 REVTMENT, CLASS E	1,491.000 TON				
0180	2507-8029000 EROSION STONE	38.000 TON				
0190	2520-0005010 POP-UP NETWORK DEVICE	1.000 EACH				
0200	2520-3350010 FIELD LABORATORY	1.000 EACH				
0210	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM			
0220	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
0230	2599-9999010 (‘LUMP SUM’ ITEM) Prefabricated Bridge Superstructure Move	LUMP SUM	LUMP SUM			
0240	2599-9999010 (‘LUMP SUM’ ITEM) Prefabricated Bridge Superstructure Temporary Works	LUMP SUM	LUMP SUM			
Section: 0001			Total:			



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 54-0211-046-A

Call Order: 003

Letting Date: June 16, 2026

SECTION: 0002
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	2102-0425070 SPECIAL BACKFILL	158.700 TON				
0260	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	792.000 CY				
0270	2102-2710090 EXCAVATION, CLASS 10, WASTE	911.000 CY				
0280	2102-2712015 EXCAVATION, CLASS 12, BOULDERS OR ROCK FRAGMENTS	8.000 CY				
0290	2102-2713090 EXCAVATION, CLASS 13, WASTE	170.800 CY				
0300	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	421.000 CY				
0310	2107-0875100 COMPACTION WITH MOISTURE CONTROL	608.000 CY				
0320	2121-7425010 GRANULAR SHOULDERS, TYPE A	10.100 TON				
0330	2123-7450000 SHOULDER CONSTRUCTION, EARTH	4.500 STA				
0340	2301-0690205 BRIDGE APPROACH, BR-205	747.400 SY				
0350	2301-1033100 STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 10 IN.	251.900 SY				



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 54-0211-046-A

Call Order: 003

Letting Date: June 16, 2026

SECTION: 0002
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0360	2412-0000100 LONGITUDINAL GROOVING IN CONCRETE, BRIDGE DECK	1,011.900 SY				
0370	2503-0500402 BRIDGE END DRAIN, DR-402	4.000 EACH				
0380	2505-4008120 REMOVAL OF STEEL BEAM GUARDRAIL	582.000 LF				
0390	2505-4008300 STEEL BEAM GUARDRAIL	125.000 LF				
0400	2505-4008415 STEEL BEAM GUARDRAIL BARRIER TRANSITION SECTION, BA-209	4.000 EACH				
0410	2505-4021010 STEEL BEAM GUARDRAIL END ANCHOR, BOLTED	4.000 EACH				
0420	2505-4021720 STEEL BEAM GUARDRAIL TANGENT END TERMINAL, BA-205	4.000 EACH				
0430	2510-6745850 REMOVAL OF PAVEMENT	1,241.600 SY				
0440	2524-6765010 REMOVE AND REINSTALL SIGN AS PER PLAN	2.000 EACH				
0450	2527-9263209 PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	5.750 STA				
0460	2528-2518000 SAFETY CLOSURE	4.000 EACH				



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 54-0211-046-A

Call Order: 003

Letting Date: June 16, 2026

SECTION: 0002
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0470	2528-8400048 TEMPORARY BARRIER RAIL, CONCRETE	600.000 LF				
0480	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
0490	2528-8445113 FLAGGERS	10.000 EACH		630.00000		6,300.00
0500	2528-9290050 PORTABLE DYNAMIC MESSAGE SIGN (PDMS)	20.000 CDAY				
0510	2548-0000320 MILLED CENTERLINE RUMBLE STRIPS, PCC SURFACE	0.950 STA				
0520	2551-0000110 TEMP CRASH CUSHION	4.000 EACH				
0530	2601-2634100 MULCHING	4.000 ACRE				
0540	2601-2636015 NATIVE GRASS SEEDING	1.800 ACRE				
0550	2601-2636043 SEEDING AND FERTILIZING (RURAL)	0.200 ACRE				
0560	2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING	2.000 ACRE				
0570	2602-0000030 SILT FENCE FOR DITCH CHECKS	1,215.000 LF				
0580	2602-0000071 REMOVAL OF SILT FENCE OR SILT FENCE FOR DITCH CHECKS	1,215.000 LF				



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 54-0211-046-A

Call Order: 003

Letting Date: June 16, 2026

SECTION: 0002
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0590	2602-0000101 MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	1,215.000 LF				
0600	2602-0000150 STABILIZED CONSTRUCTION ENTRANCE, EC-303	400.000 LF				
0610	2602-0000312 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	3,140.000 LF				
0620	2602-0000351 REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	3,140.000 LF				
0630	2602-0010010 MOBILIZATIONS, EROSION CONTROL	1.000 EACH		600.00000		600.00
0640	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	1.000 EACH		1,200.00000		1,200.00
Section: 0002			Total:			



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 54-0211-046-A

Call Order: 003

Letting Date: June 16, 2026

SECTION: 0003

ALTERNATE 'AA' OPTION 1: PCC SHOULDER, BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0650	2102-0425070 SPECIAL BACKFILL PCC Option	359.000 TON				
0660	2122-5190008 PAVED SHOULDER, P.C. CONCRETE, 8 IN.	384.300 SY				
0670	2548-0000200 MILLED SHOULDER RUMBLE STRIPS, PCC SURFACE	2.910 STA				
Section: 0003			Total:			

SECTION: 0004

ALTERNATE 'AA' OPTION 2: HMA SHOULDER, BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0680	2102-0425070 SPECIAL BACKFILL HMA Option	331.900 TON				
0690	2122-5500090 PAVED SHOULDER, HOT MIX ASPHALT MIXTURE, 9 IN.	384.300 SY				
0700	2548-0000100 MILLED SHOULDER RUMBLE STRIPS, HMA SURFACE	2.910 STA				
0710	2548-0000110 ASPHALT EMULSION FOR FOG SEAL (SHOULDER RUMBLE STRIPS)	3.200 GAL				
Section: 0004			Total:			
			Total Bid:			