



CONTRACTS AND SPECIFICATIONS BUREAU Proposal

Proposal ID: 82-1827-703

Letting Date: June 16, 2026

Call Order: 104

Proposal Work Type: PCC PAVEMENT - GRADE & REPLACE

DBE Goal: 0.0%

Contracting Authority: CITY OF DAVENPORT

Proposal Guaranty: \$100,000.00

This proposal includes the following project(s):

Project Number: HDP-1827(703)--71-82

County: SCOTT

Project Work Type: PCC PAVEMENT - GRADE &
REPLACE

Route: 2ND ST

Location: In the city of Davenport, Raise and reconstruct the 2nd Strret and Gaines Street
intersection by 2 feet

Road System: URBAN

Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

Contract Time

Proposal ID: 82-1827-703

Call Order: 104

Letting Date: June 16, 2026

Site ID	Site Details			Liquidated Damages
00	Late Start Date	07/14/2026	60 WORK DAYS	\$1,000.00

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

Notes

Proposal ID: 82-1827-703

Call Order: 104

Letting Date: June 16, 2026

Notes :

There are no notes for this proposal.



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 82-1827-703

Call Order: 104

Letting Date: June 16, 2026

Note	Description
001.2023	<p>*** STANDARD SPECIFICATIONS -- SERIES 2023 ***</p> <p>The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.</p>
500.01	<p>*** WINTER WORK ***</p> <p>The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.</p>
660.26	<p>*** SPECIALTY ITEM ***</p> <p>The item 'TRAFFIC SIGNALIZATION' and/or 'TRAFFIC SIGNAL INSTALLATION' is considered a specialty item for this project.</p> <p>When performed by subcontract, the cost of the specialty item/s so performed by subcontract may be deducted from the total cost before computing the amount of work required to be performed by the Prime Contractor with his/her own organization. Refer to Article 1108.01 of the Standard Specifications.</p>
FHWA-1273.09	<p>FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023</p> <p>23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.</p>
GS-23006	<p>GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION</p>



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 82-1827-703

Call Order: 104

Letting Date: June 16, 2026

Note	Description
IA26-1.0	<p>PREDETERMINED WAGE RATES - GENERAL DECISION NUMBER IA20260001 FOR HEAVY AND HIGHWAY CONSTRUCTION -- SCOTT COUNTY IN IOWA</p> <p>*** Additional Requirement ***</p> <p>The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.</p>
SP-236057	<p>SPECIAL PROVISIONS FOR VIBRATION MONITORING TO PROTECT HISTORIC STRUCTURES</p> <p>Scott County HDP-1827(703)--71-82</p>
SS-23003	SUPPLEMENTAL SPECIFICATIONS FOR PORTLAND CEMENT CONCRETE STEPS



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 82-1827-703

Call Order: 104

Letting Date: June 16, 2026

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2101-0850002 CLEARING AND GRUBBING	258.400 UNIT				
0020	2102-2625001 EMBANKMENT-IN-PLACE, CONTRACTOR FURNISHED	1,062.200 CY				
0030	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	1,196.100 CY				
0040	2102-2710080 EXCAVATION, CLASS 10, UNSUITABLE OR UNSTABLE MATERIAL	450.000 CY				
0050	2105-8425005 TOPSOIL, FURNISH AND SPREAD	103.700 CY				
0060	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	240.000 CY				
0070	2109-8225100 SPECIAL COMPACTION OF SUBGRADE	18.000 STA				
0080	2111-8174100 GRANULAR SUBBASE	1,664.700 SY				
0090	2113-0001100 SUBGRADE STABILIZATION MATERIAL, POLYMER GRID	1,286.000 SY				
0100	2115-0100000 MODIFIED SUBBASE	1,174.000 CY				
0110	2210-0475290 MACADAM STONE BASE	600.000 TON				



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 82-1827-703

Call Order: 104

Letting Date: June 16, 2026

SECTION: 0001

ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	2301-1033100 STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 10 IN.	6,650.000 SY				
0130	2317-7000110 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR PCC PAVEMENT SMOOTHNESS (BY SCHEDULE)	6,650.000 EACH		1.00000	6,650.00	
0140	2401-6745359 REMOVAL OF CONCRETE FOUNDATIONS OF LIGHT POLES	18.000 EACH				
0150	2401-6745765 REMOVAL OF LIGHT POLES	18.000 EACH				
0160	2435-0140160 MANHOLE, STORM SEWER, SW-401, 60 IN.	2.000 EACH				
0170	2435-0250100 INTAKE, SW-501	3.000 EACH				
0180	2435-0250248 INTAKE, SW-502, 48 IN.	3.000 EACH				
0190	2435-0250500 INTAKE, SW-505	4.000 EACH				
0200	2435-0251218 INTAKE, SW-512, 18 IN.	3.000 EACH				
0210	2435-0600010 MANHOLE ADJUSTMENT, MINOR	5.000 EACH				
0220	2435-0600020 MANHOLE ADJUSTMENT, MAJOR	2.000 EACH				



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 82-1827-703

Call Order: 104

Letting Date: June 16, 2026

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0230	2499-7000000 PCC STEPS	12.000 SF				
0240	2502-6745952 REMOVAL OF SUBDRAIN	1,000.000 LF				
0250	2502-8212206 SUBDRAIN, PERFORATED PLASTIC PIPE, 6 IN. DIA.	1,166.000 LF				
0260	2502-8221303 SUBDRAIN OUTLET, DR-303	16.000 EACH				
0270	2503-0114212 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 12 IN.	84.000 LF				
0280	2503-0114215 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 15 IN.	431.000 LF				
0290	2503-0114224 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 24 IN.	96.000 LF				
0300	2503-0200036 REMOVE STORM SEWER PIPE LESS THAN OR EQUAL TO 36 IN.	567.000 LF				
0310	2503-0200341 STORM SEWER ABANDONMENT, FILL AND PLUG, LESS THAN OR EQUAL TO 36 IN. DIA.	14.000 LF				



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 82-1827-703

Call Order: 104

Letting Date: June 16, 2026

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0320	2510-6745850 REMOVAL OF PAVEMENT	7,220.500 SY				
0330	2510-6750600 REMOVAL OF INTAKES AND UTILITY ACCESSES	18.000 EACH				
0340	2511-6745900 REMOVAL OF SIDEWALK	829.800 SY				
0350	2511-7526005 SIDEWALK, P.C. CONCRETE, 5 IN.	1,011.300 SY				
0360	2511-7526006 SIDEWALK, P.C. CONCRETE, 6 IN.	558.100 SY				
0370	2511-7526008 SIDEWALK, P.C. CONCRETE, 8 IN.	69.600 SY				
0380	2511-7528101 DETECTABLE WARNINGS	188.000 SF				
0390	2515-2475008 DRIVEWAY, P.C. CONCRETE, 8 IN.	85.500 SY				
0400	2515-6745600 REMOVAL OF PAVED DRIVEWAY	108.000 SY				
0410	2523-0000100 LIGHTING POLES DECORATIVE	11.000 EACH				
0420	2523-0000100 LIGHTING POLES STREET	3.000 EACH				
0430	2523-0000200 ELECTRICAL CIRCUITS	600.000 LF				
0440	2523-0000310 HANDHOLES AND JUNCTION BOXES	14.000 EACH				



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 82-1827-703

Call Order: 104

Letting Date: June 16, 2026

SECTION: 0001

ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0450	2524-6765110 REMOVAL OF TYPE A SIGN	18.000 EACH				
0460	2524-9276010 PERFORATED SQUARE STEEL TUBE POSTS	169.000 LF				
0470	2524-9276021 PERFORATED SQUARE STEEL TUBE POST ANCHOR, BREAK-AWAY SOIL INSTALLATION	11.000 EACH				
0480	2524-9276024 PERFORATED SQUARE STEEL TUBE POST ANCHOR, BREAK-AWAY CONCRETE INSTALLATION	16.000 EACH				
0490	2524-9325001 TYPE A SIGNS, SHEET ALUMINUM	126.000 SF				
0500	2525-0000100 TRAFFIC SIGNALIZATION	LUMP SUM	LUMP SUM			
0510	2525-0000120 REMOVAL OF TRAFFIC SIGNALIZATION	LUMP SUM	LUMP SUM			
0520	2526-8285020 CONSTRUCTION SURVEY, CONTROL POINT SURVEY	LUMP SUM	LUMP SUM			
0530	2526-8285030 CONSTRUCTION SURVEY, RIGHT OF WAY	LUMP SUM	LUMP SUM			
0540	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM			
0550	2527-9263143 PAINTED SYMBOLS AND LEGENDS, DURABLE	12.000 EACH				



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 82-1827-703

Call Order: 104

Letting Date: June 16, 2026

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0560	2527-9263209 PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	21.730 STA				
0570	2527-9263217 PAINTED PAVEMENT MARKINGS, DURABLE	25.240 STA				
0580	2528-2518000 SAFETY CLOSURE	7.000 EACH				
0590	2528-8400256 TEMPORARY TRAFFIC SIGNALS	4.000 EACH				
0600	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
0610	2528-9290050 PORTABLE DYNAMIC MESSAGE SIGN (PDMS)	28.000 CDAY				
0620	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
0630	2554-0212020 VALVE BOX EXTENSION	2.000 EACH				
0640	2555-0000010 DELIVER AND STOCKPILE SALVAGED MATERIALS	LUMP SUM	LUMP SUM			
0650	2599-9999003 (‘CUBIC YARDS’ ITEM) RAISED CONCRETE PLANTER	13.500 CY				
0660	2599-9999009 (‘LINEAR FEET’ ITEM) LIGHTING CONDUIT, 2 INCH, PVC, TRENCHED	600.000 LF				



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 82-1827-703

Call Order: 104

Letting Date: June 16, 2026

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0670	2599-9999010 (‘LUMP SUM’ ITEM) VIBRATION MONITORING	LUMP SUM	LUMP SUM			
0680	2599-9999018 (‘SQUARE YARDS’ ITEM) BRICK PAVER REMOVAL	462.900 SY				
0690	2601-2639010 SODDING	185.500 SQ				
0700	2601-2642120 STABILIZING CROP - SEEDING AND FERTILIZING (URBAN)	0.100 ACRE				
0710	2601-2643110 WATERING FOR SOD, SPECIAL DITCH CONTROL, OR SLOPE PROTECTION	109.400 MGAL		75.00000		8,205.00
0720	2601-2643300 MOBILIZATION FOR WATERING	5.000 EACH		450.00000		2,250.00
0730	2602-0000312 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	1,820.000 LF				
0740	2602-0000320 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 20 IN. DIA.	1,770.000 LF				
0750	2602-0000351 REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	3,590.000 LF				
0760	2602-0000400 TEMPORARY INTAKE OR MANHOLE COVER ASSEMBLY	7.000 EACH				



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 82-1827-703

Call Order: 104

Letting Date: June 16, 2026

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0770	2602-0000410 MAINTENANCE OF TEMPORARY INTAKE OR MANHOLE COVER ASSEMBLY	7.000 EACH	_____	_____	_____	_____
0780	2602-0000420 REMOVAL OF TEMPORARY INTAKE OR MANHOLE COVER ASSEMBLY	7.000 EACH	_____	_____	_____	_____
0790	2602-0000530 GRATE INTAKE SEDIMENT FILTER BAG, EC-604	28.000 EACH	_____	_____	_____	_____
0800	2602-0000540 MAINTENANCE OF GRATE INTAKE SEDIMENT FILTER BAG	28.000 EACH	_____	_____	_____	_____
0810	2602-0000550 REMOVAL OF GRATE INTAKE SEDIMENT FILTER BAG	28.000 EACH	_____	_____	_____	_____
0820	2602-0010010 MOBILIZATIONS, EROSION CONTROL	2.000 EACH	600.00000		1,200.00	
0830	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	4.000 EACH	1,200.00000		4,800.00	
Section: 0001			Total:		_____	
			Total Bid:		_____	