



<b>CONTRACTS AND SPECIFICATIONS BUREAU Proposal</b>
---

---

**Proposal ID:** 81-1754-021**Letting Date:** June 16, 2026**Call Order:** 156**Proposal Work Type:** HMA RESURFACING WITH MILLING**DBE Goal:** 0.0%**Contracting Authority:** IOWA DEPARTMENT OF TRANSPORTATION**Proposal Guaranty:** \$375,000.00

---

**This proposal includes the following project(s):**

---

**Project Number:** NHSX-071-6(056)--3H-81**County:** SAC**Project Work Type:** HMA RESURFACING WITH MILLING**Route:** U.S. 71**Location:** S Jct IA 175 in Auburn to N Jct IA 175**Road System:** PRIMARY ROAD (on NHS)**Federal Aid - Wages:** Federal Aid - Predetermined Wages are in Effect

---

**Project Number:** STP-175-4(021)--2C-81**County:** SAC**Project Work Type:** HMA RESURFACING WITH MILLING**Route:** IOWA 175**Location:** IA 471 to W Jct. US 71**Road System:** PRIMARY ROAD (non-NHS)**Federal Aid - Wages:** Federal Aid - Predetermined Wages are in Effect

---

**Contract Time**

**Proposal ID:** 81-1754-021

**Call Order:** 156

**Letting Date:** June 16, 2026

Site ID	Site Details			Liquidated Damages
00	Late Start Date	07/20/2026	80 WORK DAYS	\$2,000.00
See description below.				
01	Late Start Date	04/05/2027	20 WORK DAYS	\$2,000.00
Seeding and erosion control. See description below.				

**(\*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit**



Contracts and Specifications Bureau

5/12/2026 11:34 AM

### Notes

---

**Proposal ID:** 81-1754-021

**Call Order:** 156

**Letting Date:** June 16, 2026

---

#### Notes :

\*\*\*Site 00\*\*\*

Completion of all work except Site 01 work.

\*\*\*Site 01\*\*\*

This site is for permanent seeding and the completion of erosion control and the needed removal of erosion control.



5/12/2026 11:34 AM

**Contracts and Specifications Bureau**

**Proposal Specifications List**

**Proposal ID:** 81-1754-021

**Call Order:** 156

**Letting Date:** June 16, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.
500.01	*** WINTER WORK *** The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.
DS-23032	DEVELOPMENTAL SPECIFICATIONS FOR ELECTRONIC TICKETING
DS-23078	DEVELOPMENTAL SPECIFICATIONS FOR HIGH PERFORMANCE THIN LIFT OVERLAY
DS-23079	DEVELOPMENTAL SPECIFICATIONS FOR PREFORMED THERMOPLASTIC PAVEMENT MARKINGS
DS-23085	DEVELOPMENTAL SPECIFICATIONS FOR DIAMOND GRINDING RUMBLE STRIPS
FHWA-1273.09	FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023 23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.
GS-23006	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 81-1754-021

Call Order: 156

Letting Date: June 16, 2026

Note	Description
IA26-28.0	<p>PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20260028 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY)</p> <p>Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract.</p> <p>*** Additional Requirement ***</p> <p>The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.</p>
SP-230414	<p>SPECIAL PROVISIONS FOR PENETRATING ENGINEERED FOG SEAL</p> <p>Sac County STP-175-4(021)--2C-81 NHSX-071-6(056)--3H-81</p>



5/12/2026 11:34 AM

## Contracts and Specifications Bureau

## Proposal Schedule of Items

Proposal ID: 81-1754-021

Call Order: 156

Letting Date: June 16, 2026

## SECTION: 0001

Roadway Items - NHSX-071-6(056)--3H-81

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2121-7425020 GRANULAR SHOULDERS, TYPE B	2,590.930 TON				
0020	2212-0475095 CLEANING AND PREPARATION OF BASE	6.940 MILE				
0030	2212-5070310 PATCHES, FULL-DEPTH REPAIR	471.900 SY				
0040	2212-5070330 PATCHES BY COUNT (REPAIR)	53.000 EACH				
0050	2212-5075001 HOT MIX ASPHALT SURFACE PATCHES	34.700 TON				
0060	2214-5145150 PAVEMENT SCARIFICATION, NOMINAL THICKNESS	98,393.800 SY				
0070	2303-0003380 HOT MIX ASPHALT MIXTURE THIN LIFT SURFACE COURSE, 3/8 IN. MIX	8,079.300 TON				
0080	2303-1043500 HOT MIX ASPHALT HIGH TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT	684.900 TON				
0090	2303-1258284 ASPHALT BINDER, PG 58-28H, HIGH TRAFFIC	3.400 TON				
0100	2303-1264347 ASPHALT BINDER, PG 64-34E+, EXTREMELY HIGH TRAFFIC, 90% ELASTIC RECOVERY	646.400 TON				
0110	2303-6911000 HOT MIX ASPHALT PAVEMENT SAMPLES	LUMP SUM	LUMP SUM			



5/12/2026 11:34 AM

## Contracts and Specifications Bureau

## Proposal Schedule of Items

Proposal ID: 81-1754-021

Call Order: 156

Letting Date: June 16, 2026

## SECTION: 0001

Roadway Items - NHSX-071-6(056)--3H-81

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	2308-1000000 ASPHALT EMULSION FOR FOG SEAL (SHOULDERS)	1,628.500 GAL				
0130	2317-7000120 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR HMA PAVEMENT SMOOTHNESS (BY SCHEDULE)	23,450.200 EACH		1.00000	23,450.20	
0140	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM			
0150	2527-9263155 PRE-CUT SYMBOLS AND LEGENDS, PREFORMED THERMOPLASTIC MARKING MATERIAL	8.000 EACH				
0160	2527-9263209 PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	2,922.090 STA				
0170	2527-9263225 PERMANENT TAPE MARKINGS, PREFORMED THERMOPLASTIC MARKING MATERIAL	35.980 STA				
0180	2527-9270112 GROOVES CUT FOR PAVEMENT MARKINGS	799.700 STA				
0190	2527-9270120 GROOVES CUT FOR SYMBOLS AND LEGENDS	8.000 EACH				
0200	2528-2518000 SAFETY CLOSURE	2.000 EACH				
0210	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 81-1754-021

Call Order: 156

Letting Date: June 16, 2026

SECTION: 0001

Roadway Items - NHSX-071-6(056)--3H-81

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0220	2528-8445113 FLAGGERS	30.000 EACH		630.00000		18,900.00
0230	2528-8445115 PILOT CARS	15.000 EACH		945.00000		14,175.00
0240	2529-5070110 PATCHES, FULL-DEPTH FINISH, BY AREA	104.900 SY		_____.		_____.
0250	2529-5070120 PATCHES, FULL-DEPTH FINISH, BY COUNT	12.000 EACH		_____.		_____.
0260	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			_____.
0270	2548-0000310 MILLED CENTERLINE RUMBLE STRIPS, HMA SURFACE	356.120 STA		_____.		_____.
0280	2548-0000315 ENGINEERED EMULSION FOR FOG SEAL (CENTERLINE RUMBLE STRIPS)	385.780 GAL		_____.		_____.
0290	2548-0000365 DIAMOND GROUND CENTERLINE SINUSOIDAL RUMBLE STRIPS, PCC SURFACE	40.540 STA		_____.		_____.
Section: 0001			Total:			_____.



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 81-1754-021

Call Order: 156

Letting Date: June 16, 2026

SECTION: 0002

Roadway Items - STP-175-4(021)--2C-81

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0300	2102-2625000 EMBANKMENT-IN-PLACE	254.000 CY				
0310	2102-2713090 EXCAVATION, CLASS 13, WASTE	7,908.200 CY				
0320	2121-7425020 GRANULAR SHOULDERS, TYPE B	9,587.800 TON				
0330	2123-7450020 SHOULDER FINISHING, EARTH	6.950 STA				
0340	2212-0475095 CLEANING AND PREPARATION OF BASE	9.250 MILE				
0350	2212-5070310 PATCHES, FULL-DEPTH REPAIR	680.100 SY				
0360	2212-5070330 PATCHES BY COUNT (REPAIR)	81.000 EACH				
0370	2212-5075001 HOT MIX ASPHALT SURFACE PATCHES	46.250 TON				
0380	2214-5145150 PAVEMENT SCARIFICATION, NOMINAL THICKNESS	121,511.300 SY				
0390	2214-7450050 BLADING AND SHAPING SHOULDER MATERIAL	917.180 STA				
0400	2301-0690203 BRIDGE APPROACH, BR-203	333.400 SY				
0410	2303-0003380 HOT MIX ASPHALT MIXTURE THIN LIFT SURFACE COURSE, 3/8 IN. MIX	13,320.000 TON				



5/12/2026 11:34 AM

## Contracts and Specifications Bureau

## Proposal Schedule of Items

Proposal ID: 81-1754-021

Call Order: 156

Letting Date: June 16, 2026

## SECTION: 0002

## Roadway Items - STP-175-4(021)--2C-81

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0420	2303-1031750 HOT MIX ASPHALT STANDARD TRAFFIC, BASE COURSE, 3/4 IN. MIX	11,487.980 TON				
0430	2303-1043500 HOT MIX ASPHALT HIGH TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, NO SPECIAL FRICTION REQUIREMENT	148.120 TON				
0440	2303-1258283 ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC	689.280 TON				
0450	2303-1258284 ASPHALT BINDER, PG 58-28H, HIGH TRAFFIC	8.880 TON				
0460	2303-1264347 ASPHALT BINDER, PG 64-34E+, EXTREMELY HIGH TRAFFIC, 90% ELASTIC RECOVERY	1,065.600 TON				
0470	2303-6911000 HOT MIX ASPHALT PAVEMENT SAMPLES	LUMP SUM	LUMP SUM			
0480	2317-7000120 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR HMA PAVEMENT SMOOTHNESS (BY SCHEDULE)	29,163.000 EACH		1.00000	29,163.00	
0490	2505-4008120 REMOVAL OF STEEL BEAM GUARDRAIL	510.000 LF				
0500	2505-4008300 STEEL BEAM GUARDRAIL	350.000 LF				
0510	2505-4008410 STEEL BEAM GUARDRAIL BARRIER TRANSITION SECTION, BA-201	4.000 EACH				



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 81-1754-021

Call Order: 156

Letting Date: June 16, 2026

SECTION: 0002

Roadway Items - STP-175-4(021)--2C-81

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0520	2505-4021720 STEEL BEAM GUARDRAIL TANGENT END TERMINAL, BA-205	4.000 EACH				
0530	2510-6745850 REMOVAL OF PAVEMENT	435.600 SY				
0540	2524-6765010 REMOVE AND REINSTALL SIGN AS PER PLAN	2.000 EACH				
0550	2524-9265010 POSTS, STEEL, AS PER PLAN	1.000 EACH				
0560	2524-9276024 PERFORATED SQUARE STEEL TUBE POST ANCHOR, BREAK-AWAY CONCRETE INSTALLATION	1.000 EACH				
0570	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM			
0580	2527-9263155 PRE-CUT SYMBOLS AND LEGENDS, PREFORMED THERMOPLASTIC MARKING MATERIAL	17.000 EACH				
0590	2527-9263181 PAVEMENT MARKINGS REMOVED	33.750 STA				
0600	2527-9263209 PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	3,465.100 STA				
0610	2527-9263225 PERMANENT TAPE MARKINGS, PREFORMED THERMOPLASTIC MARKING MATERIAL	2.160 STA				



5/12/2026 11:34 AM

## Contracts and Specifications Bureau

## Proposal Schedule of Items

Proposal ID: 81-1754-021

Call Order: 156

Letting Date: June 16, 2026

## SECTION: 0002

## Roadway Items - STP-175-4(021)--2C-81

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0620	2527-9263231 REMOVABLE TAPE MARKINGS, WET RETROREFLECTIVE	122.880 STA				
0630	2527-9270112 GROOVES CUT FOR PAVEMENT MARKINGS	1,047.830 STA				
0640	2527-9270120 GROOVES CUT FOR SYMBOLS AND LEGENDS	17.000 EACH				
0650	2528-8400048 TEMPORARY BARRIER RAIL, CONCRETE	712.000 LF				
0660	2528-8400256 TEMPORARY TRAFFIC SIGNALS	1.000 EACH				
0670	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
0680	2528-8445113 FLAGGERS	100.000 EACH		630.00000		63,000.00
0690	2528-8445115 PILOT CARS	50.000 EACH		945.00000		47,250.00
0700	2529-5070110 PATCHES, FULL-DEPTH FINISH, BY AREA	37.500 SY				
0710	2529-5070120 PATCHES, FULL-DEPTH FINISH, BY COUNT	1.000 EACH				
0720	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			



5/12/2026 11:34 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 81-1754-021

Call Order: 156

Letting Date: June 16, 2026

SECTION: 0002

Roadway Items - STP-175-4(021)--2C-81

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0730	2548-0000100 MILLED SHOULDER RUMBLE STRIPS, HMA SURFACE	819.500 STA	_____	_____	_____	_____
0740	2548-0000110 ASPHALT EMULSION FOR FOG SEAL (SHOULDER RUMBLE STRIPS)	887.800 GAL	_____	_____	_____	_____
0750	2548-0000310 MILLED CENTERLINE RUMBLE STRIPS, HMA SURFACE	409.750 STA	_____	_____	_____	_____
0760	2548-0000317 ENGINEERED EMULSION FOR FOG SEAL (CENTERLINE RUMBLE STRIPS)	6,829.200 SY	_____	_____	_____	_____
0770	2551-0000110 TEMP CRASH CUSHION	2.000 EACH	_____	_____	_____	_____
Section: 0002			Total:		_____	_____
			Total Bid:		_____	_____