Refer to Standard Road Plans EW-101 and EW-102.

TABULATION OF TEMPLATE QUANTITIES AND ADJUSTMENTS

107-28
04-21-15

Station	Cut					Fill				Checks (EW-102)		Topsoil										
	[1]	[2]	[3]	[4]	[5]	[6]	[7]	[8]	[9]	[10]	[11]	[12]	[13]	[14]	[15]	[16]	[17]	[18]	[19]	[20]	[21]	[22]
	Total Cut Unadjusted Volume	Total Class 10 Unadjusted Volume	Topsoil Cut Volume	Template Pavement Removal Volume	Total Cut Adjusted	Total Fill Unadjusted Volume	Total Fill Adjusted	Total Fill Adjusted w/ Weighted Average 1.3 Shrink Factor	Total Cut Adjusted Minus Fill w/ Shrink	Approx. Fill Vol. Below 5' & Above 20' w/ Shrink	Approx. Fill Volume Below 3' w/ Shrink	Topsoil Stripping Undercut Volume	Topsoil Placement Undercut Volume	Topsoil Placement With 1.4 Shrink Factor	Topsoil Stripping Minus Topsoil Placement w/Shrink							
US65																						
835+96.42																						
836+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0							
836+25.00	31	15	12	3	15	8	8	11	5	0	0	12	2	3	9							
836+50.00	61	31	23	7	31	19	19	25	6	0	0	23	4	6	18							
836+75.00	62	30	24	8	30	22	22	29	2	0	0	24	5	6	18							
837+00.00	62	31	22	10	31	15	15	19	12	0	0	22	4	6	16							
837+25.00	64	35	17	12	35	7	7	9	25	0	0	17	3	4	14							
837+50.00	68	41	13	14	41	4	4	5	36	0	0	13	1	1	12							
837+75.00	69	43	11	15	43	3	3	4	40	0	0	11	0	0	11							
838+00.00	69	41	12	15	41	4	4	5	36	0	0	12	1	1	11							
838+25.00	69	38	15	15	38	5	5	7	31	0	0	15	2	3	12							
838+50.00	67	37	14	16	37	4	4	6	32	0	0	14	1	2	12							
838+75.00	66	35	16	15	35	7	7	10	25	0	0	16	2	3	13							
839+00.00	87	41	20	26	41	16	16	21	20	0	0	20	4	6	14							
839+25.00	106	48	22	36	48	20	20	26	22	0	0	22	4	6	16							
839+50.00	101	46	22	33	46	11	11	14	32	0	0	22	2	3	19							
839+75.00	245	190	25	31	190	2	2	3	187	0	0	25	0	0	25							
840+00.00	311	267	30	15	267	1	1	2	265	0	0	30	0	0	30							
840+25.00	117	100	16	0	100	1	1	1	99	0	0	16	0	0	16							
840+50.00	74	63	11	0	63	0	0	0	63	0	0	11	0	0	11							
840+75.00	295	259	27	9	259	0	0	0	259	0	0	27	0	0	27							
841+00.00	344	288	31	25	288	10	10	13	275	0	0	31	3	4	27							
841+25.00	174	114	27	33	114	16	16	21	93	0	0	27	5	7	20							
841+50.00	104	46	24	33	46	11	11	14	32	0	0	24	5	7	18							
841+75.00	107	50	24	33	50	9	9	12	38	0	0	24	5	8	16							
842+00.00	88	43	24	20	43	7	7	10	34	0	0	24	8	11	13							
842+25.00	67	35	24	8	35	6	6	8	27	0	0	24	9	13	11							
842+50.00	68	35	25	8	35	5	5	7	28	0	0	25	9	13	12							
842+75.00	66	34	24	8	34	4	4	6	29	0	0	24	9	13	11							
843+00.00	63	33	22	8	33	4	4	5	29	0	0	22	8	11	11							
843+25.00	62	32	21	8	32	4	4	5	28	0	0	21	7	10	11							
843+50.00	61	32	21	8	32	4	4	5	27	0	0	21	7	10	11							
843+75.00	61	32	21	8	32	4	4	5	26	0	0	21	7	10	11							
844+00.00	60	31	21	8	31	4	4	5	26	0	0	21	7	11	11							
844+25.00	48	25	17	6	25	3	3	5	20	0	0	17	6	9	9							
844+50.00	37	20	14	4	20	3	3	4	16	0	0	14	5	7	7							
844+55.00	7	4	3	1	4	1	1	1	3	0	0	3	1	1	1							
US65																						
Totals:	3,441	2,246	696	499	2,246	245	245	320	1,928	0	0	696	137	192	506							

FILE NO.	ENGLISH	DESIGN TEAM MILLER\SCHOENROCK\EVANS	WARREN COUNTY	PROJECT NUMBER BRF-065-3(087)--38-91	SHEET NUMBER T.1

Refer to Standard Road Plans EW-101 and EW-102.

TABULATION OF TEMPLATE QUANTITIES AND ADJUSTMENTS

107-28
04-21-15

Station	Cut					Fill				Checks (EW-102)		Topsoil										
	[1]	[2]	[3]	[4]	[5]	[6]	[7]	[8]	[9]	[10]	[11]	[12]	[13]	[14]	[15]	[16]	[17]	[18]	[19]	[20]	[21]	[22]
	Total Cut Unadjusted Volume	Total Class 10 Unadjusted Volume	Topsoil Cut Volume	Template Pavement Removal Volume	Total Cut Adjusted	Total Fill Unadjusted Volume	Total Fill Adjusted	Total Fill Adjusted w/ Weighted Average 1.3 Shrink Factor	Total Cut Adjusted Minus Fill w/ Shrink	Approx. Fill Vol. Below 5' & Above 20' w/ Shrink	Approx. Fill Volume Below 3' w/ Shrink	Topsoil Stripping Undercut Volume	Topsoil Placement Undercut Volume	Topsoil Placement With 1.4 Shrink Factor	Topsoil Stripping Minus Topsoil Placement w/Shrink							
Summary:																						
US65	3,441	2,246	696	499	2,246	245	245	320	1,928	0	0	696	137	192	506							
Project Totals:	3,441	2,246	696	499	2,246	245	245	320	1,928	0	0	696	137	192	506							

FILE NO.	ENGLISH	DESIGN TEAM MILLER\SCHOENROCK\EVANS	WARREN COUNTY	PROJECT NUMBER BRF-065-3(087)--38-91	SHEET NUMBER T.2