



CONTRACTS AND SPECIFICATIONS BUREAU Proposal

Proposal ID: 03-C003-069**Letting Date:** November 17, 2026**Call Order:** 002**Proposal Work Type:** BRIDGE REPLACEMENT - PPCB**DBE Goal:** 0.0%**Contracting Authority:** ALLAMAKEE COUNTY**Proposal Guaranty:** \$250,000.00

This proposal includes the following project(s):

Project Number: BROSCHBP-C003(69)--NC-03**County:** ALLAMAKEE**Project Work Type:** BRIDGE REPLACEMENT - PPCB**Route:** SUTTLE CREEK ROAD**Location:** On Suttle Creek Road, Over YELLOW RIVER, S18 T96N R04W**Road System:** LOCAL SECONDARY ROAD**Federal Aid - Wages:** Federal Aid - Predetermined Wages are in Effect

Project Number: BROSCHBP-C009(86)--GA-09**County:** BREMER**Project Work Type:** BRIDGE REPLACEMENT - PPCB**Route:** V19**Location:** On V19, Over QUARTER SEC RUN, S20 T91 R13**Road System:** FARM TO MARKET ROAD**Federal Aid - Wages:** Federal Aid - Predetermined Wages are in Effect

Project Number: BROSCHBP-C009(95)--NC-09**County:** BREMER**Project Work Type:** RCB CULVERT REPLACEMENT -
TRIPLE BOX**Route:** 240TH STREET**Location:** On 240TH ST, Over CREEK, S17 T91 R14**Road System:** LOCAL SECONDARY ROAD**Federal Aid - Wages:** Federal Aid - Predetermined Wages are in Effect

Contract Time

Proposal ID: 03-C003-069

Call Order: 002

Letting Date: November 17, 2026

Site ID	Site Details			Liquidated Damages
00	Late Start Date	05/17/2027	100 WORK DAYS	\$1,800.00
	BROSCHBP-C003(69)--NC-03			
01	Late Start Date	07/12/2027	65 WORK DAYS	\$1,800.00
	BROSCHBP-C009(86)--GA-09			
02	Late Start Date	06/14/2027	80 WORK DAYS	\$1,800.00
	BROSCHBP-C009(95)--NC-09			

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit



Contracts and Specifications Bureau

10/14/2026 9:26 AM

Notes

Proposal ID: 03-C003-069

Call Order: 002

Letting Date: November 17, 2026

Notes :

*** WINTER WORK ***

BROSCHBP-C003(69)--NC-03: The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.

BROSCHBP-C009(86)--GA-09 and BROSCHBP-C009(95)--NC-09
Winter Work will be allowed during the winter 2026/2027 for these two projects. No working days will be charged between November 15, 2026 and April 1, 2027.



10/14/2026 9:26 AM

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 03-C003-069

Call Order: 002

Letting Date: November 17, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 03-C003-069

Call Order: 002

Letting Date: November 17, 2026

Note	Description																						
005.1107.02	*** Revisions to Article 1107.02 *** Article 1107.02, Insurance, is amended by the following modifications and additions. This proposal note becomes null and void January 1, 2027. A. It shall be the Contractor's responsibility to have liability insurance covering all of the construction operations incident to contract completion and the Contractor must have on file with the Contracting Authority a current "Certificate of Insurance" prior to award of contract. The certificate shall identify the insurance company firm name and address, Contractor firm name, policy period, type of policy, limits of coverage, and scope of work covered (single contract or statewide). This requirement shall apply with equal force, whether the work is performed by persons employed directly by the Contractor including a subcontractor, persons employed by a subcontractor, or by an independent contractor. B. In addition to the above, the Contracting Authority shall be included as an insured party, or a separate owner's protective policy shall be filed showing the Contracting Authority as an insured party. C. The liability insurance shall be written by an insurance company (or companies) qualified to do business in Iowa. For independent contractors engaged solely in the transportation of materials, the minimum coverage provided by such insurance shall be not less than that required by Chapter 325A, Code of Iowa, for such truck operators or contract carriers as defined therein. For all other contractors, subcontractors, independent contractors, and the Contracting Authority, the minimum coverage by such insurance shall be as follows: <table> <tr> <td>General Liability, Including:</td><td>BODILY INJURY</td></tr> <tr> <td>Independent Contractors</td><td>\$500,000 Each Occurrence</td></tr> <tr> <td>Contractual Liability,</td><td>\$500,000 Aggregate</td></tr> <tr> <td>Products and Completed</td><td>PROPERTY DAMAGE</td></tr> <tr> <td>Operations</td><td>\$250,000 Each Occurrence</td></tr> <tr> <td></td><td>\$250,000 Aggregate</td></tr> <tr> <td></td><td>or</td></tr> <tr> <td></td><td>BODILY INJURY AND PROPERTY DAMAGE</td></tr> <tr> <td></td><td>- COMBINED SINGLE LIMIT*</td></tr> <tr> <td></td><td>\$750,000 Each Occurrence</td></tr> <tr> <td></td><td>\$750,000 Aggregate</td></tr> </table> *A comprehensive Catastrophe Liability Policy (Umbrella) can be used to aid in	General Liability, Including:	BODILY INJURY	Independent Contractors	\$500,000 Each Occurrence	Contractual Liability,	\$500,000 Aggregate	Products and Completed	PROPERTY DAMAGE	Operations	\$250,000 Each Occurrence		\$250,000 Aggregate		or		BODILY INJURY AND PROPERTY DAMAGE		- COMBINED SINGLE LIMIT*		\$750,000 Each Occurrence		\$750,000 Aggregate
General Liability, Including:	BODILY INJURY																						
Independent Contractors	\$500,000 Each Occurrence																						
Contractual Liability,	\$500,000 Aggregate																						
Products and Completed	PROPERTY DAMAGE																						
Operations	\$250,000 Each Occurrence																						
	\$250,000 Aggregate																						
	or																						
	BODILY INJURY AND PROPERTY DAMAGE																						
	- COMBINED SINGLE LIMIT*																						
	\$750,000 Each Occurrence																						
	\$750,000 Aggregate																						

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 03-C003-069

Call Order: 002

Letting Date: November 17, 2026

Note	Description
	achieving the minimum required limits.
	D. Failure on the part of the Contractor to comply with the requirements of this article will be considered sufficient cause to suspend the work, withhold estimates, and to deny the Contractor from receiving further contract awards, as provided in Article 1103.01.
410.11	*** STORM WATER POLLUTION PREVENTION PLAN *** A Storm Water Pollution Prevention Plan has been developed by the Contracting Authority for one or more projects on this contract. See the project plans (or other contract document) for specific Storm Water Pollution Prevention Plan details.
500.2027	*** NO WINTER FREE TIME *** The free time allowed between November 15 and April 1 will not be permitted on this project during the winter of 2027-2028. The Contractor shall work during the winter on all working days as defined in article 1101.03 'working day'.
DS-23011	DEVELOPMENTAL SPECIFICATIONS FOR FLOATING SILT CURTAIN
FHWA-1273.09	FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023 23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.
GS-23007	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, OCTOBER 20, 2026 RELEASE
IA26-28.4A	PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20260028 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY) Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract.



10/14/2026 9:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 03-C003-069

Call Order: 002

Letting Date: November 17, 2026

SECTION: 0001

Items for a 201'-4 x 30'-0 Pretensioned Prestressed Concrete Beam Bridge - (069)

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2101-0850001 CLEARING AND GRUBBING	0.800 ACRE				
0020	2102-2625001 EMBANKMENT-IN-PLACE, CONTRACTOR FURNISHED	15,480.000 CY				
0030	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	192.000 CY				
0040	2104-2710020 EXCAVATION, CLASS 10, CHANNEL	710.000 CY				
0050	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	1,000.000 CY				
0060	2123-7450020 SHOULDER FINISHING, EARTH	31.800 STA				
0070	2210-0475290 MACADAM STONE BASE	1,950.000 TON				
0080	2213-7100400 RELOCATION OF MAIL BOXES	2.000 EACH				
0090	2301-0690220 BRIDGE APPROACH, SECONDARY ROADS	70.100 SY				
0100	2307-0025003 AGGREGATE, ROADWAY COVER, 3/8 IN.	70.000 TON				
0110	2307-0600456 BINDER BITUMEN, CRS-2P	1,639.000 GAL				
0120	2312-8260051 GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE	330.000 TON				



10/14/2026 9:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 03-C003-069

Call Order: 002

Letting Date: November 17, 2026

SECTION: 0001

Items for a 201'-4 x 30'-0 Pretensioned Prestressed Concrete Beam Bridge - (069)

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	2315-8275025 SURFACING, DRIVEWAY, CLASS A CRUSHED STONE	250.000 TON				
0140	2401-6745625 REMOVAL OF EXISTING BRIDGE	LUMP SUM	LUMP SUM			
0150	2402-0425030 GRANULAR BACKFILL	90.000 CY				
0160	2402-2720000 EXCAVATION, CLASS 20	105.000 CY				
0170	2402-2720100 EXCAVATION, CLASS 20, FOR ROADWAY PIPE CULVERT	40.000 CY				
0180	2402-2721000 EXCAVATION, CLASS 21	345.000 CY				
0190	2402-2722000 EXCAVATION, CLASS 22	50.000 CY				
0200	2403-0100010 STRUCTURAL CONCRETE (BRIDGE)	501.000 CY				
0210	2404-7775005 REINFORCING STEEL, EPOXY COATED	97,280.000 LB				
0220	2407-0551363 BEAMS, PRETENSIONED PRESTRESSED CONCRETE, C63	10.000 EACH				
0230	2407-0551371 BEAMS, PRETENSIONED PRESTRESSED CONCRETE, C71	5.000 EACH				
0240	2408-7800000 STRUCTURAL STEEL	5,182.000 LB				



10/14/2026 9:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 03-C003-069

Call Order: 002

Letting Date: November 17, 2026

SECTION: 0001

Items for a 201'-4 x 30'-0 Pretensioned Prestressed Concrete Beam Bridge - (069)

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	2414-6424110 CONCRETE BARRIER RAILING	462.900 LF				
0260	2417-0225024 APRONS, METAL, 24 IN. DIA.	4.000 EACH				
0270	2417-1060024 CULVERT, CORRUGATED METAL ROADWAY PIPE, 24 IN. DIA.	115.000 LF				
0280	2499-2300001 DECK DRAINS	LUMP SUM	LUMP SUM			
0290	2501-0201057 PILES, STEEL, HP 10 X 57	540.000 LF				
0300	2501-6335010 PREBORED HOLES	80.000 LF				
0310	2503-0200036 REMOVE STORM SEWER PIPE LESS THAN OR EQUAL TO 36 IN.	85.000 LF				
0320	2503-0200341 STORM SEWER ABANDONMENT, FILL AND PLUG, LESS THAN OR EQUAL TO 36 IN. DIA.	79.000 LF				
0330	2507-3250005 ENGINEERING FABRIC	717.000 SY				
0340	2507-4011100 CONCRETE GROUT FOR REVTMENT OR GABION	42.000 CY				
0350	2507-6800061 REVTMENT, CLASS E	750.000 TON				
0360	2524-6765010 REMOVE AND REINSTALL SIGN AS PER PLAN	2.000 EACH				



10/14/2026 9:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 03-C003-069

Call Order: 002

Letting Date: November 17, 2026

SECTION: 0001

Items for a 201'-4 x 30'-0 Pretensioned Prestressed Concrete Beam Bridge - (069)

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0370	2524-6765210 REMOVAL OF TYPE A SIGN ASSEMBLY	6.000 EACH				
0380	2524-9100030 OBJECT MARKER, TYPE 3	4.000 EACH				
0390	2524-9276010 PERFORATED SQUARE STEEL TUBE POSTS	153.000 LF				
0400	2524-9276021 PERFORATED SQUARE STEEL TUBE POST ANCHOR, BREAK-AWAY SOIL INSTALLATION	15.000 EACH				
0410	2524-9325001 TYPE A SIGNS, SHEET ALUMINUM	74.300 SF				
0420	2527-9263209 PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	18.750 STA				
0430	2528-2518000 SAFETY CLOSURE	4.000 EACH				
0440	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
0450	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
0460	2599-9999020 (‘TONS’ ITEM) MODIFIED SUBBASE	570.000 TON				
0470	2601-2636015 NATIVE GRASS SEEDING	1.100 ACRE				
0480	2601-2636043 SEEDING AND FERTILIZING (RURAL)	0.500 ACRE				



10/14/2026 9:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 03-C003-069

Call Order: 002

Letting Date: November 17, 2026

SECTION: 0001

Items for a 201'-4 x 30'-0 Pretensioned Prestressed Concrete Beam Bridge - (069)

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0490	2601-2638352 SLOPE PROTECTION, WOOD EXCELSIOR MAT	355.000 SQ				
0500	2602-0000212 FLOATING SILT CURTAIN (HANGING)	350.000 LF				
0510	2602-0000240 MAINTENANCE OF FLOATING SILT CURTAIN	200.000 LF				
0520	2602-0000312 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	1,465.000 LF				
0530	2602-0000351 REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	1,465.000 LF				
0540	2602-0010010 MOBILIZATIONS, EROSION CONTROL	3.000 EACH		600.00000		1,800.00
0550	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	2.000 EACH		1,200.00000		2,400.00
Section: 0001			Total:			



10/14/2026 9:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 03-C003-069

Call Order: 002

Letting Date: November 17, 2026

SECTION: 0002

Items for a 213'-0 x 30'-6 Pretensioned Prestressed Concrete Beam Bridge - (086)

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0560	2101-0850001 CLEARING AND GRUBBING	1.200 ACRE				
0570	2102-2625000 EMBANKMENT-IN-PLACE	294.000 CY				
0580	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	1,300.000 CY				
0590	2104-2710020 EXCAVATION, CLASS 10, CHANNEL	3,200.000 CY				
0600	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	1,650.000 CY				
0610	2312-8260051 GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE	350.000 TON				
0620	2401-6745625 REMOVAL OF EXISTING BRIDGE	LUMP SUM	LUMP SUM			
0630	2402-2720000 EXCAVATION, CLASS 20	215.000 CY				
0640	2402-2721000 EXCAVATION, CLASS 21	225.000 CY				
0650	2403-0100010 STRUCTURAL CONCRETE (BRIDGE)	444.400 CY				
0660	2404-7775000 REINFORCING STEEL	99,114.000 LB				
0670	2407-0551367 BEAMS, PRETENSIONED PRESTRESSED CONCRETE, C67	10.000 EACH				



10/14/2026 9:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 03-C003-069

Call Order: 002

Letting Date: November 17, 2026

SECTION: 0002

Items for a 213'-0 x 30'-6 Pretensioned Prestressed Concrete Beam Bridge - (086)

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0680	2407-0551375 BEAMS, PRETENSIONED PRESTRESSED CONCRETE, C75	5.000 EACH				
0690	2408-7800000 STRUCTURAL STEEL	4,287.000 LB				
0700	2414-6424124 CONCRETE OPEN RAILING, TL-4	481.700 LF				
0710	2417-1040018 CULVERT, CORRUGATED METAL ENTRANCE PIPE, 18 IN. DIA.	70.000 LF				
0720	2417-1040024 CULVERT, CORRUGATED METAL ENTRANCE PIPE, 24 IN. DIA.	100.000 LF				
0730	2501-0201057 PILES, STEEL, HP 10 X 57	2,745.000 LF				
0740	2501-6335010 PREBORED HOLES	180.000 LF				
0750	2505-4008300 STEEL BEAM GUARDRAIL	50.000 LF				
0760	2505-4008420 STEEL BEAM GUARDRAIL BARRIER TRANSITION SECTION, BA-221	4.000 EACH				
0770	2505-4021010 STEEL BEAM GUARDRAIL END ANCHOR, BOLTED	4.000 EACH				
0780	2505-4021722 STEEL BEAM GUARDRAIL TANGENT END TERMINAL, BA-225	4.000 EACH				
0790	2507-3250005 ENGINEERING FABRIC	1,750.000 SY				



10/14/2026 9:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 03-C003-069

Call Order: 002

Letting Date: November 17, 2026

SECTION: 0002

Items for a 213'-0 x 30'-6 Pretensioned Prestressed Concrete Beam Bridge - (086)

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0800	2507-6800061 REVTMENT, CLASS E	1,200.000 TON				
0810	2507-6875002 REVTMENT, REMOVE AND REPLACE	25.000 CY				
0820	2526-8285010 CONSTRUCTION SURVEY, MONUMENT PRESERVATION	LUMP SUM	LUMP SUM			
0830	2526-8285020 CONSTRUCTION SURVEY, CONTROL POINT SURVEY	LUMP SUM	LUMP SUM			
0840	2526-8285030 CONSTRUCTION SURVEY, RIGHT OF WAY	LUMP SUM	LUMP SUM			
0850	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM			
0860	2528-2518000 SAFETY CLOSURE	2.000 EACH				
0870	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
0880	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
0890	2601-2634100 MULCHING	4.000 ACRE				
0900	2601-2636043 SEEDING AND FERTILIZING (RURAL)	2.000 ACRE				
0910	2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING	2.000 ACRE				



10/14/2026 9:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 03-C003-069

Call Order: 002

Letting Date: November 17, 2026

SECTION: 0002

Items for a 213'-0 x 30'-6 Pretensioned Prestressed Concrete Beam Bridge - (086)

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0920	2602-0000020 SILT FENCE	1,170.000 LF				
0930	2602-0000030 SILT FENCE FOR DITCH CHECKS	150.000 LF				
0940	2602-0000101 MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	1,320.000 LF				
0950	2602-0000160 ROCK CHECK DAM	75.000 LF				
0960	2602-0000170 MAINTENANCE OF ROCK CHECK DAM	3.000 EACH				
0970	2602-0000312 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	490.000 LF				
0980	2602-0010010 MOBILIZATIONS, EROSION CONTROL	1.000 EACH		600.00000		600.00
0990	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	1.000 EACH		1,200.00000		1,200.00
Section: 0002			Total:			



10/14/2026 9:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 03-C003-069

Call Order: 002

Letting Date: November 17, 2026

SECTION: 0003

Items for a Triple 14' x 7' x 62' Reinforced Concrete Box Culvert - (095)

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1000	2101-0850001 CLEARING AND GRUBBING	0.500 ACRE				
1010	2102-0425070 SPECIAL BACKFILL	185.000 TON				
1020	2102-2625000 EMBANKMENT-IN-PLACE	1,140.000 CY				
1030	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	790.000 CY				
1040	2104-2710020 EXCAVATION, CLASS 10, CHANNEL	135.000 CY				
1050	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	1,050.000 CY				
1060	2107-0425020 COMPACTING BACKFILL ADJACENT TO BRIDGES, CULVERTS OR STRUCTURES	45.000 CY				
1070	2312-8260051 GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE	300.000 TON				
1080	2401-6745625 REMOVAL OF EXISTING BRIDGE	LUMP SUM	LUMP SUM			
1090	2402-0425040 FLOODED BACKFILL	56.000 CY				
1100	2402-0875150 COMPACTION WITH MOISTURE CONTROL (STRUCTURES)	360.000 CY				
1110	2402-2720000 EXCAVATION, CLASS 20	890.000 CY				



10/14/2026 9:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 03-C003-069

Call Order: 002

Letting Date: November 17, 2026

SECTION: 0003

Items for a Triple 14' x 7' x 62' Reinforced Concrete Box Culvert - (095)

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1120	2403-0100020 STRUCTURAL CONCRETE (RCB CULVERT)	455.600 CY	_____	_____	_____	_____
1130	2404-7775000 REINFORCING STEEL	65,432.000 LB	_____	_____	_____	_____
1140	2417-1040018 CULVERT, CORRUGATED METAL ENTRANCE PIPE, 18 IN. DIA.	68.000 LF	_____	_____	_____	_____
1150	2417-1040024 CULVERT, CORRUGATED METAL ENTRANCE PIPE, 24 IN. DIA.	100.000 LF	_____	_____	_____	_____
1160	2417-1040036 CULVERT, CORRUGATED METAL ENTRANCE PIPE, 36 IN. DIA.	62.000 LF	_____	_____	_____	_____
1170	2418-0000010 TEMPORARY STREAM DIVERSION	1.000 EACH	_____	_____	_____	_____
1180	2502-8215815 SUBDRAIN, TILE, 15 IN. DIA.	70.000 LF	_____	_____	_____	_____
1190	2502-8221305 SUBDRAIN OUTLET, DR-305	1.000 EACH	_____	_____	_____	_____
1200	2507-3250005 ENGINEERING FABRIC	330.000 SY	_____	_____	_____	_____
1210	2507-6800061 REVETMENT, CLASS E	250.000 TON	_____	_____	_____	_____
1220	2526-8285010 CONSTRUCTION SURVEY, MONUMENT PRESERVATION	LUMP SUM	LUMP SUM		_____	_____
1230	2526-8285020 CONSTRUCTION SURVEY, CONTROL POINT SURVEY	LUMP SUM	LUMP SUM		_____	_____



10/14/2026 9:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 03-C003-069

Call Order: 002

Letting Date: November 17, 2026

SECTION: 0003

Items for a Triple 14' x 7' x 62' Reinforced Concrete Box Culvert - (095)

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1240	2526-8285030 CONSTRUCTION SURVEY, RIGHT OF WAY	LUMP SUM	LUMP SUM			
1250	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM			
1260	2528-2518000 SAFETY CLOSURE	4.000 EACH				
1270	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
1280	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
1290	2601-2634100 MULCHING	2.400 ACRE				
1300	2601-2636043 SEEDING AND FERTILIZING (RURAL)	1.200 ACRE				
1310	2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING	1.200 ACRE				
1320	2602-0000020 SILT FENCE	205.000 LF				
1330	2602-0000030 SILT FENCE FOR DITCH CHECKS	221.000 LF				
1340	2602-0000101 MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	426.000 LF				
1350	2602-0000312 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	235.000 LF				



10/14/2026 9:26 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 03-C003-069

Call Order: 002

Letting Date: November 17, 2026

SECTION: 0003

Items for a Triple 14' x 7' x 62' Reinforced Concrete Box Culvert - (095)

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1360	2602-0010010 MOBILIZATIONS, EROSION CONTROL	1.000 EACH		600.00000		600.00
1370	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	1.000 EACH		1,200.00000		1,200.00

Section: 0003

Total: _____.

Total Bid: _____.