



U07 Utility Bid Attachment

County: Jasper
Route: IA 224
Location: 0.1 mi S of N 75th Ave
Type of Work: RCB Culvert Replacement – Single Box
Project Code: 26-50-224-010
Construction Project: STPN-224-1(020)—2J-50
ROW Phase Number: STPN-224-1(021)—2J-50
Utility Process: Non-Point 25
Letting Date: 11/17/2026

Point25 projects follow provisions set out in Iowa Administrative Code 761–115.25.

Non-Point25 projects are not required to follow provisions set out in Iowa Administrative Code 761–115.25.

This document is provided for the benefit of bidding contractors to assist in evaluating possible construction conflicts and does not represent legal obligations on the part of the department or utility companies.

This project comes under the department's standard specifications 1107.15, Contractor's Responsibility for Utility Facility and Services.

*Additional information regarding the location of utility facilities may be obtained from the department including issued utility permits and a Utility Conflict List (when available) by contacting the **District Utility Coordinator**.*

The Iowa DOT District Utility Coordinator for this project is:

Sean Passick, District 1 Utility Coordinator

Email: sean.passick@iowadot.us

Phone: 515-988-1325

Status of Utility Facilities:

Alliant Energy Electric Distribution OH

Facility Status: Affected

Relocation Needed: Yes

Coordination Status: Temporary relocation is required

Estimated Start Date for Relocation: October 2026

Estimated Completion Date for Relocation: January 2027

Utility Bid Attachment Notes: Alliant is going to temporarily shoe-fly around the end of the proposed culvert and return to original alignment after the project has been completed. Dillion Wright

DillionWright@alliantenergy.com 641-269-2907

IMON Communications Fiber

Facility Status: Not Affected

Relocation Needed: No

Coordination Status: Complete

Utility Bid Attachment Notes: IMON estimates their depth at 24' below the existing waterway and no conflict is anticipated. Eric Bieber eric.bieber@imon.net 319-533-2691

Iowa Regional Utilities Association

Facility Status: Not Affected

Relocation Needed: No

Coordination Status: Complete

Utility Bid Attachment Notes: The IRUA water line is 10' below the waterway and no conflict is anticipated. Derek Ebert debert@irua.net 641-792-7011

Mediacom Communications

Facility Status: Affected

Relocation Needed: Yes

Coordination Status: Complete

Relocation is complete

Utility Bid Attachment Notes: Mediacom lowered their line in place to avoid conflict. Rusty Beaty rbeaty@mediacom.com 641-204-9558

Partner Communications Company

Facility Status: Not Affected

Relocation Needed: No

Coordination Status: Complete

Utility Bid Attachment Notes: Partner Communications located their fiber and their general manager decided they will not be in conflict. We encourage the winning bidder to physically locate this fiber before excavating. Adam Wilkens adamw@pcctel.net 641-498-3511