



CONTRACTS AND SPECIFICATIONS BUREAU Proposal

Proposal ID: 82-1827-698

Letting Date: October 20, 2026

Call Order: 013

Proposal Work Type: BRIDGE REPLACEMENT - CCS

DBE Goal: 0.0%

Contracting Authority: CITY OF DAVENPORT

Proposal Guaranty: \$125,000.00

This proposal includes the following project(s):

Project Number: BRM-1827(698)--8N-82

County: SCOTT

Project Work Type: BRIDGE REPLACEMENT - CCS

Route: EASTERN AVE.

Location: In the city of Davenport, On EASTERN AVE, Over GOOSE CREEK, S18 T78 R04E

Road System: URBAN

Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

Contract Time

Proposal ID: 82-1827-698

Call Order: 013

Letting Date: October 20, 2026

Site ID	Site Details			Liquidated Damages
00	Late Start Date	04/05/2027	105 WORK DAYS	\$1,000.00

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

Contracts and Specifications Bureau

Notes

Proposal ID: 82-1827-698**Call Order:** 013**Letting Date:** October 20, 2026

Notes :***** WINTER WORK *****

The free time allowed between November 15, 2026 and February 14, 2027 will not be permitted on this project during this time. The Contractor shall work during this time on all working days as defined in Article 1101.03 'Working Day'.

Winter Work will be allowed during the winter from February 15, 2027 and April 1, 2027. No working days will be charged between February 15, 2027 and April 1, 2027.



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 82-1827-698

Call Order: 013

Letting Date: October 20, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 82-1827-698

Call Order: 013

Letting Date: October 20, 2026

Note	Description																						
005.1107.02	*** Revisions to Article 1107.02 *** Article 1107.02, Insurance, is amended by the following modifications and additions. This proposal note becomes null and void January 1, 2027. A. It shall be the Contractor's responsibility to have liability insurance covering all of the construction operations incident to contract completion and the Contractor must have on file with the Contracting Authority a current "Certificate of Insurance" prior to award of contract. The certificate shall identify the insurance company firm name and address, Contractor firm name, policy period, type of policy, limits of coverage, and scope of work covered (single contract or statewide). This requirement shall apply with equal force, whether the work is performed by persons employed directly by the Contractor including a subcontractor, persons employed by a subcontractor, or by an independent contractor. B. In addition to the above, the Contracting Authority shall be included as an insured party, or a separate owner's protective policy shall be filed showing the Contracting Authority as an insured party. C. The liability insurance shall be written by an insurance company (or companies) qualified to do business in Iowa. For independent contractors engaged solely in the transportation of materials, the minimum coverage provided by such insurance shall be not less than that required by Chapter 325A, Code of Iowa, for such truck operators or contract carriers as defined therein. For all other contractors, subcontractors, independent contractors, and the Contracting Authority, the minimum coverage by such insurance shall be as follows: <table> <tr> <td>General Liability, Including:</td><td>BODILY INJURY</td></tr> <tr> <td>Independent Contractors</td><td>\$500,000 Each Occurrence</td></tr> <tr> <td>Contractual Liability,</td><td>\$500,000 Aggregate</td></tr> <tr> <td>Products and Completed</td><td>PROPERTY DAMAGE</td></tr> <tr> <td>Operations</td><td>\$250,000 Each Occurrence</td></tr> <tr> <td></td><td>\$250,000 Aggregate</td></tr> <tr> <td></td><td>or</td></tr> <tr> <td></td><td>BODILY INJURY AND PROPERTY DAMAGE</td></tr> <tr> <td></td><td>- COMBINED SINGLE LIMIT*</td></tr> <tr> <td></td><td>\$750,000 Each Occurrence</td></tr> <tr> <td></td><td>\$750,000 Aggregate</td></tr> </table>	General Liability, Including:	BODILY INJURY	Independent Contractors	\$500,000 Each Occurrence	Contractual Liability,	\$500,000 Aggregate	Products and Completed	PROPERTY DAMAGE	Operations	\$250,000 Each Occurrence		\$250,000 Aggregate		or		BODILY INJURY AND PROPERTY DAMAGE		- COMBINED SINGLE LIMIT*		\$750,000 Each Occurrence		\$750,000 Aggregate
General Liability, Including:	BODILY INJURY																						
Independent Contractors	\$500,000 Each Occurrence																						
Contractual Liability,	\$500,000 Aggregate																						
Products and Completed	PROPERTY DAMAGE																						
Operations	\$250,000 Each Occurrence																						
	\$250,000 Aggregate																						
	or																						
	BODILY INJURY AND PROPERTY DAMAGE																						
	- COMBINED SINGLE LIMIT*																						
	\$750,000 Each Occurrence																						
	\$750,000 Aggregate																						

*A comprehensive Catastrophe Liability Policy (Umbrella) can be used to aid in

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 82-1827-698

Call Order: 013

Letting Date: October 20, 2026

Note	Description
	achieving the minimum required limits.
	D. Failure on the part of the Contractor to comply with the requirements of this article will be considered sufficient cause to suspend the work, withhold estimates, and to deny the Contractor from receiving further contract awards, as provided in Article 1103.01.
410.11	*** STORM WATER POLLUTION PREVENTION PLAN *** A Storm Water Pollution Prevention Plan has been developed by the Contracting Authority for one or more projects on this contract. See the project plans (or other contract document) for specific Storm Water Pollution Prevention Plan details.
500.2027	*** NO WINTER FREE TIME *** The free time allowed between November 15 and April 1 will not be permitted on this project during the winter of 2027-2028. The Contractor shall work during the winter on all working days as defined in article 1101.03 'working day'.
DS-23006	DEVELOPMENTAL SPECIFICATIONS FOR FABRIC FORMED CONCRETE STRUCTURE REVETMENT
FHWA-1273.09	FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023 23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.
GS-23007	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, OCTOBER 20, 2026 RELEASE



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 82-1827-698

Call Order: 013

Letting Date: October 20, 2026

Note	Description
IA26-1.2A	PREDETERMINED WAGE RATES - GENERAL DECISION NUMBER IA20260001 FOR HEAVY AND HIGHWAY CONSTRUCTION -- SCOTT COUNTY IN IOWA *** Additional Requirement *** Contracts where the Department is the Contracting Authority: The Prime Contractor and each approved Subcontractor shall submit certified payrolls weekly to the Project Engineer. Each Contractor shall use the AASHTOWare Project Civil Rights and Labor (AWP CRL) software to electronically submit Certified Payroll Reports. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall review and approve each Subcontractor's payroll within AWP CRL. Contracts where the Department is not the Contracting Authority: The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.
SP-236073	SPECIAL PROVISIONS FOR STAINLESS STEEL GATES FOR SANITARY SEWER MANHOLES Scott County BRM-1827(689)--8N-82
SP-236074	SPECIAL PROVISIONS FOR SANITARY SEWER MANHOLE LINER Scott County BRM-1827(689)--8N-82



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 82-1827-698

Call Order: 013

Letting Date: October 20, 2026

SECTION: 0001

ITEMS FOR A 90'-0 X 50'-0 CONTINUOUS CONCRETE SLAB BRIDGE W/5'-4 SIDEWALK

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2101-0850001 CLEARING AND GRUBBING	0.100 ACRE				
0020	2104-2710020 EXCAVATION, CLASS 10, CHANNEL	781.400 CY				
0030	2105-8425005 TOPSOIL, FURNISH AND SPREAD	124.000 CY				
0040	2125-2225050 RESHAPING DITCHES	1.100 STA				
0050	2301-0690205 BRIDGE APPROACH, BR-205	779.700 SY				
0060	2401-6745625 REMOVAL OF EXISTING BRIDGE	LUMP SUM	LUMP SUM			
0070	2401-6745650 REMOVAL OF EXISTING STRUCTURES	LUMP SUM	LUMP SUM			
0080	2402-2720000 EXCAVATION, CLASS 20	175.000 CY				
0090	2403-0100010 STRUCTURAL CONCRETE (BRIDGE)	351.500 CY				
0100	2404-7775005 REINFORCING STEEL, EPOXY COATED	83,415.000 LB				
0110	2404-7775009 REINFORCING STEEL, STAINLESS STEEL	310.000 LB				
0120	2412-0000100 LONGITUDINAL GROOVING IN CONCRETE, BRIDGE DECK AND/OR APPROACHES	1,232.900 SY				



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 82-1827-698

Call Order: 013

Letting Date: October 20, 2026

SECTION: 0001

ITEMS FOR A 90'-0 X 50'-0 CONTINUOUS CONCRETE SLAB BRIDGE W/5'-4 SIDEWALK

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	2414-6425410 CONCRETE BARRIER, REINFORCED, SEPARATION	198.000 LF				
0140	2414-6444100 STEEL PIPE PEDESTRIAN HAND RAILING	97.000 LF				
0150	2416-0100018 APRONS, CONCRETE, 18 IN. DIA.	1.000 EACH				
0160	2416-0100024 APRONS, CONCRETE, 24 IN. DIA.	1.000 EACH				
0170	2435-0130172 MANHOLE, SANITARY SEWER, SW- 301, 72 IN.	2.000 EACH				
0180	2435-0130410 MANHOLE, SANITARY SEWER, SW- 304 MODIFIED	2.000 EACH				
0190	2435-0140160 MANHOLE, STORM SEWER, SW-401, 60 IN.	2.000 EACH				
0200	2435-0251218 INTAKE, SW-512, 18 IN.	1.000 EACH				
0210	2435-0251224 INTAKE, SW-512, 24 IN.	1.000 EACH				
0220	2435-0700020 CONNECTION TO EXISTING INTAKE	1.000 EACH				
0230	2501-0201042 PILES, STEEL, HP 10 X 42	720.000 LF				
0240	2501-0201253 PILES, STEEL, HP 12 X 53	880.000 LF				



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 82-1827-698

Call Order: 013

Letting Date: October 20, 2026

SECTION: 0001

ITEMS FOR A 90'-0 X 50'-0 CONTINUOUS CONCRETE SLAB BRIDGE W/5'-4 SIDEWALK

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	2501-5478053 CONCRETE ENCASEMENT OF STEEL H PILES, HP 12 X 53 (P10L TYPE 3)	264.000 LF				
0260	2503-0110018 STORM SEWER GRAVITY MAIN, TRENCHED, 18 IN.	142.000 LF				
0270	2503-0110024 STORM SEWER GRAVITY MAIN, TRENCHED, 24 IN.	172.000 LF				
0280	2503-0200036 REMOVE STORM SEWER PIPE LESS THAN OR EQUAL TO 36 IN.	76.000 LF				
0290	2503-0200341 STORM SEWER ABANDONMENT, FILL AND PLUG, LESS THAN OR EQUAL TO 36 IN. DIA.	239.000 LF				
0300	2504-0110042 SANITARY SEWER GRAVITY MAIN, TRENCHED, 42 IN.	22.000 LF				
0310	2504-0114024 SANITARY SEWER GRAVITY MAIN, TRENCHED, POLYVINYL CHLORIDE PIPE (PVC), 24 IN.	243.000 LF				
0320	2504-0240237 SANITARY SEWER ABANDONMENT, FILL AND PLUG, GREATER THAN 36 IN. DIA.	47.000 LF				
0330	2507-2638660 BRIDGE WING ARMORING - MACADAM STONE	10.100 SY				
0340	2507-3250005 ENGINEERING FABRIC	616.500 SY				



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 82-1827-698

Call Order: 013

Letting Date: October 20, 2026

SECTION: 0001

ITEMS FOR A 90'-0 X 50'-0 CONTINUOUS CONCRETE SLAB BRIDGE W/5'-4 SIDEWALK

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	2507-6800061 REVTMENT, CLASS E	509.100 TON				
0360	2507-8029000 EROSION STONE	11.500 TON				
0370	2507-8500080 FABRIC FORMED CONCRETE REVTMENT, ARTICULATING BLOCK MAT, 8 INCH	104.900 SY				
0380	2510-6745850 REMOVAL OF PAVEMENT	794.100 SY				
0390	2511-6745900 REMOVAL OF SIDEWALK	94.100 SY				
0400	2511-7526004 SIDEWALK, P.C. CONCRETE, 4 IN.	106.400 SY				
0410	2515-2475007 DRIVEWAY, P.C. CONCRETE, 7 IN.	289.600 SY				
0420	2515-6745600 REMOVAL OF PAVED DRIVEWAY	326.700 SY				
0430	2516-8625000 COMBINED CONCRETE SIDEWALK AND RETAINING WALL	63.400 CY				
0440	2519-1002042 FENCE, CHAIN LINK, 42 IN. HEIGHT	100.000 LF				
0450	2519-1002048 FENCE, CHAIN LINK, 48 IN. HEIGHT	99.000 LF				
0460	2524-9100030 OBJECT MARKER, TYPE 3	2.000 EACH				



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 82-1827-698

Call Order: 013

Letting Date: October 20, 2026

SECTION: 0001

ITEMS FOR A 90'-0 X 50'-0 CONTINUOUS CONCRETE SLAB BRIDGE W/5'-4 SIDEWALK

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0470	2524-9276010 PERFORATED SQUARE STEEL TUBE POSTS	14.000 LF				
0480	2524-9276021 PERFORATED SQUARE STEEL TUBE POST ANCHOR, BREAK-AWAY SOIL INSTALLATION	2.000 EACH				
0490	2524-9325001 TYPE A SIGNS, SHEET ALUMINUM	13.000 SF				
0500	2524-9325150 INSTALL TYPE A SIGN	4.000 EACH				
0510	2526-8285010 CONSTRUCTION SURVEY, MONUMENT PRESERVATION	LUMP SUM	LUMP SUM			
0520	2526-8285020 CONSTRUCTION SURVEY, CONTROL POINT SURVEY	LUMP SUM	LUMP SUM			
0530	2526-8285030 CONSTRUCTION SURVEY, RIGHT OF WAY	LUMP SUM	LUMP SUM			
0540	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM			
0550	2527-9263209 PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	3.960 STA				
0560	2528-2518000 SAFETY CLOSURE	3.000 EACH				
0570	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 82-1827-698

Call Order: 013

Letting Date: October 20, 2026

SECTION: 0001

ITEMS FOR A 90'-0 X 50'-0 CONTINUOUS CONCRETE SLAB BRIDGE W/5'-4 SIDEWALK

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0580	2528-9290050 PORTABLE DYNAMIC MESSAGE SIGN (PDMS)	14.000 CDAY				
0590	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
0600	2549-0041060 BYPASS PUMPING Bypass Pumping	LUMP SUM	LUMP SUM			
0610	2551-0000210 PERMANENT CRASH CUSHION	2.000 EACH				
0620	2552-0000230 SPECIAL PIPE EMBEDMENT OR ENCASEMENT	77.000 LF				
0630	2599-9999005 ('EACH' ITEM) STAINLESS STEEL FLAP GATE	3.000 EACH				
0640	2599-9999005 ('EACH' ITEM) STAINLESS STEEL SLUICE GATE	3.000 EACH				
0650	2601-2634100 MULCHING	0.300 ACRE				
0660	2601-2639010 SODDING	110.000 SQ				
0670	2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING	0.300 ACRE				
0680	2601-2643110 WATERING FOR SOD, SPECIAL DITCH CONTROL, OR SLOPE PROTECTION	0.100 MGAL		75.00000		7.50



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 82-1827-698

Call Order: 013

Letting Date: October 20, 2026

SECTION: 0001

ITEMS FOR A 90'-0 X 50'-0 CONTINUOUS CONCRETE SLAB BRIDGE W/5'-4 SIDEWALK

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0690	2602-0000312 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	900.000 LF				
0700	2602-0000351 REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	900.000 LF				
0710	2602-0000530 GRATE INTAKE SEDIMENT FILTER BAG, EC-604	2.000 EACH				
0720	2602-0000540 MAINTENANCE OF GRATE INTAKE SEDIMENT FILTER BAG	2.000 EACH				
0730	2602-0000550 REMOVAL OF GRATE INTAKE SEDIMENT FILTER BAG	2.000 EACH				
0740	2602-0010010 MOBILIZATIONS, EROSION CONTROL	1.000 EACH		600.00000		600.00
0750	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	1.000 EACH		1,200.00000		1,200.00
Section: 0001			Total:			
			Total Bid:			