



CONTRACTS AND SPECIFICATIONS BUREAU Proposal

Proposal ID: 85-0305-311

Letting Date: October 20, 2026

Call Order: 014

Proposal Work Type: BRIDGE REPLACEMENT - PPCB

DBE Goal: 0.0%

Contracting Authority: IOWA DEPARTMENT OF TRANSPORTATION

Proposal Guaranty: \$750,000.00

This proposal includes the following project(s):

Project Number: NHSX-030-5(310)--3H-85 **County:** STORY
Project Work Type: PCC PAVEMENT - GRADE AND NEW **Route:** U.S. 30
Location: S Duff Ave to S Dayton Ave in Ames (WB)
Road System: PRIMARY ROAD (on NHS)
Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

Project Number: BRF-030-5(311)--38-85 **County:** STORY
Project Work Type: BRIDGE REPLACEMENT - PPCB **Route:** U.S. 30
Location: South Skunk River 1.2 mi W of I-35 (WB)
Road System: PRIMARY ROAD (on NHS)
Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

Project Number: NHSX-030-5(312)--3H-85 **County:** STORY
Project Work Type: RCB CULVERT NEW - TRIPLE BOX **Route:** U.S. 30
Location: W of the South Skunk River (WB)
Road System: PRIMARY ROAD (on NHS)
Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

Project Number: NHSX-030-5(313)--3H-85 **County:** STORY
Project Work Type: RCB CULVERT NEW - TRIPLE BOX **Route:** U.S. 30
Location: E of the South Skunk River (WB)
Road System: PRIMARY ROAD (on NHS)
Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

Project Number: NHSX-030-5(314)--3H-85	County: STORY
Project Work Type: TRAFFIC SIGNS	Route: U.S. 30
Location: S Duff Ave to S Dayton Ave in Ames (WB)	
Road System: PRIMARY ROAD (on NHS)	
Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect	
Project Number: NHSX-030-5(315)--3H-85	County: STORY
Project Work Type: LIGHTING	Route: U.S. 30
Location: S Duff Ave to S Dayton Ave in Ames (WB)	
Road System: PRIMARY ROAD (on NHS)	
Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect	

Contract Time

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

Site ID	Site Details				Liquidated Damages
00	Late Start Date	04/05/2027	140	WORK DAYS	\$2,000.00
	Overall site.				
01	Specified Start Date	06/01/2027	61	CALENDAR DAYS	\$2,000.00
	Duff Ramp closure.				

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

The following sections are alternates:

0003	AA	1	DESIGN NO. 227; ALT 'AA' OPT 1: BEAMS, PPC, BTC105 BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN (311)
0004	AA	2	DESIGN NO. 227; ALT 'AA' OPT 2: BEAMS, PPC, BTC105 BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN (311)

Notes

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

Notes :

There are no notes for this proposal.



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

Note	Description																						
005.1107.02	*** Revisions to Article 1107.02 *** Article 1107.02, Insurance, is amended by the following modifications and additions. This proposal note becomes null and void January 1, 2027. A. It shall be the Contractor's responsibility to have liability insurance covering all of the construction operations incident to contract completion and the Contractor must have on file with the Contracting Authority a current "Certificate of Insurance" prior to award of contract. The certificate shall identify the insurance company firm name and address, Contractor firm name, policy period, type of policy, limits of coverage, and scope of work covered (single contract or statewide). This requirement shall apply with equal force, whether the work is performed by persons employed directly by the Contractor including a subcontractor, persons employed by a subcontractor, or by an independent contractor. B. In addition to the above, the Contracting Authority shall be included as an insured party, or a separate owner's protective policy shall be filed showing the Contracting Authority as an insured party. C. The liability insurance shall be written by an insurance company (or companies) qualified to do business in Iowa. For independent contractors engaged solely in the transportation of materials, the minimum coverage provided by such insurance shall be not less than that required by Chapter 325A, Code of Iowa, for such truck operators or contract carriers as defined therein. For all other contractors, subcontractors, independent contractors, and the Contracting Authority, the minimum coverage by such insurance shall be as follows: <table> <tr> <td>General Liability, Including:</td><td>BODILY INJURY</td></tr> <tr> <td>Independent Contractors</td><td>\$500,000 Each Occurrence</td></tr> <tr> <td>Contractual Liability,</td><td>\$500,000 Aggregate</td></tr> <tr> <td>Products and Completed</td><td>PROPERTY DAMAGE</td></tr> <tr> <td>Operations</td><td>\$250,000 Each Occurrence</td></tr> <tr> <td></td><td>\$250,000 Aggregate</td></tr> <tr> <td></td><td>or</td></tr> <tr> <td></td><td>BODILY INJURY AND PROPERTY DAMAGE</td></tr> <tr> <td></td><td>- COMBINED SINGLE LIMIT*</td></tr> <tr> <td></td><td>\$750,000 Each Occurrence</td></tr> <tr> <td></td><td>\$750,000 Aggregate</td></tr> </table>	General Liability, Including:	BODILY INJURY	Independent Contractors	\$500,000 Each Occurrence	Contractual Liability,	\$500,000 Aggregate	Products and Completed	PROPERTY DAMAGE	Operations	\$250,000 Each Occurrence		\$250,000 Aggregate		or		BODILY INJURY AND PROPERTY DAMAGE		- COMBINED SINGLE LIMIT*		\$750,000 Each Occurrence		\$750,000 Aggregate
General Liability, Including:	BODILY INJURY																						
Independent Contractors	\$500,000 Each Occurrence																						
Contractual Liability,	\$500,000 Aggregate																						
Products and Completed	PROPERTY DAMAGE																						
Operations	\$250,000 Each Occurrence																						
	\$250,000 Aggregate																						
	or																						
	BODILY INJURY AND PROPERTY DAMAGE																						
	- COMBINED SINGLE LIMIT*																						
	\$750,000 Each Occurrence																						
	\$750,000 Aggregate																						

*A comprehensive Catastrophe Liability Policy (Umbrella) can be used to aid in

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

Note	Description
	achieving the minimum required limits.
	D. Failure on the part of the Contractor to comply with the requirements of this article will be considered sufficient cause to suspend the work, withhold estimates, and to deny the Contractor from receiving further contract awards, as provided in Article 1103.01.
410.11	*** STORM WATER POLLUTION PREVENTION PLAN *** A Storm Water Pollution Prevention Plan has been developed by the Contracting Authority for one or more projects on this contract. See the project plans (or other contract document) for specific Storm Water Pollution Prevention Plan details.
500.01	*** WINTER WORK *** The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.
DS-23011	DEVELOPMENTAL SPECIFICATIONS FOR FLOATING SILT CURTAIN
DS-23032	DEVELOPMENTAL SPECIFICATIONS FOR ELECTRONIC TICKETING
DS-23074	DEVELOPMENTAL SPECIFICATIONS FOR INTELLIGENT TRANSPORTATION SYSTEMS
DS-23082	DEVELOPMENTAL SPECIFICATIONS FOR HIGH PERFORMANCE CONCRETE FOR STRUCTURES
DS-23083	DEVELOPMENTAL SPECIFICATIONS FOR FIBER REINFORCEMENT FOR STRUCTURAL CONCRETE
DS-23088	DEVELOPMENTAL SPECIFICATIONS FOR DIAMOND GRINDING RUMBLE STRIPS

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

Note	Description
FHWA-1273.09	FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023 23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.
GS-23007	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, OCTOBER 20, 2026 RELEASE
IA26-28.4A	PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20260028 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY) Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract. *** Additional Requirement *** Contracts where the Department is the Contracting Authority: The Prime Contractor and each approved Subcontractor shall submit certified payrolls weekly to the Project Engineer. Each Contractor shall use the AASHTOWare Project Civil Rights and Labor (AWP CRL) software to electronically submit Certified Payroll Reports. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall review and approve each Subcontractor's payroll within AWP CRL. Contracts where the Department is not the Contracting Authority: The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

SECTION: 0001

ROADWAY ITEMS - NHSX-030-5(310)--3H-85

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2101-0850001 CLEARING AND GRUBBING	0.532 ACRE				
0020	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	4,503.000 CY				
0030	2102-2710090 EXCAVATION, CLASS 10, WASTE	9,365.000 CY				
0040	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	6,070.000 CY				
0050	2107-0425020 COMPACTING BACKFILL ADJACENT TO BRIDGES, CULVERTS OR STRUCTURES	148.700 CY				
0060	2107-0875100 COMPACTION WITH MOISTURE CONTROL	3,451.000 CY				
0070	2115-0100000 MODIFIED SUBBASE	6,668.590 CY				
0080	2122-5190105 PAVED SHOULDER, P.C. CONCRETE, 10.5 IN.	6,696.600 SY				
0090	2123-7450000 SHOULDER CONSTRUCTION, EARTH	101.030 STA				
0100	2301-0690203 BRIDGE APPROACH, BR-203	1,059.800 SY				
0110	2301-1033105 STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 10.5 IN.	16,390.500 SY				



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

SECTION: 0001

ROADWAY ITEMS - NHSX-030-5(310)--3H-85

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	2301-7000110 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR PCC PAVEMENT THICKNESS (BY SCHEDULE)	19,188.600 EACH		1.00000	19,188.60	
0130	2304-0101000 TEMPORARY PAVEMENT	361.500 SY				
0140	2317-7000110 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR PCC PAVEMENT SMOOTHNESS (BY SCHEDULE)	12,300.400 EACH		1.00000	12,300.40	
0150	2402-0425040 FLOODED BACKFILL	180.100 CY				
0160	2402-2720100 EXCAVATION, CLASS 20, FOR ROADWAY PIPE CULVERT	61.700 CY				
0170	2412-0000100 LONGITUDINAL GROOVING IN CONCRETE, BRIDGE DECK AND/OR APPROACHES	3,419.000 SY				
0180	2416-0100018 APRONS, CONCRETE, 18 IN. DIA.	1.000 EACH				
0190	2416-1180018 CULVERT, CONCRETE ROADWAY PIPE, 18 IN. DIA.	64.000 LF				
0200	2435-0251224 INTAKE, SW-512, 24 IN.	1.000 EACH				
0210	2502-8212034 SUBDRAIN, LONGITUDINAL, (SHOULDER) 4 IN. DIA.	8,196.000 LF				



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

SECTION: 0001

ROADWAY ITEMS - NHSX-030-5(310)--3H-85

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0220	2502-8221306 SUBDRAIN OUTLET, DR-306	25.000 EACH				
0230	2503-0500402 BRIDGE END DRAIN, DR-402	6.000 EACH				
0240	2505-4008300 STEEL BEAM GUARDRAIL	912.500 LF				
0250	2505-4008415 STEEL BEAM GUARDRAIL BARRIER TRANSITION SECTION, BA-209	3.000 EACH				
0260	2505-4021010 STEEL BEAM GUARDRAIL END ANCHOR, BOLTED	3.000 EACH				
0270	2505-4021020 STEEL BEAM GUARDRAIL END ANCHOR, W-BEAM	1.000 EACH				
0280	2505-4021720 STEEL BEAM GUARDRAIL TANGENT END TERMINAL, BA-205	4.000 EACH				
0290	2505-4502100 STEEL BEAM GUARDRAIL, POST ADAPTER UNIT, BA-210	17.000 EACH				
0300	2507-3250005 ENGINEERING FABRIC	16.000 SY				
0310	2507-6800061 REVTMENT, CLASS E	8.910 TON				
0320	2510-6745850 REMOVAL OF PAVEMENT	20,169.800 SY				
0330	2511-0300000 REMOVAL OF RECREATIONAL TRAIL	138.500 SY				



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

SECTION: 0001

ROADWAY ITEMS - NHSX-030-5(310)--3H-85

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0340	2511-0302700 RECREATIONAL TRAIL, PORTLAND CEMENT CONCRETE, 7 IN.	137.000 SY				
0350	2519-1002072 FENCE, CHAIN LINK, 72 IN. HEIGHT	2,871.900 LF				
0360	2519-3000000 FLOOD PLAIN FENCE	57.100 LF				
0370	2519-4200120 REMOVAL OF FENCE, CHAIN LINK	2,944.200 LF				
0380	2520-3350010 FIELD LABORATORY	1.000 EACH				
0390	2526-8285020 CONSTRUCTION SURVEY, CONTROL POINT SURVEY	LUMP SUM	LUMP SUM			
0400	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM			
0410	2527-9263181 PAVEMENT MARKINGS REMOVED	431.420 STA				
0420	2527-9263209 PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	642.110 STA				
0430	2527-9263231 REMOVABLE TAPE MARKINGS, WET RETROREFLECTIVE	133.520 STA				
0440	2527-9270112 GROOVES CUT FOR PAVEMENT MARKINGS	333.150 STA				
0450	2528-2518000 SAFETY CLOSURE	6.000 EACH				



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

SECTION: 0001

ROADWAY ITEMS - NHSX-030-5(310)--3H-85

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0460	2528-3800000 MODULAR GLARE SCREEN SYSTEM	2,837.500 LF				
0470	2528-8400048 TEMPORARY BARRIER RAIL, CONCRETE	2,437.500 LF				
0480	2528-8400157 TEMPORARY FLOODLIGHTING LUMINAIRE	4.000 EACH				
0490	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
0500	2528-8445113 FLAGGERS	60.000 EACH		660.00000		39,600.00
0510	2528-9290050 PORTABLE DYNAMIC MESSAGE SIGN (PDMS)	60.000 CDAY				
0520	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
0530	2548-0000100 MILLED SHOULDER RUMBLE STRIPS, HMA SURFACE	109.740 STA				
0540	2548-0000110 ASPHALT EMULSION FOR FOG SEAL (SHOULDER RUMBLE STRIPS)	118.900 GAL				
0550	2548-0000250 DIAMOND GROUND SHOULDER RUMBLE STRIPS, PCC SURFACE	89.320 STA				
0560	2551-0000130 TEMP CRASH CUSHION, SEVERE USE (SU)	2.000 EACH				



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

SECTION: 0001

ROADWAY ITEMS - NHSX-030-5(310)--3H-85

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0570	2599-9999005 (‘EACH’ ITEM) TEMP CRASH CUSHION, SEVERE USE (SU), REMOVE	7.000 EACH	_____	_____	_____	_____
0580	2599-9999009 (‘LINEAR FEET’ ITEM) TEMPORARY BARRIER RAIL, CONCRETE, RELOCATE	1,875.000 LF	_____	_____	_____	_____
0590	2599-9999009 (‘LINEAR FEET’ ITEM) TEMPORARY BARRIER RAIL, CONCRETE, REMOVE	687.500 LF	_____	_____	_____	_____
0600	2601-2633100 MOWING	8.000 ACRE	_____	_____	_____	_____
0610	2601-2634100 MULCHING	10.600 ACRE	_____	_____	_____	_____
0620	2601-2636015 NATIVE GRASS SEEDING	4.000 ACRE	_____	_____	_____	_____
0630	2601-2636043 SEEDING AND FERTILIZING (RURAL)	1.300 ACRE	_____	_____	_____	_____
0640	2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING	5.300 ACRE	_____	_____	_____	_____
0650	2602-0000020 SILT FENCE	7,493.000 LF	_____	_____	_____	_____
0660	2602-0000030 SILT FENCE FOR DITCH CHECKS	1,466.000 LF	_____	_____	_____	_____
0670	2602-0000071 REMOVAL OF SILT FENCE OR SILT FENCE FOR DITCH CHECKS	8,959.000 LF	_____	_____	_____	_____



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

SECTION: 0001

ROADWAY ITEMS - NHSX-030-5(310)--3H-85

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0680	2602-0000101 MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	8,959.000 LF				
0690	2602-0000160 ROCK CHECK DAM	119.000 LF				
0700	2602-0000170 MAINTENANCE OF ROCK CHECK DAM	8.000 EACH				
0710	2602-0000180 REMOVAL OF ROCK CHECK DAM	3.000 EACH				
0720	2602-0000212 FLOATING SILT CURTAIN (HANGING)	620.000 LF				
0730	2602-0000240 MAINTENANCE OF FLOATING SILT CURTAIN	310.000 LF				
0740	2602-0000312 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	680.000 LF				
0750	2602-0000320 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 20 IN. DIA.	630.000 LF				
0760	2602-0000351 REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	1,310.000 LF				
0770	2602-0010010 MOBILIZATIONS, EROSION CONTROL	1.000 EACH		600.00000		600.00
0780	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	1.000 EACH		1,200.00000		1,200.00



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

Section: 0001

Total: _____.



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

SECTION: 0002

DESIGN NO. 0227; A 376'-0 X 60'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE BRF-030-5(311)--38-85

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0790	2104-2710020 EXCAVATION, CLASS 10, CHANNEL	1,128.400 CY				
0800	2401-6745625 REMOVAL OF EXISTING BRIDGE	LUMP SUM	LUMP SUM			
0810	2402-2720000 EXCAVATION, CLASS 20	388.000 CY				
0820	2402-2721000 EXCAVATION, CLASS 21	874.000 CY				
0830	2403-0100010 STRUCTURAL CONCRETE (BRIDGE)	656.500 CY				
0840	2403-1000005 FIBER REINFORCEMENT FOR STRUCTURAL CONCRETE	807.300 CY				
0850	2403-1000010 TRIAL BATCH AND TEST PLACEMENT (FIBER REINFORCED CONCRETE)	LUMP SUM	LUMP SUM			
0860	2403-7000210 HIGH PERFORMANCE STRUCTURAL CONCRETE	807.300 CY				
0870	2404-7775000 REINFORCING STEEL	98,422.000 LB				
0880	2404-7775005 REINFORCING STEEL, EPOXY COATED	254,181.000 LB				
0890	2404-7775009 REINFORCING STEEL, STAINLESS STEEL	7,052.000 LB				



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

SECTION: 0002

DESIGN NO. 0227; A 376'-0 X 60'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE BRF-030-5(311)--38-85

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0900	2407-0563080 BEAMS, PRETENSIONED PRESTRESSED CONCRETE, BTC80	14.000 EACH				
0910	2414-6424110 CONCRETE BARRIER RAILING	806.000 LF				
0920	2501-0201057 PILES, STEEL, HP 10 X 57	1,870.000 LF				
0930	2501-0201473 PILES, STEEL, HP 14 X 73	5,130.000 LF				
0940	2501-6335010 PREBORED HOLES	220.000 LF				
0950	2507-2638650 BRIDGE WING ARMORING - EROSION STONE	24.400 SY				
0960	2507-3250005 ENGINEERING FABRIC	1,245.200 SY				
0970	2507-6800061 REVETMENT, CLASS E	1,692.600 TON				
0980	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM			
0990	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
Section: 0002			Total:			



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

SECTION: 0003

DESIGN NO. 227; ALT 'AA' OPT 1: BEAMS, PPC, BTC105 BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN (311)

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1000	2407-0563105 BEAMS, PRETENSIONED PRESTRESSED CONCRETE, BTC105	2.000 EACH				
1010	2408-7800000 STRUCTURAL STEEL	20,586.000 LB				
1020	2599-9999005 (‘EACH’ ITEM) Remove and Reinstall Existing PPC Beams	12.000 EACH				
Section: 0003			Total:			

SECTION: 0004

DESIGN NO. 227; ALT 'AA' OPT 2: BEAMS, PPC, BTC105 BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN (311)

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1030	2407-0563105 BEAMS, PRETENSIONED PRESTRESSED CONCRETE, BTC105	14.000 EACH				
1040	2408-7800000 STRUCTURAL STEEL	20,294.000 LB				
Section: 0004			Total:			



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

SECTION: 0005

DESIGN NO. 727; A TRIPLE 12' X 9' X 191'-0 (105'-0, STAGE 2) CAST-IN-PLACE RCB CULVERT NHSX-030-5(312)--3H-85

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1050	2104-2710020 EXCAVATION, CLASS 10, CHANNEL	247.100 CY				
1060	2402-2720000 EXCAVATION, CLASS 20	3,077.000 CY				
1070	2402-3825025 GRANULAR MATERIAL FOR BLANKET	206.000 CY				
1080	2403-0100020 STRUCTURAL CONCRETE (RCB CULVERT)	452.200 CY				
1090	2404-7775000 REINFORCING STEEL	77,487.000 LB				
1100	2501-8400172 TEMPORARY SHORING	LUMP SUM	LUMP SUM			
1110	2507-3250005 ENGINEERING FABRIC	542.000 SY				
1120	2507-6800061 REVETMENT, CLASS E	370.600 TON				
1130	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM			
1140	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
Section: 0005			Total:			



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

SECTION: 0006

DESIGN NO. 827; A TRIPLE 16' X 12' X 214'-0 (128'-0 STAGE 2) CAST-IN-PLACE RCB CULVERT NHSX-030-5(313)--3H-85

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1150	2104-2710020 EXCAVATION, CLASS 10, CHANNEL	298.900 CY				
1160	2402-2720000 EXCAVATION, CLASS 20	6,082.000 CY				
1170	2402-3825025 GRANULAR MATERIAL FOR BLANKET	332.000 CY				
1180	2403-0100020 STRUCTURAL CONCRETE (RCB CULVERT)	893.200 CY				
1190	2404-7775000 REINFORCING STEEL	160,692.000 LB				
1200	2501-8400172 TEMPORARY SHORING	LUMP SUM	LUMP SUM			
1210	2507-3250005 ENGINEERING FABRIC	509.500 SY				
1220	2507-6800061 REVETMENT, CLASS E	448.500 TON				
1230	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM			
1240	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
Section: 0006			Total:			



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

SECTION: 0007

TRAFFIC SIGN ITEMS - NHSX-030-5(314)--3H-85

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1250	2401-6745355 REMOVAL OF CONCRETE FOOTINGS OF HIGHWAY SIGNS	15.000 EACH				
1260	2402-2720000 EXCAVATION, CLASS 20	704.800 CY				
1270	2403-0100000 STRUCTURAL CONCRETE (MISCELLANEOUS)	168.800 CY				
1280	2404-7775005 REINFORCING STEEL, EPOXY COATED	25,056.000 LB				
1290	2423-0001010 DYNAMIC MESSAGE SIGN (D.M.S.) INSTALLATION	1.000 EACH				
1300	2423-1051320 STEEL CANTILEVER SIGN TRUSS, 32 FT. ARM	1.000 EACH				
1310	2423-1051380 STEEL CANTILEVER SIGN TRUSS, 38 FT. ARM	1.000 EACH				
1320	2423-1060085 STEEL OVERHEAD SIGN TRUSS, 85 FT. SPAN	2.000 EACH				
1330	2501-8400172 TEMPORARY SHORING	LUMP SUM	LUMP SUM			
1340	2518-0000080 ITS HANDHOLE, 30x17x24	2.000 EACH				
1350	2518-0000090 ITS HANDHOLE, 36x24x36	1.000 EACH				



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

SECTION: 0007

TRAFFIC SIGN ITEMS - NHSX-030-5(314)--3H-85

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1360	2518-0000150 ITS GROUND ROD	3.000 EACH				
1370	2518-0001200 ITS CONDUIT, HDPE, 2 INCH BORED	632.000 LF				
1380	2518-0002200 ITS CONDUIT, HDPE, 2 INCH PLOWED	798.000 LF				
1390	2518-0004200 ITS CONDUIT, RIGID STEEL, 2 INCH	16.000 LF				
1400	2518-0006004 XHHW COPPER WIRE, NO. 4 AWG	3,618.000 LF				
1410	2518-0006006 XHHW COPPER WIRE, NO. 6 AWG	621.000 LF				
1420	2518-0006015 ITS TRACER WIRE	97.000 LF				
1430	2518-0008300 FIBER OPTIC CABLE, INSTALL ONLY	97.000 LF				
1440	2518-0008322 ITS CIRCUIT BREAKER	2.000 EACH				
1450	2518-0008325 ITS TRANSFORMER	2.000 EACH				
1460	2518-0008400 FIBER OPTIC CABLE ACCEPTANCE TESTING	LUMP SUM	LUMP SUM			
1470	2524-6765010 REMOVE AND REINSTALL SIGN AS PER PLAN	1.000 EACH				



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

SECTION: 0007

TRAFFIC SIGN ITEMS - NHSX-030-5(314)--3H-85

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1480	2524-6765210 REMOVAL OF TYPE A SIGN ASSEMBLY	1.000 EACH				
1490	2524-6765220 REMOVAL OF TYPE B SIGN ASSEMBLY	9.000 EACH				
1500	2524-9081275 CONCRETE FOOTING FOR BREAKAWAY SIGN POST, 2'-8" DIA. X 7'-6"	4.000 EACH				
1510	2524-9081290 CONCRETE FOOTING FOR BREAKAWAY SIGN POST, 2'-8" DIA. X 9'-0"	6.000 EACH				
1520	2524-9089100 DELINEATOR, RIGID - TYPE I	11.000 EACH				
1530	2524-9089110 DELINEATOR, RIGID - TYPE IA	4.000 EACH				
1540	2524-9089200 DELINEATOR, RIGID - TYPE II	18.000 EACH				
1550	2524-9210007 REFERENCE LOCATION SIGNS	4.000 EACH				
1560	2524-9276010 PERFORATED SQUARE STEEL TUBE POSTS	45.000 LF				
1570	2524-9276027 PERFORATED SQUARE STEEL TUBE POST ANCHOR, TRIANGULAR SLIP BASE ASSEMBLY	3.000 EACH				



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

SECTION: 0007

TRAFFIC SIGN ITEMS - NHSX-030-5(314)--3H-85

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1580	2524-9281090 STEEL BREAKAWAY SIGN POSTS FOR TYPE A OR B SIGNS, W 6 X 9	18.000 LF				
1590	2524-9281210 STEEL BREAKAWAY SIGN POSTS FOR TYPE A OR B SIGNS, W 8 X 21	69.400 LF				
1600	2524-9281426 STEEL BREAKAWAY SIGN POSTS FOR TYPE A OR B SIGNS, W 12 X 26	144.500 LF				
1610	2524-9325001 TYPE A SIGNS, SHEET ALUMINUM	16.000 SF				
1620	2524-9380001 TYPE B SIGNS, EXTRUDED ALUMINUM STRUCTURAL PANEL	1,553.000 SF				
1630	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM			
1640	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
1650	2555-0000010 DELIVER AND STOCKPILE SALVAGED MATERIALS	LUMP SUM	LUMP SUM			
1660	2599-9999005 (‘EACH’ ITEM) Anchor Bolt Assembly, Install and Survey	10.000 EACH				
1670	2599-9999005 (‘EACH’ ITEM) Delineator, Gore	7.000 EACH				
1680	2599-9999005 (‘EACH’ ITEM) ITS TRANSFORMER BASE	2.000 EACH				



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

SECTION: 0007

TRAFFIC SIGN ITEMS - NHSX-030-5(314)--3H-85

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1690	2599-9999005 ('EACH' ITEM) MASSH-400 Sign Post	2.000 EACH	_____	_____	_____	_____
1700	2599-9999008 ('POUNDS' ITEM) Anchor Bolt Assembly, Furnish	7,230.000 LB	_____	_____	_____	_____
Section: 0007			Total:		_____	_____



9/8/2026 1:05 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 85-0305-311

Call Order: 014

Letting Date: October 20, 2026

SECTION: 0008

LIGHTING ITEMS - NHSX-030-5(315)--3H-85

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1710	2401-6745356 REMOVAL OF CONCRETE FOOTINGS OF LIGHT POLES	10.000 EACH				
1720	2401-6745765 REMOVAL OF LIGHT POLES	10.000 EACH				
1730	2523-0000100 LIGHTING POLES	10.000 EACH				
1740	2523-0000200 ELECTRICAL CIRCUITS	3,480.000 LF				
1750	2523-0000310 HANDHOLES AND JUNCTION BOXES	2.000 EACH				
1760	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM			
1770	2528-8400157 TEMPORARY FLOODLIGHTING LUMINAIRE	3.000 EACH				
1780	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
1790	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
1800	2555-0000010 DELIVER AND STOCKPILE SALVAGED MATERIALS	LUMP SUM	LUMP SUM			
1810	2599-9999010 (‘LUMP SUM’ ITEM) DEMOLITION OF ELECTRIC CIRCUITS	LUMP SUM	LUMP SUM			
Section: 0008			Total:			

Total Bid: _____.