8/11/2026 10:46 AM

IOWA | DOT

CONTRACTS AND SPECIFICATIONS BUREAU
Proposal

Proposal ID: 77-C077-252 **Letting Date:** September 15, 2026
Call Order: 005
Proposal Work Type: RCB CULVERT NEW - TWIN BOX
DBE Goal: 0.0%
Contracting Authority: POLK COUNTY
Proposal Guaranty: $62,500.00

This proposal includes the following project(s):

Project Number: STP-S-C077(252)--5A-77 **County:** POLK
Project Work Type: RCB CULVERT NEW - TWIN BOX **Route:** 150TH AVE
Location: On NE 150th Ave, Over Skunk River Tributary, W of NE 72nd St
Road System: FARM TO MARKET ROAD
Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

Project Number: BROS-C077(253)--5F-77 **County:** POLK
Project Work Type: RCB CULVERT NEW - TWIN BOX **Route:** 150TH AVE
Location: On NE 150th Ave over old channel S. Skunk River, W of NE 68th St
Road System: FARM TO MARKET ROAD
Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

IOWA | DOT

Contracts and Specifications Bureau

Contract Time

Proposal ID: 77-C077-252 **Call Order:** 005 **Letting Date:** September 15, 2026

Site ID	Site Details				Liquidated Damages
00	Late Start Date	05/10/2027	100	WORK DAYS	$1,000.00

.

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

IOWA | DOT

Contracts and Specifications Bureau

Notes

Proposal ID: 77-C077-252 **Call Order:** 005 **Letting Date:** September 15, 2026

Notes :

Work Restriction
Road may not be closed before February 15, 2027.

Winter Work
Winter work will be allowed from February 15, 2027 and April 1st, 2027. No working days will be charged during this time.

8/11/2026 10:46 AM

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 77-C077-252 **Call Order:** 005 **Letting Date:** September 15, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.
410.11	*** STORM WATER POLLUTION PREVENTION PLAN *** A Storm Water Pollution Prevention Plan has been developed by the Contracting Authority for one or more projects on this contract. See the project plans (or other contract document) for specific Storm Water Pollution Prevention Plan details.
500.2027	*** NO WINTER FREE TIME *** The free time allowed between November 15 and April 1 will not be permitted on this project during the winter of 2027-2028. The Contractor shall work during the winter on all working days as defined in article 1101.03 'working day'.
FHWA-1273.09	FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023 23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.
GS-23006	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION

IOWA | DOT

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 77-C077-252 **Call Order:** 005 **Letting Date:** September 15, 2026

Note	Description
IA26-28.4	PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20260028 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY) Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract. *** Additional Requirement *** The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 77-C077-252 **Call Order:** 005 **Letting Date:** September 15, 2026

SECTION: 0001

ITEMS FOR A 12'-0 X 8'-0 X 66'-0 TWIN BARREL REINFORCED CONCRETE BOX CULVERT - STP-S-C077(252)--5A-77

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2102-0425070 SPECIAL BACKFILL (STRUCTURE)	238.430 TON	_____._____		_____._____	
0020	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	535.000 CY	_____._____		_____._____	
0030	2102-2710090 EXCAVATION, CLASS 10, WASTE	1,087.300 CY	_____._____		_____._____	
0040	2102-2713090 EXCAVATION, CLASS 13, WASTE	64.000 CY	_____._____		_____._____	
0050	2104-2710020 EXCAVATION, CLASS 10, CHANNEL	299.900 CY	_____._____		_____._____	
0060	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	809.900 CY	_____._____		_____._____	
0070	2115-0100000 MODIFIED SUBBASE	317.890 CY	_____._____		_____._____	
0080	2123-7450000 SHOULDER CONSTRUCTION, EARTH	11.600 STA	_____._____		_____._____	
0090	2213-7100400 RELOCATION OF MAIL BOXES	1.000 EACH	_____._____		_____._____	
0100	2312-8260051 GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE	579.670 TON	_____._____		_____._____	
0110	2315-8275025 SURFACING, DRIVEWAY, CLASS A CRUSHED STONE	199.750 TON	_____._____		_____._____	
0120	2401-6745625 REMOVAL OF EXISTING BRIDGE	 LUMP SUM	 LUMP SUM		_____._____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 77-C077-252 **Call Order:** 005 **Letting Date:** September 15, 2026

SECTION: 0001

ITEMS FOR A 12'-0 X 8'-0 X 66'-0 TWIN BARREL REINFORCED CONCRETE BOX CULVERT - STP-S-C077(252)--5A-77

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	2401-6745910 REMOVAL OF SIGN (REMOVE, SALVAGE, REPLACE)	1.000 EACH	_____	_____	_____	_____
0140	2402-0425031 GRANULAR BACKFILL	375.080 TON	_____	_____	_____	_____
0150	2402-2720000 EXCAVATION, CLASS 20	1,755.300 CY	_____	_____	_____	_____
0160	2403-0100020 STRUCTURAL CONCRETE (RCB CULVERT)	297.000 CY	_____	_____	_____	_____
0170	2404-7775000 REINFORCING STEEL	47,920.000 LB	_____	_____	_____	_____
0180	2417-0225015 APRONS, METAL, 15 IN. DIA.	2.000 EACH	_____	_____	_____	_____
0190	2417-0225018 APRONS, METAL, 18 IN. DIA.	1.000 EACH	_____	_____	_____	_____
0200	2417-1040015 CULVERT, CORRUGATED METAL ENTRANCE PIPE, 15 IN. DIA.	34.000 LF	_____	_____	_____	_____
0210	2417-1040018 CULVERT, CORRUGATED METAL ENTRANCE PIPE, 18 IN. DIA.	65.000 LF	_____	_____	_____	_____
0220	2418-0000010 TEMPORARY STREAM DIVERSION	1.000 EACH	_____	_____	_____	_____
0230	2503-0200036 REMOVE STORM SEWER PIPE LESS THAN OR EQUAL TO 36 IN.	113.000 LF	_____	_____	_____	_____

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 77-C077-252 **Call Order:** 005 **Letting Date:** September 15, 2026

SECTION: 0001

ITEMS FOR A 12'-0 X 8'-0 X 66'-0 TWIN BARREL REINFORCED CONCRETE BOX CULVERT - STP-S-C077(252)--5A-77

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	2503-3775018 GATE, OUTLET CONTROL, FLAP, 18 IN. (REMOVE, SALVAGE, REUSE)	1.000 EACH	_____	_____	_____	_____
0250	2507-6800061 REVETMENT, CLASS E	386.770 TON	_____	_____	_____	_____
0260	2526-8285010 CONSTRUCTION SURVEY, MONUMENT PRESERVATION	LUMP SUM	LUMP SUM		_____	_____
0270	2526-8285020 CONSTRUCTION SURVEY, CONTROL POINT SURVEY	LUMP SUM	LUMP SUM		_____	_____
0280	2526-8285030 CONSTRUCTION SURVEY, RIGHT OF WAY	LUMP SUM	LUMP SUM		_____	_____
0290	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM		_____	_____
0300	2528-2518000 SAFETY CLOSURE	2.000 EACH	_____	_____	_____	_____
0310	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM		_____	_____
0320	2528-9290050 PORTABLE DYNAMIC MESSAGE SIGN (PDMS)	14.000 CDAY	_____	_____	_____	_____
0330	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
0340	2601-2634110 MULCHING, MECHANICALLY-BONDED FIBER MATRIX	1.830 ACRE	_____	_____	_____	_____

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 77-C077-252 **Call Order:** 005 **Letting Date:** September 15, 2026

SECTION: 0001

ITEMS FOR A 12'-0 X 8'-0 X 66'-0 TWIN BARREL REINFORCED CONCRETE BOX CULVERT - STP-S-C077(252)--5A-77

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	2601-2636043 SEEDING AND FERTILIZING (RURAL)	0.800 ACRE	_____._____		_____._____	
0360	2601-2638352 SLOPE PROTECTION, WOOD EXCELSIOR MAT	39.530 SQ	_____._____		_____._____	
0370	2601-2640350 SPECIAL DITCH CONTROL, WOOD EXCELSIOR MAT	59.100 SQ	_____._____		_____._____	
0380	2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING	1.030 ACRE	_____._____		_____._____	
0390	2601-2643110 WATERING FOR SOD, SPECIAL DITCH CONTROL, OR SLOPE PROTECTION	19.730 MGAL	75.00000		1,479.75	
0400	2601-2643300 MOBILIZATION FOR WATERING	4.000 EACH	450.00000		1,800.00	
0410	2602-0000309 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 9 IN. DIA.	542.000 LF	_____._____		_____._____	
0420	2602-0000351 REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	786.000 LF	_____._____		_____._____	
0430	2602-0000362 DITCH CHECK SEDIMENT CONTROL DEVICE, 12 IN. DIA.	244.000 LF	_____._____		_____._____	
0440	2602-0010010 MOBILIZATIONS, EROSION CONTROL	4.000 EACH	600.00000		2,400.00	
0450	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	1.000 EACH	1,200.00000		1,200.00	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 77-C077-252 **Call Order:** 005 **Letting Date:** September 15, 2026

Section: 0001 **Total:** _____._____

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 77-C077-252 **Call Order:** 005 **Letting Date:** September 15, 2026

SECTION: 0002

ITEMS FOR A 12'-0 X 8'-0 X 66'-0 TWIN BARREL REINFORCED CONCRETE BOX CULVERT - BROS-C077(253)--5F-77

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0460	2101-0850001 CLEARING AND GRUBBING	0.100 ACRE				
0470	2102-0425070 SPECIAL BACKFILL (STRUCTURE)	165.570 TON				
0480	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	1,567.900 CY				
0490	2102-2710090 EXCAVATION, CLASS 10, WASTE	1,612.900 CY				
0500	2102-2713090 EXCAVATION, CLASS 13, WASTE	10.000 CY				
0510	2104-2710020 EXCAVATION, CLASS 10, CHANNEL	251.100 CY				
0520	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	788.500 CY				
0530	2115-0100000 MODIFIED SUBBASE	360.000 CY				
0540	2123-7450000 SHOULDER CONSTRUCTION, EARTH	12.000 STA				
0550	2312-8260051 GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE	636.900 TON				
0560	2315-8275025 SURFACING, DRIVEWAY, CLASS A CRUSHED STONE	27.500 TON				
0570	2401-6745625 REMOVAL OF EXISTING BRIDGE	 LUMP SUM	 LUMP SUM			

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 77-C077-252 **Call Order:** 005 **Letting Date:** September 15, 2026

SECTION: 0002

ITEMS FOR A 12'-0 X 8'-0 X 66'-0 TWIN BARREL REINFORCED CONCRETE BOX CULVERT - BROS-C077(253)--5F-77

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0580	2402-0425031 GRANULAR BACKFILL	312.260 TON	_____.____		_____.____	
0590	2402-2720000 EXCAVATION, CLASS 20	1,129.100 CY	_____.____		_____.____	
0600	2403-0100020 STRUCTURAL CONCRETE (RCB CULVERT)	214.600 CY	_____.____		_____.____	
0610	2404-7775000 REINFORCING STEEL	34,154.000 LB	_____.____		_____.____	
0620	2417-0225024 APRONS, METAL, 24 IN. DIA.	2.000 EACH	_____.____		_____.____	
0630	2417-1040024 CULVERT, CORRUGATED METAL ENTRANCE PIPE, 24 IN. DIA.	47.000 LF	_____.____		_____.____	
0640	2418-0000010 TEMPORARY STREAM DIVERSION	1.000 EACH	_____.____		_____.____	
0650	2503-0200036 REMOVE STORM SEWER PIPE LESS THAN OR EQUAL TO 36 IN.	31.000 LF	_____.____		_____.____	
0660	2507-6800061 REVETMENT, CLASS E	199.660 TON	_____.____		_____.____	
0670	2519-3280000 FENCE, FIELD	385.000 LF	_____.____		_____.____	
0680	2519-3300400 FIELD FENCE BRACE PANELS	14.000 EACH	_____.____		_____.____	
0690	2519-4200140 REMOVAL OF FENCE, FIELD	354.000 LF	_____.____		_____.____	

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 77-C077-252 **Call Order:** 005 **Letting Date:** September 15, 2026

SECTION: 0002

ITEMS FOR A 12'-0 X 8'-0 X 66'-0 TWIN BARREL REINFORCED CONCRETE BOX CULVERT - BROS-C077(253)--5F-77

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0700	2526-8285010 CONSTRUCTION SURVEY, MONUMENT PRESERVATION	LUMP SUM	LUMP SUM		_____	_____
0710	2526-8285020 CONSTRUCTION SURVEY, CONTROL POINT SURVEY	LUMP SUM	LUMP SUM		_____	_____
0720	2526-8285030 CONSTRUCTION SURVEY, RIGHT OF WAY	LUMP SUM	LUMP SUM		_____	_____
0730	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM		_____	_____
0740	2528-2518000 SAFETY CLOSURE	2.000 EACH	_____	_____	_____	_____
0750	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM		_____	_____
0760	2528-9290050 PORTABLE DYNAMIC MESSAGE SIGN (PDMS)	14.000 CDAY	_____	_____	_____	_____
0770	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
0780	2601-2634110 MULCHING, MECHANICALLY-BONDED FIBER MATRIX	1.790 ACRE	_____	_____	_____	_____
0790	2601-2636043 SEEDING AND FERTILIZING (RURAL)	0.800 ACRE	_____	_____	_____	_____
0800	2601-2638352 SLOPE PROTECTION, WOOD EXCELSIOR MAT	15.000 SQ	_____	_____	_____	_____

IOWA | DOT

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 77-C077-252 **Call Order:** 005 **Letting Date:** September 15, 2026

SECTION: 0002

ITEMS FOR A 12'-0 X 8'-0 X 66'-0 TWIN BARREL REINFORCED CONCRETE BOX CULVERT - BROS-C077(253)--5F-77

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0810	2601-2640350 SPECIAL DITCH CONTROL, WOOD EXCELSIOR MAT	65.000 SQ	_____._____		_____._____	
0820	2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING	0.990 ACRE	_____._____		_____._____	
0830	2601-2643110 WATERING FOR SOD, SPECIAL DITCH CONTROL, OR SLOPE PROTECTION	4.000 MGAL	75.00000		300.00	
0840	2601-2643300 MOBILIZATION FOR WATERING	4.000 EACH	450.00000		1,800.00	
0850	2602-0000309 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 9 IN. DIA.	960.000 LF	_____._____		_____._____	
0860	2602-0000351 REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	1,195.000 LF	_____._____		_____._____	
0870	2602-0000362 DITCH CHECK SEDIMENT CONTROL DEVICE, 12 IN. DIA.	235.000 LF	_____._____		_____._____	
0880	2602-0010010 MOBILIZATIONS, EROSION CONTROL	4.000 EACH	600.00000		2,400.00	
0890	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	1.000 EACH	1,200.00000		1,200.00	

Section: 0002 **Total:** _____._____

Total Bid: _____._____