



CONTRACTS AND SPECIFICATIONS BUREAU Proposal

Proposal ID: 21-0182-142

Letting Date: September 15, 2026

Call Order: 102

Proposal Work Type: PCC PAVEMENT - GRADE AND NEW

DBE Goal: 0.0%

Contracting Authority: IOWA DEPARTMENT OF TRANSPORTATION

Proposal Guaranty: \$375,000.00

This proposal includes the following project(s):

Project Number: HSIPX-018-2(142)--3L-21

County: CLAY

Project Work Type: PCC PAVEMENT - GRADE AND NEW

Route: U.S. 18

Location: N US 71 Intersection in Spencer

Road System: PRIMARY ROAD (on NHS)

Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

Project Number: HSIPX-018-2(143)--3L-21

County: CLAY

Project Work Type: TRAFFIC SIGNS

Route: U.S. 18

Location: N US 71 Intersection in Spencer

Road System: PRIMARY ROAD (on NHS)

Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

Project Number: HSIPX-018-2(144)--3L-21

County: CLAY

Project Work Type: LIGHTING

Route: U.S. 18

Location: N US 71 Intersection in Spencer

Road System: PRIMARY ROAD (on NHS)

Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect



Contracts and Specifications Bureau

8/11/2026 10:46 AM

Contract Time

Proposal ID: 21-0182-142

Call Order: 102

Letting Date: September 15, 2026

Site ID	Site Details				Liquidated Damages
00	Late Start Date	04/05/2027	30	WORK DAYS	\$2,000.00
Completion of Stage 5. See description below.					
01	Late Start Date	04/05/2027	238	CALENDAR DAYS	\$2,000.00
Stages 1 through 4. See description below.					
02	No Start Date Specified		14	CALENDAR DAYS	\$2,000.00
Stage 2A. See description below.					
03	No Start Date Specified		42	CALENDAR DAYS	\$4,000.00
Stage 3. See description below					

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

Contracts and Specifications Bureau

Notes

Proposal ID: 21-0182-142**Call Order:** 102**Letting Date:** September 15, 2026

Notes :*****Site 00****

This site is for the completion of Stage 5, erosion control and seeding for project NSIPX-018-2(142)--3H-21. This site is to be used when no other sites are being charged. Through traffic must be maintained on US 71, US 18, and County Road B19/320th.

*****Site 01*****

This site is an Incentive/Disincentive site per Section 1111 of the Standard Specifications. Incentive/Disincentive/Liquidated Damages Per Day; \$2,000.00.

This site is for all work in Stages 1 through 4 for project HSIPX-018-2(142)--3H-21, all lighting work for project HSIPX-18-2(142)--3L-21, and all signing work for project HSIPX-18-2(144)--3L-21. This site will be considered complete when all lanes, shoulders, roundabout elements, side roads, entrances, and sidewalk/trail are open to traffic and pedestrians with no further closures. This site includes the installation of all signing, striping, and symbols.

*****Site 02*****

This site is an Incentive/Disincentive site per Section 1111 of the Standard Specifications. Incentive/Disincentive/Liquidated Damages Per Day; \$2,000.00.

This site is for the closure of the intersection of B19/230th with 2nd Ave E in Stage 2A for project HSPIX-18-1(142)--3L-21. This site will be considered complete when the B19/230th and 2nd Ave E intersection is opened to traffic with no further closures. This site requires pavement, shoulder, and field entrance to be completed and open to traffic.

*****Site 03*****

This site is an Incentive/Disincentive site per Section 1111 of the Standard Specifications. Incentive/Disincentive/Liquidated Damages Per Day; \$4,000.00.

This site is for the closure of US 18 in Stage 3 for project HSPIX-18-1(142)--3L-21. This site will be considered complete when US 18 is open to traffic without any further closures and traffic is in Stage 4 configuration. This site requires pavement, truck aprons, curb, splitter islands, and shoulders to be open to traffic. This site includes the installation of all signing, striping, and symbols.

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 21-0182-142

Call Order: 102

Letting Date: September 15, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.
410.11	*** STORM WATER POLLUTION PREVENTION PLAN *** A Storm Water Pollution Prevention Plan has been developed by the Contracting Authority for one or more projects on this contract. See the project plans (or other contract document) for specific Storm Water Pollution Prevention Plan details.
500.01	*** WINTER WORK *** The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.
DS-23045	DEVELOPMENTAL SPECIFICATIONS FOR GEOSPATIAL MAPPING OF SUB-SURFACE AND UNDERGROUND UTILITIES
DS-23079	DEVELOPMENTAL SPECIFICATIONS FOR PREFORMED THERMOPLASTIC PAVEMENT MARKINGS
FHWA-1273.09	FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023 23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.
GS-23006	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 21-0182-142

Call Order: 102

Letting Date: September 15, 2026

Note	Description
IA26-28.4	PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20260028 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY) Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract. *** Additional Requirement *** The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.
SP-230422	SPECIAL PROVISIONS FOR COLORED PORTLAND CEMENT CONCRETE Clay County HSIPX-018-2(142)--3H-21



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 21-0182-142

Call Order: 102

Letting Date: September 15, 2026

SECTION: 0001

ROADWAY ITEMS - HSIPX-018-2(142)--3L-21

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2102-0425071 SPECIAL BACKFILL	6,430.630 CY				
0020	2102-2625000 EMBANKMENT-IN-PLACE	11,390.000 CY				
0030	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	15,834.000 CY				
0040	2102-2710090 EXCAVATION, CLASS 10, WASTE	9,158.000 CY				
0050	2102-2712015 EXCAVATION, CLASS 12, BOULDERS OR ROCK FRAGMENTS	5.000 CY				
0060	2102-4560000 LOCATING TILE LINES	103.200 STA				
0070	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	16,864.000 CY				
0080	2107-0875100 COMPACTION WITH MOISTURE CONTROL	23,563.000 CY				
0090	2109-8225100 SPECIAL COMPACTION OF SUBGRADE	40.280 STA				
0100	2115-0100000 MODIFIED SUBBASE	7,898.340 CY				
0110	2121-7425010 GRANULAR SHOULDERS, TYPE A	3,375.500 TON				
0120	2122-5190009 PAVED SHOULDER, P.C. CONCRETE, 9 IN.	1,909.100 SY				



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 21-0182-142

Call Order: 102

Letting Date: September 15, 2026

SECTION: 0001

ROADWAY ITEMS - HSIPX-018-2(142)--3L-21

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	2122-5190095 PAVED SHOULDER, P.C. CONCRETE, 9.5 IN.	4,270.400 SY	_____	_____	_____	_____
0140	2123-7450000 SHOULDER CONSTRUCTION, EARTH	168.600 STA	_____	_____	_____	_____
0150	2123-7450020 SHOULDER FINISHING, EARTH	11.660 STA	_____	_____	_____	_____
0160	2301-1033090 STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 9 IN.	11,648.500 SY	_____	_____	_____	_____
0170	2301-1033095 STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 9.5 IN.	11,088.600 SY	_____	_____	_____	_____
0180	2301-4875006 MEDIAN, P.C. CONCRETE, 6 IN.	1,141.500 SY	_____	_____	_____	_____
0190	2301-7000110 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR PCC PAVEMENT THICKNESS (BY SCHEDULE)	26,602.000 EACH		1.00000		26,602.00
0200	2304-0100000 DETOUR PAVEMENT 9 IN PCC or 12 IN HMA	3,706.400 SY	_____	_____	_____	_____
0210	2312-8260051 GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE	231.500 TON	_____	_____	_____	_____
0220	2315-8275055 SURFACING, DRIVEWAY	457.900 TON	_____	_____	_____	_____



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 21-0182-142

Call Order: 102

Letting Date: September 15, 2026

SECTION: 0001

ROADWAY ITEMS - HSIPX-018-2(142)--3L-21

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0230	2317-7000110 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR PCC PAVEMENT SMOOTHNESS (BY SCHEDULE)	17,053.000 EACH		1.00000	17,053.00	
0240	2402-0425040 FLOODED BACKFILL	166.800 CY				
0250	2402-2720100 EXCAVATION, CLASS 20, FOR ROADWAY PIPE CULVERT	139.800 CY				
0260	2416-0100012 APRONS, CONCRETE, 12 IN. DIA.	1.000 EACH				
0270	2416-0100015 APRONS, CONCRETE, 15 IN. DIA.	14.000 EACH				
0280	2416-0100018 APRONS, CONCRETE, 18 IN. DIA.	1.000 EACH				
0290	2416-0100024 APRONS, CONCRETE, 24 IN. DIA.	6.000 EACH				
0300	2416-0102224 APRON, LOW CLEARANCE CONCRETE, EQUIVALENT DIAMETER 24 IN.	6.000 EACH				
0310	2416-0102236 APRON, LOW CLEARANCE CONCRETE, EQUIVALENT DIAMETER 36 IN.	4.000 EACH				
0320	2416-1180018 CULVERT, CONCRETE ROADWAY PIPE, 18 IN. DIA.	8.000 LF				



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 21-0182-142

Call Order: 102

Letting Date: September 15, 2026

SECTION: 0001

ROADWAY ITEMS - HSIPX-018-2(142)--3L-21

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0330	2416-1180024 CULVERT, CONCRETE ROADWAY PIPE, 24 IN. DIA.	206.000 LF				
0340	2416-1190224 CULVERT, LOW CLEARANCE CONCRETE ENTRANCE PIPE, EQUIVALENT DIAMETER 24 IN.	58.000 LF				
0350	2416-1200224 CULVERT, LOW CLEARANCE CONCRETE ROADWAY PIPE, EQUIVALENT DIAMETER 24 IN.	72.000 LF				
0360	2416-1200236 CULVERT, LOW CLEARANCE CONCRETE ROADWAY PIPE, EQUIVALENT DIAMETER 36 IN.	2.000 LF				
0370	2422-0360000 UNCLASSIFIED APRONS, 12 IN. DIA.	4.000 EACH				
0380	2422-0360024 APRONS, UNCLASSIFIED, 24 IN. DIA.	2.000 EACH				
0390	2422-1720000 UNCLASSIFIED PIPE CULVERT, 12 IN. DIA.	108.000 LF				
0400	2422-1723024 CULVERT, UNCLASSIFIED ROADWAY PIPE, 24 IN. DIA.	188.000 LF				
0410	2435-0140148 MANHOLE, STORM SEWER, SW-401, 48 IN.	1.000 EACH				
0420	2435-0250100 INTAKE, SW-501	8.000 EACH				



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 21-0182-142

Call Order: 102

Letting Date: September 15, 2026

SECTION: 0001

ROADWAY ITEMS - HSIPX-018-2(142)--3L-21

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0430	2435-0250248 INTAKE, SW-502, 48 IN.	14.000 EACH				
0440	2435-0250700 INTAKE, SW-507	6.000 EACH				
0450	2435-0254100 INTAKE, SW-541	2.000 EACH				
0460	2502-6745952 REMOVAL OF SUBDRAIN	2,063.700 LF				
0470	2502-8212034 SUBDRAIN, LONGITUDINAL, (SHOULDER) 4 IN. DIA.	4,527.100 LF				
0480	2502-8221303 SUBDRAIN OUTLET, DR-303	8.000 EACH				
0490	2502-8221306 SUBDRAIN OUTLET, DR-306	20.000 EACH				
0500	2503-0114212 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 12 IN.	32.000 LF				
0510	2503-0114215 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 15 IN.	1,150.000 LF				
0520	2506-4984000 FLOWABLE MORTAR	68.500 CY				
0530	2510-6745850 REMOVAL OF PAVEMENT	32,336.400 SY				



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 21-0182-142

Call Order: 102

Letting Date: September 15, 2026

SECTION: 0001

ROADWAY ITEMS - HSIPX-018-2(142)--3L-21

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0540	2511-7526006 SIDEWALK, P.C. CONCRETE, 6 IN.	868.700 SY				
0550	2511-7528101 DETECTABLE WARNINGS	200.000 SF				
0560	2512-1725256 CURB AND GUTTER, P.C. CONCRETE, 2.5 FT.	3,145.600 LF				
0570	2512-1725306 CURB AND GUTTER, P.C. CONCRETE, 3.0 FT.	427.300 LF				
0580	2515-2475008 DRIVEWAY, P.C. CONCRETE, 8 IN.	1,485.800 SY				
0590	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM			
0600	2527-9263155 PRE-CUT SYMBOLS AND LEGENDS, PREFORMED THERMOPLASTIC MARKING MATERIAL	14.000 EACH				
0610	2527-9263181 PAVEMENT MARKINGS REMOVED	320.590 STA				
0620	2527-9263209 PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	488.500 STA				
0630	2527-9263212 PAINTED PAVEMENT MARKINGS, HIGH-BUILD WATERBORNE	151.120 STA				
0640	2527-9263225 PERMANENT TAPE MARKINGS, PREFORMED THERMOPLASTIC MARKING MATERIAL	17.540 STA				



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 21-0182-142

Call Order: 102

Letting Date: September 15, 2026

SECTION: 0001

ROADWAY ITEMS - HSIPX-018-2(142)--3L-21

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0650	2527-9263231 REMOVABLE TAPE MARKINGS, WET RETROREFLECTIVE	133.780 STA				
0660	2527-9270112 GROOVES CUT FOR PAVEMENT MARKINGS	297.080 STA				
0670	2527-9270120 GROOVES CUT FOR SYMBOLS AND LEGENDS	14.000 EACH				
0680	2528-2518000 SAFETY CLOSURE	20.000 EACH				
0690	2528-8400157 TEMPORARY FLOODLIGHTING LUMINAIRE	8.000 EACH				
0700	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
0710	2528-9109020 TEMPORARY LANE SEPARATOR SYSTEM	3,080.000 LF				
0720	2528-9290050 PORTABLE DYNAMIC MESSAGE SIGN (PDMS)	100.000 CDAY				
0730	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
0740	2599-9999018 (‘SQUARE YARDS’ ITEM) STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 13.5 IN.	2,049.400 SY				
Section: 0001			Total:			



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 21-0182-142

Call Order: 102

Letting Date: September 15, 2026

SECTION: 0002

EROSION CONTROL ITEMS - HSIPX-018-2(142)--3L-21

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0750	2507-3250005 ENGINEERING FABRIC	400.900 SY				
0760	2507-8029000 EROSION STONE	220.200 TON				
0770	2601-2634100 MULCHING	17.300 ACRE				
0780	2601-2636043 SEEDING AND FERTILIZING (RURAL)	9.600 ACRE				
0790	2601-2636044 SEEDING AND FERTILIZING (URBAN)	4.600 ACRE				
0800	2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING	9.600 ACRE				
0810	2601-2642120 STABILIZING CROP - SEEDING AND FERTILIZING (URBAN)	4.600 ACRE				
0820	2601-2643110 WATERING FOR SOD, SPECIAL DITCH CONTROL, OR SLOPE PROTECTION	1.500 MGAL		75.00000		112.50
0830	2601-2643300 MOBILIZATION FOR WATERING	3.000 EACH		450.00000		1,350.00
0840	2601-2700020 TRANSITION MAT	729.000 SF				
0850	2602-0000020 SILT FENCE	1,314.000 LF				
0860	2602-0000030 SILT FENCE FOR DITCH CHECKS	1,350.000 LF				



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 21-0182-142

Call Order: 102

Letting Date: September 15, 2026

SECTION: 0002

EROSION CONTROL ITEMS - HSIPX-018-2(142)--3L-21

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0870	2602-0000071 REMOVAL OF SILT FENCE OR SILT FENCE FOR DITCH CHECKS	2,664.000 LF				
0880	2602-0000101 MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	266.000 LF				
0890	2602-0000150 STABILIZED CONSTRUCTION ENTRANCE, EC-303	500.000 LF				
0900	2602-0000312 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	370.000 LF				
0910	2602-0000320 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 20 IN. DIA.	370.000 LF				
0920	2602-0000351 REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	1,880.000 LF				
0930	2602-0000362 DITCH CHECK SEDIMENT CONTROL DEVICE, 12 IN. DIA.	570.000 LF				
0940	2602-0000370 DITCH CHECK SEDIMENT CONTROL DEVICE, 20 IN. DIA.	570.000 LF				
0950	2602-0000530 GRATE INTAKE SEDIMENT FILTER BAG, EC-604	33.000 EACH				
0960	2602-0000540 MAINTENANCE OF GRATE INTAKE SEDIMENT FILTER BAG	33.000 EACH				



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 21-0182-142

Call Order: 102

Letting Date: September 15, 2026

SECTION: 0002

EROSION CONTROL ITEMS - HSIPX-018-2(142)--3L-21

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0970	2602-0000550 REMOVAL OF GRATE INTAKE SEDIMENT FILTER BAG	33.000 EACH				
0980	2602-0010010 MOBILIZATIONS, EROSION CONTROL	1.000 EACH		600.00000		600.00
0990	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	1.000 EACH		1,200.00000		1,200.00
Section: 0002			Total:			



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 21-0182-142

Call Order: 102

Letting Date: September 15, 2026

SECTION: 0003

TRAFFIC SIGN ITEMS - HSIPX-018-2(143)--3L-21

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1000	2524-6765210 REMOVAL OF TYPE A SIGN ASSEMBLY	40.000 EACH	_____	_____	_____	_____
1010	2524-6765220 REMOVAL OF TYPE B SIGN ASSEMBLY	2.000 EACH	_____	_____	_____	_____
1020	2524-9081275 CONCRETE FOOTING FOR BREAKAWAY SIGN POST, 2'-8" DIA. X 7'-6"	4.000 EACH	_____	_____	_____	_____
1030	2524-9276010 PERFORATED SQUARE STEEL TUBE POSTS	403.000 LF	_____	_____	_____	_____
1040	2524-9276027 PERFORATED SQUARE STEEL TUBE POST ANCHOR, TRIANGULAR SLIP BASE ASSEMBLY	81.000 EACH	_____	_____	_____	_____
1050	2524-9281210 STEEL BREAKAWAY SIGN POSTS FOR TYPE A OR B SIGNS, W 8 X 21	152.950 LF	_____	_____	_____	_____
1060	2524-9290009 SIGN MOUNTING BRACKETS, SPECIAL	14.000 EACH	_____	_____	_____	_____
1070	2524-9325001 TYPE A SIGNS, SHEET ALUMINUM	392.900 SF	_____	_____	_____	_____
1080	2524-9380001 TYPE B SIGNS, EXTRUDED ALUMINUM STRUCTURAL PANEL	202.900 SF	_____	_____	_____	_____
1090	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM		_____	_____
1100	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 21-0182-142

Call Order: 102

Letting Date: September 15, 2026

SECTION: 0003

TRAFFIC SIGN ITEMS - HSIPX-018-2(143)--3L-21

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1110	2555-0000010 DELIVER AND STOCKPILE SALVAGED MATERIALS	LUMP SUM	LUMP SUM		_____.	
Section: 0003			Total:		_____.	



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 21-0182-142

Call Order: 102

Letting Date: September 15, 2026

SECTION: 0004

LIGHTING ITEMS - HSIPX-018-2(144)--3L-21

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1120	2401-6745356 REMOVAL OF CONCRETE FOOTINGS OF LIGHT POLES	5.000 EACH	_____	_____	_____	_____
1130	2401-6745765 REMOVAL OF LIGHT POLES	5.000 EACH	_____	_____	_____	_____
1140	2401-6750001 REMOVALS, AS PER PLAN	LUMP SUM	LUMP SUM		_____	_____
1150	2523-0000100 LIGHTING POLES	10.000 EACH	_____	_____	_____	_____
1160	2523-0000200 ELECTRICAL CIRCUITS	1,688.000 LF	_____	_____	_____	_____
1170	2523-0000310 HANDHOLES AND JUNCTION BOXES	3.000 EACH	_____	_____	_____	_____
1180	2523-0000400 CONTROL CABINET	1.000 EACH	_____	_____	_____	_____
1190	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM		_____	_____
1200	2526-9000000 GEOSPATIAL MAPPING OF SUB- SURFACE AND UNDERGROUND UTILITIES	1,688.000 LF	_____	_____	_____	_____
1210	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM		_____	_____
1220	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
Section: 0004			Total:		_____	_____
			Total Bid:		_____	_____

