



CONTRACTS AND SPECIFICATIONS BUREAU Proposal

Proposal ID: 57-1187-801 **Letting Date:** September 15, 2026
Call Order: 104
Proposal Work Type: PCC SIDEWALK/TRAIL
DBE Goal: 0.0%
Contracting Authority: CITY OF CEDAR RAPIDS
Proposal Guaranty: \$100,000.00

This proposal includes the following project(s):

Project Number: TAP-U-1187(801)--8I-57	County: LINN
Project Work Type: PCC SIDEWALK/TRAIL	Route: CHEROKEE TRAIL
Location: In the city of Cedar Rapids, along F Ave NW from Westwood Dr NW to 13th St NW	
Road System: UNDEFINED - OFF SYSTEM	
Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect	

Contract Time

Proposal ID: 57-1187-801

Call Order: 104

Letting Date: September 15, 2026

Site ID	Site Details			Liquidated Damages
00	Late Start Date	04/26/2027	70 WORK DAYS	\$1,000.00

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit



Contracts and Specifications Bureau

8/11/2026 10:46 AM

Notes

Proposal ID: 57-1187-801

Call Order: 104

Letting Date: September 15, 2026

Notes :

***Winter Work ***

Winter Work will be allowed during the winter 2026/2027 for work that does not impact/remove existing roadway pavement or existing sidewalks. No working days will be charged for this work between November 15, 2026 and April 1, 2027.

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 57-1187-801

Call Order: 104

Letting Date: September 15, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.
500.2027	*** NO WINTER FREE TIME *** The free time allowed between November 15 and April 1 will not be permitted on this project during the winter of 2027-2028. The Contractor shall work during the winter on all working days as defined in article 1101.03 'working day'.
FHWA-1273.09	FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023 23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.
GS-23006	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION
IA26-28.4	PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20260028 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY) Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract. *** Additional Requirement *** The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 57-1187-801

Call Order: 104

Letting Date: September 15, 2026

Note	Description
SP-236076	SPECIAL PROVISIONS FOR ICN FACILITIES Linn County TAP-U-1187(801)--8I-57
SP-236077	SPECIAL PROVISIONS FOR VALVES, FIRE HYDRANTS, AND APPURTENANCES Linn County TAP-U-1187(801)--8I-57
SP-236078	SPECIAL PROVISIONS FOR WATER MAIN PIPE AND FITTINGS Linn County TAP-U-1187(801)--8I-57
SP-236079	SPECIAL PROVISIONS FOR TACTILE DIRECTIONAL INDICATOR Linn County TAP-U-1187(801)--8I-57
SP-236080	SPECIAL PROVISIONS FOR SAFETY RAIL Linn County TAP-U-1187(801)--8I-57
SP-236081	SPECIAL PROVISIONS FOR INSURANCE REQUIREMENTS Linn County TAP-U-1187(801)--8I-57
SP-236082	SPECIAL PROVISIONS FOR INLINE DRAIN, PVC, 8 IN. Linn County TAP-U-1187(801)--8I-57
SP-236083	SPECIAL PROVISIONS FOR RECTANGULAR RAPID FLASHING BEACON ASSEMBLY Linn County TAP-U-1187(801)--8I-57



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-1187-801

Call Order: 104

Letting Date: September 15, 2026

SECTION: 0001

TRAIL ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	3,053.000 CY	_____	_____	_____	_____
0020	2102-2710090 EXCAVATION, CLASS 10, WASTE	721.000 CY	_____	_____	_____	_____
0030	2105-8425005 TOPSOIL, FURNISH AND SPREAD	882.000 CY	_____	_____	_____	_____
0040	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	882.000 CY	_____	_____	_____	_____
0050	2111-8174100 GRANULAR SUBBASE	3,812.000 SY	_____	_____	_____	_____
0060	2113-0001100 SUBGRADE STABILIZATION MATERIAL, POLYMER GRID	1,108.000 SY	_____	_____	_____	_____
0070	2115-0100000 MODIFIED SUBBASE	923.000 CY	_____	_____	_____	_____
0080	2122-5190012 PAVED SHOULDER, P.C. CONCRETE, 12 IN.	725.600 SY	_____	_____	_____	_____
0090	2123-7450020 SHOULDER FINISHING, EARTH	36.200 STA	_____	_____	_____	_____
0100	2210-0475105 CHOKE STONE BASE	12.300 TON	_____	_____	_____	_____
0110	2210-0475290 MACADAM STONE BASE	79.600 TON	_____	_____	_____	_____



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-1187-801

Call Order: 104

Letting Date: September 15, 2026

SECTION: 0001

TRAIL ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	2301-1032100 STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 2 DURABILITY, 10 IN.	865.500 SY				
0130	2301-6911722 PORTLAND CEMENT CONCRETE PAVEMENT SAMPLES	LUMP SUM	LUMP SUM			
0140	2431-0000100 SEGMENTAL BLOCK RETAINING WALL	525.000 SF				
0150	2435-0140148 MANHOLE, STORM SEWER, SW-401, 48 IN.	1.000 EACH				
0160	2435-0140172 MANHOLE, STORM SEWER, SW-401, 72 IN.	1.000 EACH				
0170	2435-0140600 MANHOLE, STORM SEWER, SW-406	1.000 EACH				
0180	2435-0250100 INTAKE, SW-501	1.000 EACH				
0190	2435-0250500 INTAKE, SW-505	1.000 EACH				
0200	2435-0250700 INTAKE, SW-507	1.000 EACH				
0210	2435-0250900 INTAKE, SW-509	2.000 EACH				
0220	2435-0251224 INTAKE, SW-512, 24 IN.	7.000 EACH				



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-1187-801

Call Order: 104

Letting Date: September 15, 2026

SECTION: 0001

TRAIL ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0230	2435-0251300 INTAKE, SW-513	1.000 EACH				
0240	2435-0600010 MANHOLE ADJUSTMENT, MINOR	2.000 EACH				
0250	2435-0600020 MANHOLE ADJUSTMENT, MAJOR	3.000 EACH				
0260	2435-0600110 INTAKE ADJUSTMENT, MINOR	1.000 EACH				
0270	2502-8212206 SUBDRAIN, PERFORATED PLASTIC PIPE, 6 IN. DIA.	3,559.000 LF				
0280	2502-8221303 SUBDRAIN OUTLET, DR-303	5.000 EACH				
0290	2502-8221306 SUBDRAIN OUTLET, DR-306	15.000 EACH				
0300	2503-0112010 STORM SEWER GRAVITY MAIN, TRENCHED, POLYVINYL CHLORIDE PIPE (PVC), 10 IN.	36.000 LF				
0310	2503-0114212 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 12 IN.	438.000 LF				
0320	2503-0114215 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 15 IN.	386.000 LF				



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-1187-801

Call Order: 104

Letting Date: September 15, 2026

SECTION: 0001

TRAIL ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0330	2503-0114218 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 18 IN.	14.000 LF				
0340	2503-0114224 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 24 IN.	20.000 LF				
0350	2503-0114236 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 36 IN.	14.000 LF				
0360	2503-0200036 REMOVE STORM SEWER PIPE LESS THAN OR EQUAL TO 36 IN.	268.000 LF				
0370	2507-8029000 EROSION STONE	25.100 TON				
0380	2510-6745850 REMOVAL OF PAVEMENT	2,059.900 SY				
0390	2510-6750600 REMOVAL OF INTAKES AND UTILITY ACCESSES	5.000 EACH				
0400	2511-0302600 RECREATIONAL TRAIL, PORTLAND CEMENT CONCRETE, 6 IN.	4,118.900 SY				
0410	2511-0310100 SPECIAL COMPACTION OF SUBGRADE FOR RECREATIONAL TRAIL	36.200 STA				



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-1187-801

Call Order: 104

Letting Date: September 15, 2026

SECTION: 0001

TRAIL ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0420	2511-6745900 REMOVAL OF SIDEWALK	385.700 SY				
0430	2511-7526004 SIDEWALK, P.C. CONCRETE, 4 IN.	176.900 SY				
0440	2511-7526006 SIDEWALK, P.C. CONCRETE, 6 IN.	69.800 SY				
0450	2511-7528101 DETECTABLE WARNINGS	297.000 SF				
0460	2512-1725206 CURB AND GUTTER, P.C. CONCRETE, 2.0 FT.	523.000 LF				
0470	2512-1725256 CURB AND GUTTER, P.C. CONCRETE, 2.5 FT.	307.000 LF				
0480	2512-1725356 CURB AND GUTTER, P.C. CONCRETE, 3.5 FT.	86.300 LF				
0490	2512-1725406 CURB AND GUTTER, P.C. CONCRETE, 4.0 FT.	57.300 LF				
0500	2515-2475006 DRIVEWAY, P.C. CONCRETE, 6 IN.	140.400 SY				
0510	2515-6745600 REMOVAL OF PAVED DRIVEWAY	142.000 SY				
0520	2524-6765110 REMOVAL OF TYPE A SIGN	7.000 EACH				
0530	2524-9276010 PERFORATED SQUARE STEEL TUBE POSTS	126.000 LF				



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-1187-801

Call Order: 104

Letting Date: September 15, 2026

SECTION: 0001

TRAIL ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0540	2524-9276027 PERFORATED SQUARE STEEL TUBE POST ANCHOR, TRIANGULAR SLIP BASE ASSEMBLY	9.000 EACH				
0550	2524-9325001 TYPE A SIGNS, SHEET ALUMINUM	94.700 SF				
0560	2526-8285010 CONSTRUCTION SURVEY, MONUMENT PRESERVATION	LUMP SUM	LUMP SUM			
0570	2526-8285020 CONSTRUCTION SURVEY, CONTROL POINT SURVEY	LUMP SUM	LUMP SUM			
0580	2526-8285030 CONSTRUCTION SURVEY, RIGHT OF WAY	LUMP SUM	LUMP SUM			
0590	2526-8285040 CONSTRUCTION SURVEY, LOCATION SURVEY	LUMP SUM	LUMP SUM			
0600	2527-9263143 PAINTED SYMBOLS AND LEGENDS, DURABLE	2.000 EACH				
0610	2527-9263181 PAVEMENT MARKINGS REMOVED	1.900 STA				
0620	2527-9263217 PAINTED PAVEMENT MARKINGS, DURABLE	90.520 STA				
0630	2527-9263231 REMOVABLE TAPE MARKINGS, WET RETROREFLECTIVE	22.510 STA				
0640	2527-9270112 GROOVES CUT FOR PAVEMENT MARKINGS	90.520 STA				



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-1187-801

Call Order: 104

Letting Date: September 15, 2026

SECTION: 0001

TRAIL ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0650	2527-9270120 GROOVES CUT FOR SYMBOLS AND LEGENDS	2.000 EACH	_____	_____	_____	_____
0660	2528-2518000 SAFETY CLOSURE	4.000 EACH	_____	_____	_____	_____
0670	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM		_____	_____
0680	2528-9290050 PORTABLE DYNAMIC MESSAGE SIGN (PDMS)	10.000 CDAY	_____	_____	_____	_____
0690	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
0700	2548-0000200 MILLED SHOULDER RUMBLE STRIPS, PCC SURFACE	25.400 STA	_____	_____	_____	_____
0710	2599-9999005 ('EACH' ITEM) HANDHOLE	2.000 EACH	_____	_____	_____	_____
0720	2599-9999005 ('EACH' ITEM) INLINE DRAIN, PVC, 8 IN.	1.000 EACH	_____	_____	_____	_____
0730	2599-9999005 ('EACH' ITEM) RECTANGULAR RAPID FLASHING BEACON (RRFB) ASSEMBLY	3.000 EACH	_____	_____	_____	_____
0740	2599-9999005 ('EACH' ITEM) RELOCATION OF HANDHOLE	1.000 EACH	_____	_____	_____	_____
0750	2599-9999005 ('EACH' ITEM) UTILITY CROSSING REINFORCEMENT	4.000 EACH	_____	_____	_____	_____



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-1187-801

Call Order: 104

Letting Date: September 15, 2026

SECTION: 0001

TRAIL ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0760	2599-9999005 (‘EACH’ ITEM) VALVE BOX ADJUSTMENT, WATER MAIN	5.000 EACH				
0770	2599-9999005 (‘EACH’ ITEM) VALVE BOX ADJUSTMENT, WATER SERVICE	1.000 EACH				
0780	2599-9999005 (‘EACH’ ITEM) WATER SERVICE STUB, TYPE K, 1 IN., TRENCHED	1.000 EACH				
0790	2599-9999009 (‘LINEAR FEET’ ITEM) CONDUIT, TRENCHED	267.000 LF				
0800	2599-9999009 (‘LINEAR FEET’ ITEM) SAFETY RAIL	210.000 LF				
0810	2599-9999009 (‘LINEAR FEET’ ITEM) TACTILE DIRECTIONAL INDICATOR	14.000 LF				
0820	2601-2639010 SODDING	715.000 SQ				
0830	2601-2643110 WATERING FOR SOD, SPECIAL DITCH CONTROL, OR SLOPE PROTECTION	343.000 MGAL		75.00000		25,725.00
0840	2601-2643300 MOBILIZATION FOR WATERING	5.000 EACH		450.00000		2,250.00
0850	2602-0000020 SILT FENCE	4,006.000 LF				
0860	2602-0000071 REMOVAL OF SILT FENCE OR SILT FENCE FOR DITCH CHECKS	4,006.000 LF				



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 57-1187-801

Call Order: 104

Letting Date: September 15, 2026

SECTION: 0001

TRAIL ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0870	2602-0000101 MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	401.000 LF	_____	_____	_____	_____
0880	2602-0000150 STABILIZED CONSTRUCTION ENTRANCE, EC-303	300.000 LF	_____	_____	_____	_____
0890	2602-0000309 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 9 IN. DIA.	4,370.000 LF	_____	_____	_____	_____
0900	2602-0000351 REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	4,370.000 LF	_____	_____	_____	_____
0910	2602-0010010 MOBILIZATIONS, EROSION CONTROL	5.000 EACH		600.00000		3,000.00
Section: 0001			Total:		_____	
			Total Bid:		_____	