



**CONTRACTS AND SPECIFICATIONS BUREAU
Proposal**

Proposal ID: 07-8155-788

Letting Date: September 15, 2026

Call Order: 301

Proposal Work Type: PRECAST RCB CULVERT

DBE Goal: 0.0%

Contracting Authority: CITY OF WATERLOO

Proposal Guaranty: \$50,000.00

This proposal includes the following project(s):

Project Number: TAP-U-8155(788)--8I-07

County: BLACK HAWK

Project Work Type: PRECAST RCB CULVERT

Route: SERGEANT RD TRAIL

Location: In the city of Waterloo, On Sergeant Rd Trail BRs, from 550' SW of W Shaulis Rd NE 4.1 miles to 90' NE of W 3rd St

Road System: UNDEFINED - OFF SYSTEM

Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect

Contract Time

Proposal ID: 07-8155-788

Call Order: 301

Letting Date: September 15, 2026

Site ID	Site Details			Liquidated Damages
00	Late Start Date	08/09/2027	55 WORK DAYS	\$1,000.00

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit

Notes

Proposal ID: 07-8155-788

Call Order: 301

Letting Date: September 15, 2026

Notes :

There are no notes for this proposal.

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 07-8155-788

Call Order: 301

Letting Date: September 15, 2026

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.
500.07.2026	*** WINTER WORK *** Winter Work will be allowed during the winter 2026/2027. No working days will be charged between November 15, 2026 and April 1, 2027.
500.2027	*** NO WINTER FREE TIME *** The free time allowed between November 15 and April 1 will not be permitted on this project during the winter of 2027-2028. The Contractor shall work during the winter on all working days as defined in article 1101.03 'working day'.
DS-23010	DEVELOPMENTAL SPECIFICATIONS FOR PRECAST REINFORCED CONCRETE THREE-SIDED CULVERT
FHWA-1273.09	FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023 23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.
GS-23006	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 07-8155-788

Call Order: 301

Letting Date: September 15, 2026

Note	Description
IA26-28.4	PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20260028 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY) Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract. *** Additional Requirement *** The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 07-8155-788

Call Order: 301

Letting Date: September 15, 2026

SECTION: 0001

ITEMS FOR PRECAST REINFORCED CONCRETE BOX CULVERTS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2101-0850001 CLEARING AND GRUBBING	1.510 ACRE				
0020	2102-2625000 EMBANKMENT-IN-PLACE	204.000 CY				
0030	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	1,024.100 CY				
0040	2102-2710090 EXCAVATION, CLASS 10, WASTE	1,812.500 CY				
0050	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	1,884.500 CY				
0060	2107-3825025 GRANULAR MATERIAL FOR BLANKET AND SUBDRAIN	51.300 CY				
0070	2115-0100000 MODIFIED SUBBASE	150.000 CY				
0080	2121-7425020 GRANULAR SHOULDERS, TYPE B	63.000 TON				
0090	2210-0475290 MACADAM STONE BASE	179.400 TON				
0100	2401-6745625 REMOVAL OF EXISTING BRIDGE	LUMP SUM	LUMP SUM			
0110	2401-6745650 REMOVAL OF EXISTING STRUCTURES	LUMP SUM	LUMP SUM			
0120	2415-2110806 PRECAST CONCRETE BOX CULVERT, 8 FT. X 6 FT.	62.000 LF				



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 07-8155-788

Call Order: 301

Letting Date: September 15, 2026

SECTION: 0001

ITEMS FOR PRECAST REINFORCED CONCRETE BOX CULVERTS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	2415-2111004 PRECAST CONCRETE BOX CULVERT, 10 FT. X 4 FT.	36.000 LF	_____	_____	_____	_____
0140	2415-3510000 PRECAST CONCRETE WINGWALL	8.000 EACH	_____	_____	_____	_____
0150	2416-0100048 APRONS, CONCRETE, 48 IN. DIA.	14.000 EACH	_____	_____	_____	_____
0160	2416-1165048 CULVERT, 2000D CONCRETE ENTRANCE PIPE, 48 IN. DIA.	320.000 LF	_____	_____	_____	_____
0170	2435-0251230 INTAKE, SW-512, 30 IN.	1.000 EACH	_____	_____	_____	_____
0180	2435-0700010 CONNECTION TO EXISTING MANHOLE	1.000 EACH	_____	_____	_____	_____
0190	2502-8212204 SUBDRAIN, PERFORATED PLASTIC PIPE, 4 IN. DIA.	284.000 LF	_____	_____	_____	_____
0200	2502-8221303 SUBDRAIN OUTLET, DR-303	8.000 EACH	_____	_____	_____	_____
0210	2503-0114224 STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 24 IN.	112.000 LF	_____	_____	_____	_____
0220	2507-6800042 REVTMENT, CLASS D	285.000 TON	_____	_____	_____	_____
0230	2507-8029000 EROSION STONE	497.100 TON	_____	_____	_____	_____



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 07-8155-788

Call Order: 301

Letting Date: September 15, 2026

SECTION: 0001

ITEMS FOR PRECAST REINFORCED CONCRETE BOX CULVERTS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	2511-0300000 REMOVAL OF RECREATIONAL TRAIL	501.200 SY	_____	_____	_____	_____
0250	2511-0302600 RECREATIONAL TRAIL, PORTLAND CEMENT CONCRETE, 6 IN.	501.200 SY	_____	_____	_____	_____
0260	2524-9100020 OBJECT MARKER, TYPE 2	12.000 EACH	_____	_____	_____	_____
0270	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM		_____	_____
0280	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
0290	2601-2634150 MULCHING, WOOD CELLULOSE FIBER	1.180 ACRE	_____	_____	_____	_____
0300	2601-2636041 SEEDING AND FERTILIZING	1.180 ACRE	_____	_____	_____	_____
0310	2601-2638352 SLOPE PROTECTION, WOOD EXCELSIOR MAT	487.100 SQ	_____	_____	_____	_____
0320	2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING	1.180 ACRE	_____	_____	_____	_____
0330	2601-2643411 TURF REINFORCEMENT MAT, TYPE 1	21.600 SQ	_____	_____	_____	_____
0340	2602-0000020 SILT FENCE	1,068.000 LF	_____	_____	_____	_____
0350	2602-0000071 REMOVAL OF SILT FENCE OR SILT FENCE FOR DITCH CHECKS	1,068.000 LF	_____	_____	_____	_____



8/11/2026 10:46 AM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 07-8155-788

Call Order: 301

Letting Date: September 15, 2026

SECTION: 0001

ITEMS FOR PRECAST REINFORCED CONCRETE BOX CULVERTS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0360	2602-0000101 MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	1,068.000 LF				
0370	2602-0000150 STABILIZED CONSTRUCTION ENTRANCE, EC-303	475.000 LF				
0380	2602-0000309 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 9 IN. DIA.	2,066.000 LF				
0390	2602-0000351 REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	2,066.000 LF				
0400	2602-0010010 MOBILIZATIONS, EROSION CONTROL	6.000 EACH		600.00000		3,600.00
0410	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	6.000 EACH		1,200.00000		7,200.00
Section: 0001			Total:			
			Total Bid:			